

<b>Unit Description</b>	<b>Units</b>	<b>Material Supplied By</b>	<b>Model # and Description</b>	<b>Units</b>
INNERDUCT, 3X1.25IN,	<b>FT</b>	ARRC	1.25" SDR-11 HDPE-DURA-LINE 2030036710, 3 way reel,	<b>13500</b>
INNERDUCT, 3.5in ID, BLK	<b>FT</b>	Contractor	4" SDR 11 HDPE BLK	<del>As needed</del>
HANDHOLE	<b>Ea</b>	Owner	MODEL NUMBER: BULKU3048360171000	<b>7</b>
	<b>Ea</b>	Contractor	POST, WOOD, RECT, 3.5x4.5IN x 8FT	<b>7</b>
	<b>Ea</b>	Contractor	MARKER, YLW, 4FT, WITH CLAMPS	<b>7</b>
	<b>Ea</b>	Contractor	SIGN BLANK YELLOW (MOUNTED TO POST)	<b>7</b>
30X30X12" STAINLESS STEEL NEMA BOX MOUNTING AND HARDWARE INSTALLATION	<b>Ea</b>	Contractor	KIT-NEMA 4X HOFFMAN A48H3612SS6LP ENCLOSURE. STAINLESS-STEEL (48X36X12) CONTINUOUS HINGE AND STAINLESS-STEEL DOOR CLAMP ASSEMBLY. HASP AND STAPLE FOR PADLOCKING	
2" Flexible Metallic Liquid Tight Conduit	<b>FT</b>	Contractor	2" Flexible Metallic Liquid Tight Conduit	<b>As needed</b>
Pre Term, 12 strand	<b>Ea</b>	Contractor	Preterm Assembly, cable, 50' 12 Fiber, SC-APC, SM Loose Tube, All Weather, Breakout, 18"	<b>2</b>
Fiber Splice Case	<b>Ea</b>	Contractor	Outdoor Rated Fiber Splice Case & Tray(s)	<b>2</b>
CABLE F/O 144 - Single jkt, Light armor,	<b>FT</b>	Owner	Lexington Ames-LA-LT-041-144-12-D0-PM	<b>5000</b>
SIGN WARNING FO BURIED CABLE	<b>EA</b>	Contractor	SIGN WARNING FO BURIED CABLE	<b>12</b>

**\*\*Contractor to identify and provide any additional materials not on the list to complete the project\***