



**Alaska Railroad Corporation  
327 W. Ship Creek Ave.  
Anchorage, AK 99501**

**June 12, 2024**

### **Addendum 3**

**ITB #24-40-212083**

Fiber Optic Cable Installation: Portage

### **Addendum number 3 has been issued for Questions.**

**The Closing Date for this ITB has not changed.  
Bids will be received until June 13, 2024 @ 3:00 PM Alaska time.**

---

### **Questions:**

1. There are no NEMA Enclosures listed in the Bill of Materials (BOM). Are they required at each of the Control Points for new duct entry, if so are they being furnished by the ARRC. If we are not to use NEMA Enclosures what is the preferred method for duct entry into the CPs.  
*There are no NEMA enclosures to be installed at the CPs. 2" conduit will enter the CP and PreTerm cables (2 ea) will be pulled in and terminated on Railroad supplied panels. Method of enter will be via existing holes or drill through sub floors.*
2. Addendum 1 revised the BOM and added the 2" and 4" Rolled conduit listed as items 11 and 12, these are not shown on the drawings. We can make assumptions but would like clarification on where these ducts are being installed.  
*4" Rolled conduit is for Track and or Road crossings. 2" is for CP entrances as there will be 2 cables(in/out) serving each CO.*
3. Addendum 2 Question 2 answer says "ARRC will forward splicing and terminating material lists". Will this list be provided with quantities for base bid and alt bid.  
*If optional work is awarded, the material and material list will be provided.*
4. Addendum 2 issued a new Appendix I Cost Schedule that added and alternate bid for "All additional work noted on drawing C8-C12". Will there be a ARRC provided bill of materials for this add alt scope in an additional addendum or are we to assume ARRC to provide all materials.  
*ARRC will provide the additional materials.*
5. The drawings spec qty 8 Red FOV New Manholes to be installed, the BOM shows 10. Please clarify if drawings or BOM is correct.  
*We include extra material on some line items to avoid delays due to minor design changes.*
6. The BOM item 10 specs a qty of 12 Ground Rods, the drawings show these to be installed in the new 8 FOV MHs. Where is the location for the 4 additional ground rods.  
*Extra material was ordered per question 5.*

7. This Appendix C SOW conflicts with other areas in the bid docs that specify ARRC is providing the materials. Please clarify that the contractor is not required to “Provide all materials in the Bill of Materials provided by ARRC

The contractor is not to provide any material listed in the BOM.

Please acknowledge receipt of this and all addendums in your firm’s Supply Bid Form and use the updated Schedule of Values when submitting your bid.

All other terms and conditions remain unchanged.

If there are any questions regarding this addendum please let me know.

Thank you,

*Greg C Goemer*

Sr. Contract Administrator  
Alaska Railroad Corporation