



# United States Department of the Interior



## NATIONAL PARK SERVICE

P.O. Box 37127

Washington, D.C. 20013-7127

IN REPLY REFER TO:

The Director of the National Park Service is pleased to inform you that the following properties have been entered in the National Register of Historic Places.  
For further information call 202/343-9542.

**JUL 16 1993**

WEEKLY LIST OF ACTIONS TAKEN ON PROPERTIES: 7/05/93 THROUGH 7/09/93

KEY: State, County, Property Name, Address/Boundary, City, Vicinity, Reference Number NHL Status, Action, Date, Multiple Name

ARIZONA, APACHE COUNTY, Colter Ranch Historic District, Jct. of 4th St. and School Bus Rd., Eagar vicinity, 93000626, NOMINATION, 7/09/93

CALIFORNIA, RIVERSIDE COUNTY, Mission Court Bungalows, 3355--3373 Second St. and 3354--3362 First St., Riverside, 93000549, NOMINATION, 7/08/93

CALIFORNIA, SAN BERNARDINO COUNTY, Hofer Ranch, 11248 S. Turner Ave., Ontario, 93000596, NOMINATION, 7/08/93

FLORIDA, POLK COUNTY, East Lake Morton Residential District, Roughly bounded by Orange St., Ingraham Ave., Palmetto St., Lake Morton Dr. and Massachusetts Ave., Lakeland, 93000621, NOMINATION, 7/09/93

MASSACHUSETTS, FRANKLIN COUNTY, Bernardston Congregational Unitarian Church, Jct. of Church and Depot Sts., Bernardston, 93000128, NOMINATION, 3/18/93

MICHIGAN, JACKSON COUNTY, Collins Manufacturing--Jackson Automobile Company Complex, 2301 E. Michigan Ave., Jackson, 93000622, NOMINATION, 7/09/93

MINNESOTA, POPE COUNTY, Lowry Public School, Florence Ave. and Maple St., Lowry, 82003000, REMOVAL, 6/07/93 (Pope County MRA)

MINNESOTA, STEELE COUNTY, Owatonna Water Works Pumping Station, W. School St. and Mosher Ave., Owatonna, 86001483, REMOVAL, 3/07/93

NEW YORK, SULLIVAN COUNTY, St. Joseph's Seminary, Seminary Rd. W side, Callocon, 93000582, NOMINATION, 7/08/93 (Upper Delaware Valley MPS)

NORTH CAROLINA, WAKE COUNTY, Edenwood, 7620 Old Stage Rd., Garner vicinity, 93000544, NOMINATION, 7/02/93 (Wake County MPS)

TEXAS, KAUFMAN COUNTY, Brooks, William and Blanche, House, 500 S. Center St., Forney, 93000566, NOMINATION, 7/06/93

VERMONT, WINDHAM COUNTY, Canal Street--Clark Street Neighborhood Historic District, Roughly bounded by Canal, S. Main, Lawrence and Clark Sts., Brattleboro, 93000593, NOMINATION, 7/08/93

VERMONT, WINDSOR COUNTY, Boyd, Theron, Homestead, Town Hwy. 6, Hartford, 93000381, NOMINATION, 5/20/93 (Agricultural Resources of Vermont MPS)

WEST VIRGINIA, NICHOLAS COUNTY, Brock Hotel, 1400 Webster Rd., Summersville, 93000615, NOMINATION, 7/09/93

WEST VIRGINIA, PRESTON COUNTY, McGrew, James Clark, House, 109 E. Main St., Kingwood, 93000618, NOMINATION, 7/09/93

WEST VIRGINIA, TYLER COUNTY, Middlebourne Historic District, Main, East, and Dodd Sts., Middlebourne, 93000613, NOMINATION, 7/09/93



STATE OF VERMONT  
AGENCY OF DEVELOPMENT AND COMMUNITY AFFAIRS

---

DIVISION FOR HISTORIC PRESERVATION  
*Preserving Vermont's historic, architectural and archeological resources*

March 31, 1993

Carol D. Shull, Chief of Registration  
National Register Branch, Interagency Resources Division  
National Park Service  
P.O. Box 37127  
Washington, D.C. 20013-7127

Dear Ms. Shull:

Enclosed please find the National Register nomination for  
the following:

Boyd, Theron, Homestead  
Hartford, Windsor County, Vermont

This property is being submitted under the Multiple Property  
submission "Agricultural Resources of Vermont" and under the  
Historic Preservation Act of 1966, as amended in 1980, for  
inclusion in the National Register of Historic Places.

Sincerely,

A handwritten signature in cursive script, appearing to read "Eric Gilbertson".

Eric Gilbertson  
Director/Deputy State Historic  
Preservation Officer

EG/EG

Enclosures



United States Department of the Interior  
National Park Service

# National Register of Historic Places Registration Form

This form is for use in nominating or requesting determinations for individual properties and districts. See instructions in *How to Complete the National Register of Historic Places Registration Form* (National Register Bulletin 16A). Complete each item by marking "x" in the appropriate box or by entering the information requested. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and areas of significance, enter only categories and subcategories from the instructions. Place additional entries and narrative items on continuation sheets (NPS Form 10-900a). Use a typewriter, word processor, or computer, to complete all items.

### 1. Name of Property

historic name Burtch-Udall-Cowdry-Boyd Farmstead

other names/site number Boyd, Theron, Homestead (preferred)

### 2. Location

street & number Town Highway 6 N/A not for publication

city or town Hartford N/A  vicinity

state Vermont code VT county Windsor code 027 zip code 05030

### 3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act, as amended, I hereby certify that this  nomination  request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property  meets  does not meet the National Register criteria. I recommend that this property be considered significant  nationally  statewide  locally. ( See continuation sheet for additional comments.)

Eric Silberman  
Signature of certifying official/Title

3/31/93  
Date

Vermont State Historic Preservation Office  
State of Federal agency and bureau

In my opinion, the property  meets  does not meet the National Register criteria. ( See continuation sheet for additional comments.)

\_\_\_\_\_  
Signature of certifying official/Title Date

\_\_\_\_\_  
State or Federal agency and bureau

### 4. National Park Service Certification

I hereby certify that the property is:

- entered in the National Register.  
 See continuation sheet.
- determined eligible for the National Register  
 See continuation sheet.
- determined not eligible for the National Register.
- removed from the National Register.
- other, (explain:)

\_\_\_\_\_  
Signature of the Keeper

\_\_\_\_\_  
Date of Action

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Boyd, Theron, Homestead  
Name of Property

Windsor County, Vermont  
County and State

**5. Classification**

**Ownership of Property**

(Check as many boxes as apply)

- private
- public-local
- public-State
- public-Federal

**Category of Property**

(Check only one box)

- building(s)
- district
- site
- structure
- object

**Number of Resources within Property**

(Do not include previously listed resources in the count.)

Contributing	Noncontributing	
3		buildings
1		sites
		structures
		objects
4		Total

**Name of related multiple property listing**

(Enter "N/A" if property is not part of a multiple property listing.)

Agricultural Resources of Vermont

**Number of contributing resources previously listed in the National Register**

0

**6. Function or Use**

**Historic Functions**

(Enter categories from instructions)

Domestic/Single Dwelling  
Agriculture/animal facility  
Agriculture/agricultural field  
Agriculture/agricultural outbuilding

**Current Functions**

(Enter categories from instructions)

Work in Progress

**7. Description**

**Architectural Classification**

(Enter categories from instructions)

Federal  
No Style

**Materials**

(Enter categories from instructions)

foundation Stone  
walls Weatherboard  
roof Shingle  
other Wood

**Narrative Description**

(Describe the historic and current condition of the property on one or more continuation sheets.)



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetBoyd, Theron, Homestead  
Hartford, Windsor Co., VermontSection number 7 Page 1

The Theron Boyd Homestead, located on a slope overlooking the Ottauquechee River one mile west of Quechee village in the town of Hartford, stands today much as it existed over two hundred years ago. The centerpiece of the farm complex is an unusually well-preserved two story Georgian plan house built in the transitional Georgian-Federal style in 1786 with an early 1800s brick ell. Alterations have been extraordinarily few, with no modern improvements. The property also includes a five bay early barn, dating from the late 1700s, a c.1945 sugarhouse, the foundations of a mid 19th century corn crib, and a chicken coop that was moved to the farm during the 1920s. In 1991 and 1992 conservation measures were taken to stabilize some portions of the buildings. The homestead, 30.16 acres in size since 1871, is a combination of forest and pasture, today bisected by Hillside Road from east to west and by River Road from north to south. It retains its integrity of location, design, setting, materials, workmanship, feeling, and association.

## 1. House, 1786

Main Block--Exterior

The house is set back about 25' south of Hillside Road near the western edge of the property and faces a southerly direction. It is approached by a walkway of early 19th century brick pavers. The 42' x 32' main block has a Georgian, center chimney plan, and is five bays wide and four deep. The foundation is rubble stone topped by a single row of dressed schist blocks that are visible at grade on the south, east, and west elevations and a portion of the north elevation. The frame is post and beam and is sided with vertically sawn feathered spruce or pine clapboards nailed down by 18th century handwrought butterfly-headed nails. Some of the very weathered clapboards still bear traces of their 18th century paint, showing that the main and side walls were yellow ocher, the rear wall was painted Indian red, the trim was white, and the doors were dark green.

Cornerboards with beaded Federal style moldings define the edges of the house. With few exceptions, windows are the original 12/12 double hung sash and have many 18th century panes intact. Window surrounds are plain. A cornice with two rows of dentils runs under the hipped roof, which is covered with red cedar shakes put on in 1991 to replace the asphalt shingle roofing. A large central rectangular brick



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetBoyd, Theron, Homestead  
Hartford, Windsor Co., VermontSection number 7 Page 2

chimney, repaired in 1991, rises through the roof ridge.

The symmetrical front (south) facade is divided into five bays, with the first and second and fourth and fifth bay windows being closely spaced together. The central element of this facade is an elaborate, raised-paneled, double-leaf entry door with a six pane glass transom and a Doric pilastered surround. In 1992 the door and surround were repaired and conserved, preserving the vast majority of the original materials. Sometime around the turn of this century a Colonial Revival entry porch was added to shelter the front door, and the clapboards flanking the door were changed. It was remodelled at least twice, and no longer exists.

The side walls are not as symmetrically arranged as the front wall, as windows were placed to accommodate the uses of the rooms within. The west wall is divided into three bays (window, door, window) with the pantry window offset below the northwest chamber window. The pantry sash, replaced in 1936, is 6/6 with Greek Revival period muntins. The door at the ground level is a single-leaf, raised panel door with a beaded, trabeated surround, and a five pane glass transom.

The east wall also is three bays, with the windows in the second and third bays closer together than the first and second bay windows. The cellar entrance is located beneath the left bay, first floor window. The stonework for the cellar was stabilized in 1992. An original 8" x 8" beech sill is visible, extending over the cellar opening.

The visible portion of the north (rear) wall has two asymmetrical bays. Two original windows are located on the second floor. The first floor has in the middle of the wall a raised panel door with a five pane glass transom and to the right two side by side 6/6 Greek Revival period sash installed in 1936. One of these window openings is original, while the other is an addition. The brick ell joins the house at a right angle just beyond the windows. The cornice on the rear wall has no dentils.

The north roof slope has a shed-roofed dormer, a very early alteration that probably was made for ventilation and light. The dormer was formed by lifting some of the rafters from their pocket in the purlin and raising the rafters about a foot. The side walls for the dormers were made out of one plank of wood. The framing and window at the front of the dormer likely were destroyed in the 1936 fire in the ell.



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation Sheet

7

3

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

Section number \_\_\_\_\_ Page \_\_\_\_\_

This damage was covered with tar paper, and in 1991 the framing was properly restored.

Main Block--Interior

## Cellar:

Under the main block is a full cellar, which can be accessed through a bulkhead with cut stone steps located along the east wall. The cellar floor is dirt, with the exception of two small areas paved with brick under the west parlor and within the base of the chimney. Foundation walls of uncoursed rubble, laid dry but pointed with a soft lime mortar, rise from the floor and are covered along the upper inside face with a later laid, rough-coursed veneer of brick. Single length beech sills overlie the stone and are original except for portions that were replaced in 1991. This restoration replaced sills that had been repaired early in this century. Other major timbers are beech and have mortise and tusk tenon joints. Secondary members visible within the cellar are vertically sawn oak and beech with half-lap joints.

The cellar is roughly divided into four sections. A brick-lined storage room in the southwest portion is two feet below the rest of the cellar and has wooden shelving brackets inserted at regular intervals along the brick walls. The chimney base is barrel-vaulted, and the arched space was used for a storage area. A dirt-floored area south of and adjoining the chimney base was set aside for root storage. The rest of the space, to the north and southwest, is undivided. An arched brick entrance to a crawlspace beneath the ell is located in the north wall. A stairway to the kitchen opens from the west wall. Perfected-head nails fasten the stairs and stringers in place on a mortise and tenon frame, indicating that these original elements have mid 19th century alterations. In the cellar is a very large cast iron kettle, probably from the early 1800s.

## Main Floors:

The interior living space of the main block has a center chimney Georgian plan. South (front) facing symmetrical formal parlors flank a front central hallway on the first floor with the kitchen, pantry, and an adjoining bedroom or storage room behind. The second story is accessed by two stairways--one, a formal staircase in the entry hall, and the



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetBoyd, Theron, Homestead  
Hartford, Windsor Co., VermontSection number 7 Page 4

other, a simpler utilitarian stairway adjacent to the pantry that continues to the basement. The second floor plan is similar to that of the first floor. Symmetrical bedrooms in the front of the house off the stairway offer passage to additional rooms in the back.

Most walls in the house are plastered and covered by multiple layers of patterned wallpapers from the early 19th through the early 20th centuries. Other notable decorative elements are early moldings, raised field paneling, and wide beaded board paneling. The 18th century raised panel doors in the east part of the house have many original hardware components.

The interior of the house was not entirely completed during the initial construction in 1786. The kitchen, adjoining bedroom and storage room, pantry, east parlor, the front hallway, and east side of the second floor were finished in 1786. Distinctive nail types from original and later construction provide evidence that the interior was finished during the first quarter of the 19th century.

## First floor:

The front entry hall and staircase are located in front of the central chimney stack. The main entry doors have raised panels and are held upright by wrought pintels and strap hinges. Evidence of a large early rimlock exists on center door stiles. Pine floors in this area are attached with wrought nails. Traces of two decorative paint treatments survive on plastered walls that are presently covered with remains of early 20th century wallpaper. Above the door to the east parlor is a raised panel, whereas the panel above the door to the west parlor is flush. A three-run staircase is fastened with a mixture of wrought and perfected-head nails. A distinctive marbleized paint is found on the stair risers. There are squared newel posts and simple rectangular balusters. A glazed graining found on the upstairs newel posts is a fine early example of this kind of decorative treatment.

The east front parlor is entered from the entry hall and also from the kitchen. Most features are from the 1786 period of construction. Fir flooring is fastened with wrought nails. Walls are plastered except for wainscoting and a raised panel fireplace wall on the west side of the room, which are beautiful examples of late 18th century woodwork. The



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation Sheet

7

5

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

Section number \_\_\_\_\_ Page \_\_\_\_\_

fireplace was closed off in the early 19th century to suit a five-plate Stafford (Connecticut) cast iron stove still in place. The stove says "Stafford Furnace" and is ornamented with raised Federal style swags and urns. To the left of the fireplace is a closet, which appears to have been remodeled or finished at a later time. A six-paneled door to the entry hall with HL hinges is from another location, as seen from hinge and latch cut-outs, and replaces the original four panel door like the door in the north wall to the kitchen.

The west front parlor is also accessed from the entry hall and kitchen, and probably was completed in the first decade of the 19th century as the door and window casings have thin Federal period moldings. The flooring is pine fixed with wrought T-headed nails. Walls are plastered and originally were painted a salmon color. The walls are covered by fragments of a bordered wallpaper, which, along with ingrained strip carpeting, date from a turn of the 20th century redecoration of this room. Window apron ends have been cut roughly, and plaster marks indicate that this room originally had a continuous chair rail. When the rail was removed, it appears that the room was papered. A fireplace on the east wall was replaced by a large stuccoed alcove with an off-center stove flue. A Federal period parlor stove with offset legs used in this area is temporarily in storage. Baseboards to each side of the alcove are plain and differ from those found along three other walls.

The kitchen, located in the north (rear) central portion of the first floor, is extraordinary for its state of preservation. A lone cast iron sink in this room is the only modern convenience in a house never otherwise altered for electricity or plumbing. The focus of this room, a prominent cooking fireplace with a bake oven with a removable tin door, has a simple surround, a later applied shelf, and is framed by raised wall paneling. It was closed off in the late 19th century to house a wood stove. A mica schist hearthstone is set out at the level of a 19th century fir subfloor, which is nailed with perfected-head nails. A space between the hearthstone and the hearth has been filled with sand into which stringers have been set to support and provide attachment for a 20th century tongue and groove oak floor toe-fastened in place with wire nails. A cupboard to the right of the hearth was added early in the 19th century, as evidenced by paneling with light Federal period beading that contrasts with the 1786 paneling with a heavier Georgian era bead that forms the back wall and east side of the cupboard.



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation Sheet

7

6

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

Section number \_\_\_\_\_ Page \_\_\_\_\_

The original varnish for the kitchen is still visible inside.

The original vertical beaded-board paneling on the south and west walls of the kitchen is in place. The east wall was moved inward, probably in the early 1800s, with the original wall paneling being installed horizontally. Patched plaster, above the north doorway to the summer kitchen, indicates that it was originally a window that was altered to permit entry to the brick ell.

A pantry and secondary stairhall are located off the kitchen to the west. One early intact layer of paint in the pantry gives evidence that this room has never been altered or renovated. Shelf cleats, horizontal wallboards, and cupboards held in place by wrought nails also indicate that the pantry is in original condition. The pantry has open shelves running along the south wall and on the north wall cupboards below the counter and open shelves above. The ends of the shelves on the south wall toward the window are intricately scalloped. The second floor stairway however had originally opened off the kitchen and was reversed to open off a side wall in the early 19th century. This side wall has vertical board paneling with one layer of stain.

The northeast room was originally two small rooms, with a shared dividing wall running east/west and each room having a door opening into the kitchen. The ceiling and flooring have patches and stud pockets showing where the walls were. The flooring runs north/south where these two rooms were located. In what was the northeast room, the north and east walls are infilled with brick nogging. The window, located in the east wall, has a plain surround and an Indian shutter with two raised panels that slides into a pocket in the wall. The flooring around where the threshold was for the door to this room is severely worn, indicating very heavy traffic into this room. What was the eastern room has detailed Federal profile casings around the door and windows and a chair rail on the south and east walls. The door has a lever latch. At some point the dividing wall between the two rooms and the interior walls facing the kitchen were taken down. The vertical paneling that made up these walls was re-erected, horizontally, further into the kitchen to form a new wall. The floor in the new section of the room runs east/west and is part of the original kitchen floor.



United States Department of the Interior  
National Park Service

National Register of Historic Places  
Continuation Sheet

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

Section number 7 Page 7

Second Floor:

The present second floor plan is similar to that of the first floor. Front sleeping chambers are nearly identical in size to the parlors directly below them. Back rooms have different square footages but are arranged similarly to their counterparts on the first floor. The western section of the second story was completed in the 1810 building phase.

It would appear that the floor dates to the early 1800s. The doors to the front hall and the central north chamber have original HL hinges. The latch on the hall door is replaced, but that on the north central door is an original lever latch. In the rear northeast chamber, fragments of an early 1800s wallpaper remain.

A single chamber extending the depth of the east side of the house was divided into an east and northeast chamber probably in the early 1800s, at the time the western section of the interior was completed. In both rooms tongue and groove fir flooring is toe-nailed in place with plancher nails and walls have horizontal wainscoting and a cornice fastened with wrought nails. In the front east chamber where a closet and fireplace remain, the fireplace surround has been partially removed and the fireplace was blocked up so a stove flue could be inserted. An investigation of the closet door casing revealed three incised signatures under the paint. One reads "C. Udall."

The southwest front chamber, probably finished in the early 1800s, has window trim, paneled doors, and a fireplace mantel with refined Federal style features. Spare double moldings of the surrounds are typical of high quality woodwork of the period. Chipwork at the base of the mantel is a vernacular interpretation of a Federal arch motif. A remarkable green and blue brocade block-printed wallpaper with matching border is original. Flooring is butt-edged pine planking fastened with T-headed wrought nails. In a closet on the east wall, panels are vertical beaded tongue and groove pine and appear to be reused, as there are several holes for wrought fastening nails that do not correspond to the scantling behind. Doors serving the room are set on early butt hinges with handmade screws.

A narrow stairhall opens onto the west stairway. The stair was re-oriented as evidenced by the presence of rough stringers, finish treads and risers that have open nail holes



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation Sheet

7

8

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

Section number \_\_\_\_\_ Page \_\_\_\_\_

indicating a previous nailing pattern, and the location of the north wall of the stairwell that partially blocks a window. A mix of wrought and perfected-head nails have been used in this area. Flooring here is butt-joined pine plank-ing that runs beneath the walls from the stairhall into the north and northwest chambers. The plaster walls are painted, and the trim is simple with one coat of paint. South of the stairhall, the doorway leading to the southwest bedroom was blocked at one time by a closet.

The northwest (rear) chamber opens off the northwest end of the hall and is notable for its early 19th century wallpaper, which is basically intact. The beaded baseboard here is a simplified version of that found in the west parlor and northeast room.

A central rear chamber directly above the kitchen is accessed through the east chambers and west hallway. Floors are pine, and walls are covered with several layers of wallpaper, the latest being an early 20th century floral print. A serpentine ceiling paper in this room is the only such treatment in the house. Simplified trabeated door and window surrounds and baseboards in this room have beaded inside edges. Other trim is very spare and all is fixed with perfected-head nails. This room has a small closet with horizontal back panels fixed with wrought nails. Side panels, beaded and hung vertically, are fixed with perfected-head nails, indicating mid 19th century placement. This room provides access to the west section of the second floor and to the attic.

## Attic:

The attic is reached by stairs from the north central chamber. In this area, the post and beam framing is clearly visible. Hips and principal rafters are braced to half-octagonal crown posts, which rest on the chimney girts. Secondary rafters are tenoned to purlins, which themselves are tenoned to primary rafters. The feet of the primary rafters rest directly on the ends of tie beams. These ends extend beyond the face of the exterior south and north facades to accept cornice headers. Wall plates, summer beams and some purlins are pine; principal rafters, crown posts, hips and posts are beech; and braces, joists, chimney girts and other purlins are red oak. "AB 69" is inscribed on scantling timber behind and above the northwest chamber fireplace wall.



United States Department of the Interior  
National Park Service

National Register of Historic Places  
Continuation Sheet

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

Section number 7 Page 9

Flooring on the east side of the attic is fastened with perfected-head cut nails and boards on the west with wrought nails. Boards on the north side appear to be recycled, possibly from the east chambers as they are well-worn on the face.

Ell--Exterior

The ell, two bays wide and measuring 70' x 20', appears to have been added to the house perhaps in the early 1800s. It was originally two stories, but a fire caused by lightning destroyed most of the second story in 1936. The cornice of the ell and main block are at the same height. The second floor of the ell terminates abruptly at the mid point of the first carriage bay as a result of the fire. The ell is built of warm red brick laid in a nine course American bond with thin tooled joints that required minor repointing in 1991. The four lowest courses protrude to form a raised water table over a random rubble and fieldstone foundation on the north and west walls, while on the east wall the fieldstone foundation is flush with the wall. On the north and west walls, staging bricks are set in tenth course headers at four foot intervals. Both sections of the ell have a gable roof covered with asphalt paper. A tall brick kitchen fireplace chimney built on the north wall of the summer kitchen was repaired in 1991.

The east (front) wall of the ell has regular fenestration. At the southern end, the first two bays are two stories tall and on the first floor have a pair of reused 12/12 windows (with a 6/6 window serving as a storm over the first floor right window). The second floor has one 6/6 window in the second bay. The third, fourth, fifth, and sixth bays are large elliptical arches, which serve as exterior entrances to the undivided storage space within. The central and northernmost arches are open, while the southernmost is fitted with a door. A raised doorway over a granite sill marks the seventh (northernmost) bay.

On the north (end) wall is a 6/6 window located off center at the east corner. A small sump (or drain outlet) has been built into the brick at the left of the window opening. The gable is fitted with one fixed two light sash located centrally and set above a truncated internal fireplace flue (this was originally a double hung sash opening, but as a result of the fire and the lower roof line, it is now only a



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation Sheet

7

10

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

Section number \_\_\_\_\_ Page \_\_\_\_\_

single sash opening).

The west wall is irregularly divided. The first two southerly bays on the second floor are similar to their counterparts on the east wall, except that each has a pair of 6/6 sash (replacements as a result of the fire). A door with early strap hinges in a rat tail pattern is below the window in the second bay. A large opening is at the northerly end of this west facade and provides entry to the small cellar. Above this is a window opening for the northernmost room of the ell. A shed-roofed, wood frame privy or outhouse was added after the fire. The doorway to the privy was originally a window, as can be seen from the rough cut bricks.

Ell--Interior

Inside the ell, the first floor is divided into three irregular spaces. A summer kitchen is at the southern end of the structure adjoining the main house. Entrance to this room is through the first carriage bay. An outhouse opens off the storage area to the north of center on the west wall. At the northernmost end is a small room accessed only through a door opening from the exterior. The second floor, reached by a rough stairway along the outer wall of the summer kitchen, has one room over the summer kitchen.

In the summer kitchen, walls and ceilings are covered with panels of beaverboard to conceal fire damage. Flooring is tongue and groove oak. The fireplace has been closed off, but underneath is a brick hearth with tongue and groove spruce sheathing set from floor to ceiling in front of a chimney mass. A fireplace and bake oven built into the chimney mass are complete with a wrought iron cooking crane and a scrolled tin oven door, both intact and in place. In the middle is a large undivided storage area, which was originally used for carriages, farm equipment, or for wood storage. A framed, two-hole privy is accessed from within the storage area. A raised walkway was built along the west wall of the storage area to serve the outhouse. Several tall stone steps lead up to a doorway for a finished room over a deep cellar at the northern end of the ell. Interior details were destroyed by the fire, but window openings in the north and west walls remain. Door reveals, window casings and cuts made in the east window casings show evidence of a table built into the reveal, with perfected head nails. A fireplace is located west of the north window. It has a coved chimney breast with hooks for a cooking crane.



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetBoyd, Theron, Homestead  
Hartford, Windsor Co., VermontSection number 7 Page 11

Above the summer kitchen is a room with plain detailing and plaster applied directly to the underlying brick wall. Damage done to the plaster on the ceiling and north wall during the fire resulted in the plaster being covered by beaverboard. A door on the north end leads to the now unfinished space above the carriage bays and a stairway down. Paint markings on the floor of this area indicate room divisions before the fire.

**2. Barn, c. 1786**

A 40' x 60" early post and beam, gable-roofed barn, dating from the last quarter of the 18th century, is located across Hillside Road about fifty yards to the east of the house. It rests on a low fieldstone foundation. Sills, hewn tapered posts and purlin posts, and reciprocally sawn connectors are all beech. Hewn cambered ties, plates, end ties, rafters, purlins and purlin plates are pine. Reciprocally sawn studs and braces are red oak. Original pine sheathing boards on the west end are fastened with wrought nails. Late 19th century replacement siding on the north and south sides is held in place by perfected-head nails.

The exterior was conserved and stabilized in 1991. Some replacement of materials decayed beyond salvaging was required. A portion of the exterior has been reclad with vertical board siding and the entire structure was reroofed with red cedar shingles in 1991. Details were replicated as closely as possible, using methods and materials similar to the original ones.

The interior is divided into five bays by heavy hewn timbers that were raised in six bents. The barn is two bays wider than most barns of this time period. Each bent consists of two outside posts, a tie beam and a queen post truss above. The first two bays contain the remainder of a hay mow above and horse stalls and cow stanchions below. The center bay has 12' openings on both the north and south sides. The fourth and fifth bays contain a large, open, dirt-floored area with a three-foot traverse wall on the east side and a room with a loose board ceiling. The building is unpartitioned above the ground level.



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation Sheet

7

12

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

Section number \_\_\_\_\_ Page \_\_\_\_\_

## 3. Corn Crib, c.1850

Large stones marking the foundation of a 19th century corn crib lie immediately to the east of the barn. It was in a very advanced state of disrepair and was dismantled in 1992. Its restoration is planned in the near future.

## 4. Chicken Coop, c.1920

To the west of the barn is a frame chicken coop, moved to the property in the 1920s. It is clapboarded and about 8' square with fieldstone foundations and an asphalt shingle gable roof.

## 5. Sugar House, c.1945

The sugar house, perched on a ridge above Whitman Brook, is reached by crossing a field to the north of the house. This gable-roofed, eaves entry frame building was constructed by Theron Boyd c.1945 when the old sugarhouse burned. It was built over an unmortared fieldstone foundation and is of 2" x 4" frame construction with tapered log rafters and sheathing overhang. Some of the material is reused. Exterior and interior walls are horizontal boards butted and face-nailed excepting that the entry side is clapboarded. The 6/6 and 12/12 windows, recycled from the ell after the fire, are fixed in place and located in the south and east walls. A large open ventilator is located southerly off-center on the roof ridge and a tall round metal chimney topped with a shanty cap sits in the center of the western roof slope. The interior consists of two rooms; the southernmost contains a large evaporator, and an arch. The northern room contains a sap holding tank and a large area for wood storage. A large, dry-laid rubble stone ramp is built into the west wall for ease in bringing the sap to the holding tank.

Repairs were made in 1991 to stabilize the sugarhouse and prevent ongoing deterioration. New asphalt shingles have been installed on the roof, a portion of the exterior siding has been replaced, and the evaporator has been repaired.

## 6. Landscape

The Theron Boyd Farmstead is located on a 30.16 acre (+)



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetBoyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

7

13

Section number \_\_\_\_\_ Page \_\_\_\_\_

combination of forest and open land that slopes gently upward from its eastern boundary at the Ottauquechee River to a level plateau at the western boundary. The property is divided by River Road, which crosses it from north to south and divides an arable field of about 8 acres from the rest of the property, and by Hillside Road, which joins River Road and bisects the farm in an east to west direction. Remnants of 18th century stone walls surround the farm and are visible between trees and bushes along the edges of the property and the roads. The barn, corn crib, and chicken coop are southeast of the house along Hillside Road. Pastures border the house, which is set back about 25 feet from the northern edge of Hillside Road. The house is flanked by lilac bushes that grow on either side of a walkway of 19th century brick pavers leading to the entrance. There are also hydrangeas, roses, day lilies, and flax. Sugar maples and occasional gnarled, bent apple trees remain from an orchard planted at the turn of the 20th century and dot pastures on the plateau around the house. To the west of the house is the opening (now covered) of a dug dry well that kept food cool in the summer. Depressions north of the brick ell indicate the foundations of another 18th century building now long gone.

Back almost 100' from the main house is the sugarhouse, which stands along the north edge of the pasture at the top of a steep bank that drops down to the sugarbush. The sugarbush is bisected by Whitman Brook, which joins the Ottauquechee River at the easterly boundary of the property. Wheelock Road forms the northerly boundary of the farmstead.



Boyd, Theron, Farmstead  
Name of Property

Windsor County, Vermont  
County and State

### 8. Statement of Significance

#### Applicable National Register Criteria

(Mark "x" in one or more boxes for the criteria qualifying the property for National Register listing.)

- A** Property is associated with events that have made a significant contribution to the broad patterns of our history.
- B** Property is associated with the lives of persons significant in our past.
- C** Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.
- D** Property has yielded, or is likely to yield, information important in prehistory or history.

#### Criteria Considerations

(Mark "x" in all the boxes that apply.)

Property is:

- A** owned by a religious institution or used for religious purposes.
- B** removed from its original location.
- C** a birthplace or grave.
- D** a cemetery.
- E** a reconstructed building, object, or structure.
- F** a commemorative property.
- G** less than 50 years of age or achieved significance within the past 50 years.

#### Narrative Statement of Significance

(Explain the significance of the property on one or more continuation sheets.)

### 9. Major Bibliographical References

#### Bibliography

(Cite the books, articles, and other sources used in preparing this form on one or more continuation sheets.)

#### Previous documentation on file (NPS):

- preliminary determination of individual listing (36 CFR 67) has been requested
- previously listed in the National Register
- previously determined eligible by the National Register
- designated a National Historic Landmark
- recorded by Historic American Buildings Survey # \_\_\_\_\_
- recorded by Historic American Engineering Record # \_\_\_\_\_

#### Areas of Significance

(Enter categories from instructions)

Architecture

Agriculture

#### Period of Significance

1786 - c. 1945

#### Significant Dates

c. 1786

1786

1936

#### Significant Person

(Complete if Criterion B is marked above)

N/A

#### Cultural Affiliation

N/A

#### Architect/Builder

Unknown

#### Primary location of additional data:

- State Historic Preservation Office
- Other State agency
- Federal agency
- Local government
- University
- Other

Name of repository:



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetSection number 8 Page 1 Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

The Theron Boyd Homestead is one of the most architecturally outstanding late 18th century properties in the state of Vermont. The house, built in 1786 in the transitional Georgian-Federal style, is a remarkably well-preserved Georgian plan, hip-roofed, center chimney house with few alterations and no modern improvements. Its exceptional exterior architectural features include a central, double-leaf, paneled door framed by Doric pilasters and a six pane transom, a cornice with two rows of dentils, the original feathered clapboards and 12/12 windows, narrow cornerboards with applied molding. Outstanding interior features include the massive central chimney and fireplaces, Georgian and Federal period paneling and woodwork, two early 1800s cast iron stoves, early 1800s wallpaper, and well-preserved rooms. The barn, also built in the late 18th century, is noteworthy as a rare surviving farm structure from this time period and for its large size. The house was built for William Burtch, son of one of the first settlers of Hartford, and was owned for much of the 1800s by the Udall family. This property is significant historically as an excellent example of a very early farmstead developed by a prosperous businessman, and also is representative of statewide farming trends through the 19th and first half of the 20th centuries. Until the Civil War period, farm production was diversified with a variety of crops, as was common throughout much of Vermont. After 1871, when the property reached its current size of about 30 acres, its owners engaged in subsistence farming. The c.1850 corn crib foundation, c.1920 chicken coop, c.1945 sugar house, and the landscape, including stone walls along boundaries, roads and fields, a sugar bush, open fields, and mature maples and elms, contribute to the understanding of this agricultural history. The Theron Boyd Homestead is being nominated to the National Register under the Multiple Property submission Agricultural Resources of Vermont, and meets the registration requirements for the farmstead property type.

The house and barn on the Theron Boyd Homestead property are of outstanding architectural significance to the state of Vermont. The house was built in 1786 for William Burtch, who was a prosperous early businessman in the Hartford area. Hartford, located along the Connecticut River, was an important center of early commerce for the developing towns in Windsor County and across the river in New Hampshire. Burtch's house, when built, was probably one of the most stylish houses erected in the area just after the



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetBoyd, Theron, Homestead  
Hartford, Windsor Co., VermontSection number 8 Page 2

Revolutionary War. Today it is one of the best preserved houses from its time period in the state. It is clearly different from the large, two story, Georgian period houses built in the area before the Revolution, which had steeply pitched gable roofs with little or no overhang and often little exterior ornamentation. The house does have some Georgian period features, the most prominent being the paneled, double leaf, front door, but most of the rest of the features on Burtch's house are clearly Federal in style. The front door is framed by a transom and elegant pilasters that are from the early Federal style. The house also has a high hipped roof, a delicate cornice with two rows of dentils, cornerboards with applied molding, and the window sash and window spacing of the early Federal style.

The interior of the house is also of exceptional architectural significance. It retains its original central chimney stack and most of its original floor plan, the few changes to the plan having been made in the early 1800s. The house is quite rare for never having had any modern improvements installed, such as electricity, plumbing, or telephones. The main kitchen, adjoining bedroom and storage room, pantry, east parlor, front hallway, and east side of the second floor were finished in 1786, with the rest of the main block of the house being finished in the early 1800s. The plaster walls, paneling and other woodwork in all the rooms, and most of the floors remain intact. The paneling and woodwork is of outstanding quality. The house also has two very early cast iron stoves and two rooms with wallpaper from the early 1800s. It is very rare in Vermont for wallpaper and stoves from this time period to have survived in place and in such fine condition. The front staircase has excellent examples of marbleizing and glazed graining. The main kitchen has intact its original fireplace with the bake oven and an adjoining pantry in intact condition. In the brick ell there is a summer kitchen, also with an intact fireplace, bake oven, cooking crane, and tin oven door.

The house has yielded and, upon more study, will yield further information about construction methods after the Revolutionary War, types of materials used in house construction, the level of skill of builders during the period, the introduction and evolution of architectural trends and styles during Vermont's early settlement period, and how people used their living spaces. The two intact kitchens, the pantry, the food storage areas in the cellar, and the dry well outside provide significant information on



United States Department of the Interior  
National Park Service

National Register of Historic Places  
Continuation Sheet

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

Section number 8 Page 3

early food preparation and storage.

The c.1786 barn is a rare surviving agricultural building. Many barns from this time period in Vermont have disappeared over time or have been altered or added on to. This barn is instructive about early barn construction methods, skills required to build barns, use of building materials, early farming practices in Vermont, and how farmers used the space in their barns. This barn is especially outstanding because of its large size, being five bays wide and 40' x 60' in size rather than the three bay, 30' x 40' size more common to the time period.

The chicken coop and sugar house represent the subsistence period of the farm, and each building is a good example of its type.

The history of the complex reflects the development of a farm in the Upper Connecticut River Valley from the period of settlement immediately following the Revolutionary War. The Town of Hartford was chartered in 1761 and permanent settlement began in 1764. The first settlers of this property were Benjamin Burtch, who was a carpenter, and his family. Burtch, born in Stonington, Connecticut, in 1731 and married to Anna Udall, moved to Hartford in 1765. Within the next three years he had bought part of the 500 acres that would become the Burtch farm and brought his family to live in a log cabin he built on the property. It is believed that within a short time he may have built his more permanent dwelling, a large frame house that also served as a tavern (since burned).

In 1786, according to Woodstock town historian Henry Swann Dana, Burtch's son William "built the present Udall house, using the cellar of this house for the storage of liquors and some West India goods, for want of room elsewhere." William built his house and barn next to his father's house and tavern. He had a thriving wholesale and retail trade, as well as several potasheries, a pottery, and a brickyard, and made a specialty of the preparation of a ginseng root tonic. William's house may have been similar to the one his brother Benjamin built in 1777 in Woodstock (no longer standing). It is possible that their father Benjamin may have been involved in the design and construction of these two houses.

The 1791 census records that there were eleven people in



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetBoyd, Theron, Homestead  
Hartford, Windsor Co., VermontSection number 8 Page 4

William's household. Some or most of the six males over the age of 16 may have been his employees. The 1800 census shows 22 people in the household, with thirteen men between the ages of 16 and 26. It is not known how Burtch housed 22 people, as it appears the main block of the house, although large, would not comfortably hold this many people. Perhaps the brick ell had been built by this time. There is evidence on the floor of the second story of the burned out section of the ell of room divisions. It has been suggested that the ell was built in the first quarter of the 19th century. The elliptical arches are features found in the Federal style. Further research and analysis of other early brick buildings in the area is needed to come to a better understanding of the ell and to see if it is possible that it could have been built by 1800 or if it is later.

In the late 1700s the Burtch family began suffering business reversals, and in 1793 Benjamin Burtch mortgaged 303 acres (which included the land the tavern and William's house stood on) to Samuel Udall, his neighbor. William mortgaged the rest of the property in 1802, and in December 1805 sold the whole farm to Udall for \$8,300. William Burtch continued in local business until about 1808 when he moved to Cincinnati and then Indiana with his family. While traveling down the Wabash River, they were struck by the fever and everyone in the family but two of the children died.

Throughout most of the 19th century, from 1805 to 1898, the farm was owned by James Udall and his children. Samuel Udall died on December 11, 1805. In his will, made the day before his death, he left the Burtch farm to his 26 year old son James. The use of one quarter of "the premises" was to go to Samuel's widow during her lifetime. Samuel's home farm was to be sold to settle the expenses of his estate. James Udall married Sophia Downer Champlin in September 1809; they had ten children between 1810 and 1833. Perhaps about the time of his marriage or soon thereafter Udall may have finished off the rest of the interior of the house. If the brick ell wasn't built by Burtch, perhaps Udall was responsible for its construction sometime in the first quarter of the 19th century. If so, Udall may have built the ell to house his many children, as well as others who lived in the household. It is possible that the bricks were made at the brickyard in the northeastern section of the property. The brickyard had been run by William Burtch, without much financial success, and is known to have been operated by James Udall as early as 1812.



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetBoyd, Theron, Homestead  
Hartford, Windsor Co., VermontSection number 8 Page 5

James Udall was well known in Hartford and held many offices over the years--listers, auditor, tax collector, selectman, town representative, and judge of the Hartford District Probate Court. He was a founder of the local Masonic Lodge, was a teacher for several years at district schools in Hartford in 1819-21, and at some point took in several boarding students. James farmed his property, a grandson recounting that he was a breeder of Merino sheep, Durham cattle, and Morgan horses. These breeds were among the first that Vermont farmers introduced to improve the general stock of farm animals in the state. Census records show that there were usually farm laborers living in the household.

James Udall took out a series of mortgages, using the farm as collateral, starting in 1826. It is thought the mortgages were used for farm improvements, and were quickly repaid. Among the mortgages and notes were some from William Jarvis of Weathersfield, in 1834, 1844, and 1846. Jarvis was a significant early importer to Vermont of Spanish Merino sheep. In 1845 Udall sold off two parcels, a 100 acre lot and a 150 acre lot, and in 1847 leased the "brickyard farm" parcel for a year. In 1854 he transferred to his daughter, Sophia, most of the livestock he had housed in his neighbor's barn next door, including three horses, two cows, two heifers, three calves, and one pig. It is speculated that he sold off the land and transferred the stock because of financial difficulties, but it should be noted that Udall was also getting on in years, being 66 years old in 1845.

What was left of the property continued to be farmed. The 1860 census shows that in the household, James (age 82) was listed as a farmer, two sons were farm laborers, and there were three hired farm laborers as well. The agricultural census for that year shows the farm had 140 improved acres and 60 unimproved acres, and was valued at \$10,000. Livestock, valued at \$1,000, included three milk cows, two horses, two working oxen, two other cattle, 136 sheep, and one swine. Farm products were 100 bushels of Indian corn, 15 bushels of wheat, 10 bushels of beans and peas, 250 pounds of butter, 60 tons of hay, and 400 pounds of maple syrup. This record and the list of stock transferred to Sophia in 1854 show that farming was quite diverse on the property, as was common on Vermont farms during the period.

In 1862 James Udall sold the property to his youngest son, Henry Douglass Udall, for \$6,000. Henry married Laura Keyes



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation SheetBoyd, Theron, Homestead  
Hartford, Windsor Co., VermontSection number 8 Page 6

in February 1865, and brought his wife to live in his family home. They had two children. James Udall died in 1867 at the age of 88, and his widow died in 1879 at age 86 or 87. Henry continued to farm the property but had financial difficulties, and in order to pay off a large mortgage due in April 1871, he sold over 100 acres of the farm. In November he and his wife sold for \$2,500 the rest of the farm (the current parcel) to his sister, Sophia (a widow) and to the husband of Udall's sister Lydia, Henry Kirke Brown. Brown, of Newburgh, New York, was a noted mid-19th century American sculptor with studios in New York City. Some of his major works were a bust of William Cullen Bryant, and equestrian statues of George Washington in Union Square Park, New York, and generals Nathanael Greene and Winfield Scott in Washington, D.C.

It appears that after the sale, Henry Udall and his family moved away. The 1880 census shows Sophia Udall as head of the household. Others living with her were her sister Elizabeth and brother Edward, and a farmer with his wife and two children. By this time the farm was only valued at \$2,500, with one horse, two oxen, two milch cows, one calf, one swine, ten sheep, and twenty poultry. Farm products were 200 dozen eggs, ten tons of hay, 50 bushels of Indian corn, 40 bushels of wool, five cords of wood, 400 pounds of butter, and one acre of potatoes. It is possible that in the early 1890s the Udalls may have added the Colonial Revival style entry porch (it fell off in the 1980s) to the front of the house. Found in the house was a note dated December 29, 1891, from W. P. Morse, architect, contractor, and builder of West Lebanon, New Hampshire, to Miss E. C. Udall regarding plans for some unspecified work.

After the deaths of the owners of the property, Henry Kirke Brown in 1886 and Sophia Udall in 1893, their estates had to be settled. The farm was sold at auction in 1898 to Albert and Mary Cowdry, their daughter Florence, and William Boyd, who lived nearby on the farm of Albert's father, William Cowdry. Earning a living on the property was difficult, as there was not enough land for a profitable farming operation. Boyd and sometimes Cowdry worked for neighboring farmers, doing such jobs as haying, milking, plowing, filling silos, and chopping cordwood. They were able to make a few improvements to the property, such as adding new wallpapers in the house, and planting an orchard of over 50 plum and apple trees in the field north of the brick ell.



United States Department of the Interior  
National Park ServiceNational Register of Historic Places  
Continuation Sheet

8

7

Section number \_\_\_\_\_ Page \_\_\_\_\_

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

In 1902 Albert Cowdry died and Mary's brother, George Morgan, came to live with her. He had a shop at the north end of the ell. Florence and William Boyd had a son, Theron, in 1901. They separated, probably in 1903, with William Boyd passing on his interest in the property to Florence. Florence remarried and moved, leaving Theron to be raised by her mother. To support her family Mrs. Cowdry kept cows and chickens, may have taken in laundry, did baking, and worked at the Quechee Fells Farm, located nearby.

In the 1920s Theron Boyd moved two small buildings to a site near the barn for use as chicken coops and built a sugarhouse (it burned and Boyd built another c.1945). George Morgan died in the 1920s and Mrs. Cowdry died in 1932, leaving her share of the property to her daughter, Florence. Boyd continued to live here, keeping a few cows and a garden, working the sugarbush, and working part time at the Quechee Fells Farm. Over the years he had, at various times, others living in the house, some of them assisting him with housework or sugaring. On July 8, 1936, lightning struck the brick ell, burning most of the ell's second floor. A new roof was built over the first floor and a privy was added in the ell. Other than this new roof, Boyd made no changes or modern improvements, such as electricity, plumbing, or telephone service, to his house.

After the death of his mother c.1955, he, his half-brother, and step-father received equal shares in the property. His step-father left his share to the two brothers upon his death in 1971. In the 1970s the land around the Theron Boyd property in Quechee underwent extensive development. Theron Boyd resisted pressure to sell his property and because of this, his resistance to modern improvements, and his traditional farming methods, he became somewhat of a symbol of the "traditional independent Vermont farmer." In 1979 Theron's half-brother sold his interest in the property to Armand Henault, Jr., with the provision that Theron have full use of the property until his death.

In 1981 Theron Boyd gave his half interest in the property to a friend with the understanding that she would care for him, but this plan failed and in 1986 court proceedings were filed to restore the property to him. As a result of the court settlement, this half interest in the property was transferred to the Ottauquechee Land Trust (later renamed the Vermont Land Trust), which would provide Boyd with life time care. The owners of his half-brother's half interest in the



United States Department of the Interior  
National Park Service

National Register of Historic Places  
Continuation Sheet

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

Section number 8 Page 8

property also sold their share to the Land Trust. The intention was that the property would eventually be obtained by the State of Vermont, Division for Historic Preservation. In 1987 the Division for Historic Preservation contracted with the Centre for Environmental Interpretation, Manchester Polytechnic, in Manchester, England, to prepare an interpretative plan for the property, and with the Society for the Preservation of New England Antiquities to prepare a preservation feasibility study. All but eight acres of the property was sold in 1989 to the Division for Historic Preservation. Theron Boyd died on March 22, 1990, at a nursing home in Woodstock, Vermont. The Vermont Land Trust transferred the remaining eight acres to the Division for Historic Preservation that year.

Work to stabilize the buildings began in 1991. An archeological study was done along the west and south sides of the house, around all sides of the barn, and in selected grids within the barn. That year the sugarhouse was stabilized and repaired. The Division contracted with David Briggs, restoration mason, to do masonry repairs (relaying the barn foundation, pointing the house foundation, and repointing the two house chimneys and the brick work in the ell where necessary). The Division also contracted with Jan Lewendowski to undertake heavy timber repair and restoration, repairing the sills and a portion of the east plate of the house, and for the barn conserving or restoring the framing and siding as needed and putting on new roofing. In 1991 the Division's restoration specialist, Mark Shiff, began work on window conservation, and in the winter and spring of 1992 restored the frontispiece. Ray Clark of Lyme, New Hampshire, has been continuing window conservation and repair in late 1992 and 1993.

The plan is to continue work on conservation and restoration on the property as funding is available, and to eventually open the property as a state-owned historic site.



Boyd, Theron, Homestead  
Name of Property

Windsor County, Vermont  
County and State

## 10. Geographical Data

Acreage of Property 30.16 acres

### UTM References

(Place additional UTM references on a continuation sheet.)

1	18	70481010	48338910
Zone	Easting	Northing	
2	18	7048210	48337410

3	18	7044710	48336410
Zone	Easting	Northing	
4	18	7044210	48338810

See continuation sheet

### Verbal Boundary Description

(Describe the boundaries of the property on a continuation sheet.)

### Boundary Justification

(Explain why the boundaries were selected on a continuation sheet.)

## 11. Form Prepared By

name/title draft by Betsy Baten; revised by Vermont Division for Historic Preservation  
UVM Historic Preservation Program  
organization (see above) date February 1993/March 1993  
street & number 135 State Street, Drawer 33 telephone (802) 828-3226  
city or town Montpelier state VT zip code 05633-1201

## Additional Documentation

Submit the following items with the completed form:

### Continuation Sheets

### Maps

A **USGS map** (7.5 or 15 minute series) indicating the property's location.

A **Sketch map** for historic districts and properties having large acreage or numerous resources.

### Photographs

Representative **black and white photographs** of the property.

### Additional items

(Check with the SHPO or FPO for any additional items)

## Property Owner

(Complete this item at the request of SHPO or FPO.)

name Vermont Division for Historic Preservation  
street & number 135 State Street, Drawer 33 telephone (802) 828-3226  
city or town Montpelier state Vermont zip code 05633-1201

**Paperwork Reduction Act Statement:** This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C. 470 *et seq.*).

**Estimated Burden Statement:** Public reporting burden for this form is estimated to average 18.1 hours per response including time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Chief, Administrative Services Division, National Park Service, P.O. Box 37127, Washington, DC 20013-7127; and the Office of Management and Budget, Paperwork Reductions Projects (1024-0018), Washington, DC 20503.



United States Department of the Interior  
National Park Service

## National Register of Historic Places Continuation Sheet

9, 10 1

Boyd, Theron, Homestead  
Hartford, Windsor County, Vermont

Section number \_\_\_\_\_ Page \_\_\_\_\_

### 9. BIBLIOGRAPHY

The information for this nomination comes primarily from the following source:

Society for the Preservation of New England Antiquities.  
"Preservation Feasibility Study: The Udall-Boyd House and Associated Property." (typescript). Original at Vermont Division for Historic Preservation, Montpelier, Vt. 1987.

### 10. GEOGRAPHICAL DATA

UTM References:

E. /18/704650/4834000


Verbal Boundary Description:

The boundary of the Theron Boyd Homestead is shown on the accompanying map entitled "Subdivision Plan for the Theron Boyd Property in Windsor County, Hartford, Vermont," and dated June 26, 1989. The map is recorded in the Hartford Town Offices, and is filed in the Hartford Land Records map cabinet on hanger 139-B. The property is an irregular parcel of land generally bounded on the north by Wheelock Road, on the east by River Road and the Ottauquechee River, and on the south the parcel runs south of Hillside Road.

Boundary Justification:

The + 30.16 acres included in this nomination is the plot of land that has been historically associated with the property since 1871. It includes the main house, outbuildings, adjacent fields, pastures, and sugarbush, which have historically been the core of the Theron Boyd Homestead. The boundary conveys the historic context of the property.






BOYD, THERON, HOMESTEAD  
 HARTFORD  
 WINDSOR COUNTY  
 VERMONT

Scale  
 1" = approx. 100'





**NOTES:**

- BEARINGS ARE WITH RESPECT TO APPROX TRUE NORTH
- PROPERTY IS SUBJECT TO ALL EXISTING EASEMENTS AND RIGHTS-OF-WAY OF RECORD
- BOUNDARIES COMPUTED FROM A THEODOLITE & E.D.M. FIELD SURVEY
- BOUNDARIES BASED ON PHYSICAL EVIDENCE, PREVIOUS SURVEYS, & INFORMATION PROVIDED BY OTHERS WITH NO DEED RESEARCH CONDUCTED BY BRUNO ASSOC. INC. P.C.

**ADJOINERS**

NAME	NUMBER
Q.L.C. (7, 08-02, 001)	1
N/F - MORRIS (7, 56-2)	2
N/F - H. EASTMAN (7, 56)	3
N/F - T.M. EASTMAN (7, 57)	4
N/F - D.B.L. EASTMAN (7, 57-1)	5
N/F - SEAVER (12, 1)	6
Q.L.C. - COACH RD CONDOMINIUMS (12, CRC)	7
Q.L.C. (12, 801-001)	8
Q.L.L.A. GOLF COURSE (7, 10-03)	9
Q.L.L.A. GOLF COURSE (7, 10-02)	10


**RECORD OWNER**  
 VERMONT LAND TRUST  
 KING FARM  
 WOODSTOCK, VERMONT

I DO HEREBY CERTIFY THIS MAP AND INFORMATION TO BE SUBSTANTIALLY CORRECT.  
 VT L.S. 485

**BRUNO ASSOCIATES INC. P.C.**  
 ENGINEERS, PLANNERS, SURVEYORS  
 WOODSTOCK, VERMONT

**SUBDIVISION PLAN**  
 for the  
**THONER BOYD PROPERTY**  
 in  
 WINDSOR COUNTY  
 HARTFORD  
 VERMONT

SURVEYED JWB-FM	DESIGNED
DRAWN CRM	CHECKED CF
SCALE <b>1" = 200'</b>	
DATE 6/28/89	




- LEGEND:**
- IRON PIN/PIPE FOUND
  - ⊙ IRON PIN/PIPE SET
  - BOUNDARY POINT
  - UTILITY POLE
  - CULVERT
  - STONE WALL
  - WIRE FENCE
  - CENTERLINE BROOK
  - N/F NOW OR FORMERLY

**TIE LINES ONLY**  
 A-B S 55° 19' 00" E, 722.0'  
 B-C S 47° 01' 00" W, 744.3'

**TOTAL AREA = 30.15 +/- Acres**






704 510 000 FEET 27'30" (HARTLAND) 6571 III SW NORTH HARTLAND (JUNC. U.S. 5) 4.2 MI. 25'

**BOYD, THERON HOMESTEAD**  
**HARTFORD, LUNDY & CO., VT**

SCALE 1:24 000

UTMS. \* ZONE 18

EASTING	NORTHING
Z.18 704800	4833780 - PTA.
Z.18 704820	4833740 - PT B
Z.18 704470	4833640 - PT C
Z.18 704420	4833880 - PT D
Z.18 704420	4834000 - PTE



CONTOUR INTERVAL 20 FEET  
 NATIONAL GEODETIC VERTICAL DATUM OF 1929

UTM GRID AND 1988 MAGNETIC NORTH DECLINATION AT CENTER OF SHEET

THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS  
 FOR SALE BY U. S. GEOLOGICAL SURVEY  
 DENVER, COLORADO 80225 OR RESTON, VIRGINIA 22092  
 A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST







92-97-10

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont  
Credit: John P. Dumville  
Date: November 1992  
Negative on file at VT Division  
for Historic Preservation  
View looking north; frontispiece  
of main block of house (#1)

Photo 4

VT Div. for Historic Preservation  
135 State St, Montpelier, Vermont  
Theron Boyd House, Quechee,  
Vermont. Frontispiece after  
restoration completed over the  
winter of 1991-1992.

John P. Dumville (92-A-97.10)







Theron Boyd Farmhouse - looking west  
Windsor Co., VT.  
Betsy Baten, Photographer  
3/26/92

VERMONT HISTORIC PRESERVATION OFFICE, MONTPELIER VT.

92-28

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont  
Credit: Betsy Baten  
Date: March 1992  
Negative on file at VT Division  
for Historic Preservation  
View looking southeast, west side  
of house (#1)

Photo 3







87-C-24

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont  
Credit: David Bohl  
Date: Sept./Oct. 1987  
Negative on file at VT Division  
for Historic Preservation  
View looking northwest, front east  
parlor of house (#1)

Photo 7








87-C-18

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont  
Credit: David Bohl  
Date: Sept./Oct. 1987  
Negative on file at VT Division  
for Historic Preservation  
View looking southwest; fireplace  
wall of kitchen in main block of  
house (#1)  
Photo 8







Theron Boyd Sugarhouse - Looking North  
Windsor Co, Vermont  
Betsy Baten, PHOTOGRAPHER  
3/26/92  
HISTORIC PRESERVATION OFFICE, STATE OF VT

92-28

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont  
Credit: Betsy Baten  
Date: March 1992  
Negative on file at VT Division  
for Historic Preservation  
View looking north; sugarhouse  
(#5)

Photo 12







Theron Boyd Barn - looking west  
Windsor Co, Vermont

Betsy Baten, Photographer

3/26/92

Vermont Historic Preservation Office

92-28


Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont  
Credit: Betsy Baten  
Date: March 1992  
Negative on file at VT Division  
for Historic Preservation  
View looking southeast; front and  
side of barn (#2) and chicken  
coop (#4)  
Photo 11





85-50  
Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont  
Credit: David Bohl  
Date: Sept./Oct. 1987  
Negative on file at VT Division  
for Historic Preservation  
View looking east; framing of  
attic in main block of house  
(#1)  
Photo 6





86-194

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont  
Credit: John P. Dumville  
Date: November 1986  
Negative on file at VT Division  
for Historic Preservation  
View looking north; cornice and  
window of upper southeast  
corner, front wall, house (#1)  
Photo 5





Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont  
Credit: David Bohl  
Date: Sept./Oct. 1987  
Negative on file at VT Division  
for Historic Preservation  
View looking west; pantry off  
kitchen in main block of house  
(#1)  
Photo 9

87-C-29





Boyd, Theron, Homestead <sup>34</sup>  
Hartford, Windsor Co., Vermont  
Credit: David Bohl  
Date: Sept./Oct. 1987  
Negative on file at VT Division  
for Historic Preservation  
View looking southeast; west front  
second floor bedroom in main  
block of house (#1)  
Photo 10





8  
Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont

Credit: David Bohl

Date: Sept./Oct. 1987

Negative on file at VT Division  
for Historic Preservation

View looking southwest, side and  
rear of main block, and front  
wall of ell of house (#1)

Photo 2





87-C-1

Boyd, Theron, Homestead  
Hartford, Windsor Co., Vermont  
Credit: David Bohl  
Date: Sept./Oct. 1987  
Negative on file at VT Division  
for Historic Preservation  
View looking north, front facade  
of main block of house (#1)

Photo 1