



Washington State School Seismic Safety Assessments Project

# SEISMIC UPGRADES CONCEPT DESIGN REPORT

Carbonado Historical School 19  
Carbonado School District 19

June 2019

PREPARED FOR



PREPARED BY



**This page intentionally left blank.**

# WASHINGTON STATE SCHOOL SEISMIC SAFETY ASSESSMENTS PROJECT

## SEISMIC UPGRADES CONCEPT DESIGN REPORT Carbonado Historical School 19 – Community Gym (Bldg B) Carbonado School District 19

June 2019

Prepared for:

State of Washington  
Department of Natural Resources and Office of Superintendent of Public Instruction

---



Prepared by:



333301 Ninth Ave. S, Suite 300  
Federal Way, WA 98003-2600  
206-431-2300  
File No. 262018.063  
information@abam.com



**ReidMiddleton**

728 134th Street SW, Suite 200  
Everett, WA 98204  
425-741-3800  
File No. 262018.063  
www.reidmiddleton.com

**This page intentionally left blank.**



## EXECUTIVE SUMMARY

---

This report documents the findings of a preliminary seismic evaluation of Carbonado Historical School No. 19, Community Gym Building (Building B) in Carbonado, Washington. The school is a K-8th grade school with approximately 180 students enrolled. Existing drawings or other original construction documentation were not available at the time of the site visit for this ASCE 41 Tier 1 evaluation. This building is the second building completed at the current site and was constructed in 1936, seven years after the main building, Building A. Building B, the community gym, has a footprint area of approximately 4,500 square feet. The closest structures are Building A, located approximately 50 feet to the north, and a detached covered play area located 30 feet to the south.

The roof is curved and appears to be approximately 30 feet high at the apex and 20 feet at the lower edges. The majority of the building structure is covered by siding and finishes and is not visible. The curved roof girders appear to be heavy timber. The west half of the structure is a single-story gymnasium. It is most likely that this building is timber framed, as was common for structures of this vintage.

The east half of the structure is two stories, with a kitchen, storage rooms, and restrooms at the first level and music room and storage rooms at the second level. Further investigation is required to confirm the wall construction, but it is likely that walls at this side of the building are stud framed.

The lateral system was not visible during the site visit, as it was covered by the exterior siding and interior finishes. There are a few instances of tension-only steel rod braces in the original portion of the adjacent Building A, which is seven years older. It is possible that similar bracing was used, but further investigation is required to confirm. Wood-framed floor and roof diaphragms constructed in the 1930s are usually straight or diagonally planked with dimensional lumber; it is likely one of these types of systems was used for this building's floors and roof.

BergerABAM performed a Tier 1 screening in accordance with the ASCE 41-17 *Seismic Evaluation and Retrofit of Existing Buildings*. The evaluation included field observations of the existing construction to the extent that the structure was visible. There were a number of unknowns encountered during the structural seismic evaluation that should be investigated further. First, as mentioned previously, the lateral load path could not be verified. Second, even assuming there are shear walls at the music room, connections between the stories capable of transferring overturning and shear could not be verified and may not exist. Similarly, positive connections of wood posts to the foundations, bolting of wood sills to the foundations, and positive connections between girder-to-column connections could not be verified. Ties between foundation elements could not be visually verified; however, as the soil class is believed to be "C," this check may not be required; further investigation is required.

For the second floor and roof diaphragms, while it is unlikely there are any seismic joints, the diaphragm construction was not visible and should be confirmed through further investigation. Similarly, the continuity of diaphragm chord elements could not be verified. As mentioned earlier, it was very common for wood structures of this era to be straight or diagonally sheathed.

As the construction of this building's floor and roof diaphragms could not be visually inspected, it is unknown if the diaphragms are blocked and meet the maximum permitted aspect ratios. Further investigation is required to confirm or dismiss these unknowns.

Conceptual seismic upgrade recommendations for structural and nonstructural systems are provided to improve the performance of the building to meet the designated performance criteria of ASCE 41-17. Sketches for the concept-level seismic upgrades are provided in Appendix B. The conceptual recommendations are detailed in Section 4.

The recommendations for nonstructural upgrades include upgrading sprinkler systems to comply with NFPA 13, restraining containers holding hazardous materials (if any), bracing suspended ceilings, providing independent supports for light fixtures, anchoring storage cabinets and shelving to adjacent floors or walls, and providing seismic bracing for mechanical equipment and life-safety systems.

# Table of Contents

Page No.

## EXECUTIVE SUMMARY

<b>1.0 INTRODUCTION</b> .....	<b>1</b>
1.1 BACKGROUND.....	1
1.2 SCOPE OF SERVICES.....	1
<b>2.0 SEISMIC EVALUATION PROCEDURES AND CRITERIA</b> .....	<b>5</b>
2.1 ASCE 41 SEISMIC EVALUATION AND RETROFIT OVERVIEW.....	5
2.2 SEISMIC EVALUATION AND RETROFIT CRITERIA.....	6
2.3 REPORT LIMITATIONS.....	8
<b>3.0 BUILDING DESCRIPTION &amp; SEISMIC EVALUATION FINDINGS</b> .....	<b>9</b>
3.1 BUILDING OVERVIEW.....	9
3.2 SEISMIC EVALUATION FINDINGS.....	10
<b>4.0 CONCLUSION AND RECOMMENDATIONS</b> .....	<b>15</b>
4.1 SEISMIC-STRUCTURAL UPGRADE RECOMMENDATIONS.....	15
4.2 NONSTRUCTURAL UPGRADE RECOMMENDATIONS.....	16
4.3 OPINION OF CONCEPTUAL CONSTRUCTION COSTS.....	20

## Appendix List

APPENDIX A: FIELD INVESTIGATION REPORT AND TIER 1 CHECKLISTS
APPENDIX B: CONCEPT-LEVEL SEISMIC UPGRADE FIGURES
APPENDIX C: OPINION OF PROBABLE CONSTRUCTION COSTS
APPENDIX D: EARTHQUAKE PERFORMANCE ASSESSMENT TOOL (EPAT) WORKSHEET
APPENDIX E: NOT USED
APPENDIX F: FEMA E-74 NONSTRUCTURAL SEISMIC BRACING EXCERPTS

## Figure List

FIGURE 2-1. FLOW CHART AND DESCRIPTION OF ASCE 41 SEISMIC EVALUATION PROCEDURE.....	5
---	---

## Table List

TABLE 2.2.1-1. SPECTRAL ACCELERATION PARAMETERS (NOT SITE-MODIFIED).....	7
TABLE 3.1.3-1. STRUCTURAL SYSTEM DESCRIPTIONS.....	9
TABLE 3.1.4-1. STRUCTURAL SYSTEM CONDITION DESCRIPTIONS.....	10
TABLE 3.2.1-1. IDENTIFIED STRUCTURAL SEISMIC DEFICIENCIES BASED ON TIER 1 CHECKLISTS.....	10
TABLE 3.2.2-1. IDENTIFIED STRUCTURAL CHECKLIST ITEMS MARKED AS UNKNOWN.....	11
TABLE 3.2.3-1. IDENTIFIED NONSTRUCTURAL SEISMIC DEFICIENCIES BASED ON TIER 1 CHECKLISTS.....	12
TABLE 3.2.4-1. IDENTIFIED NONSTRUCTURAL CHECKLIST ITEMS MARKED AS UNKNOWN.....	12
TABLE 4.3.1. SEISMIC UPGRADES OPINION OF PROBABLE CONSTRUCTION COSTS.....	21

## Acronyms

ADA	Americans with Disabilities Act
ASCE	American Society of Civil Engineers
BPOE	Basic Performance Objective for Existing Buildings
BSE	Basic Safety Earthquake
BU	Built-Up
CMU	Concrete Masonry Unit
CP	Collapse Prevention
DNR	Department of Natural Resources
DCR	Demand-to-Capacity Ratio
EERI	Earthquake Engineering Research Institute
EPAT	EERI Earthquake Performance Assessment Tool
FEMA	Federal Emergency Management Agency
IBC	International Building Code
ICOS	Information and Condition of Schools
IEBC	International Existing Building Code
IO	Immediate Occupancy
LS	Life Safety
MCE	Maximum Considered Earthquake
MEP	Mechanical/Electrical/Plumbing
NFPA	National Fire Protection Association
OSHA	Occupational Safety and Health Administration
OSPI	Office of the Superintendent of Public Instruction
PBEE	Performance-Based Earthquake Engineering
PR	Position Retention
ROM	Rough Order-of-Magnitude
SSSSC	School Seismic Safety Steering Committee
UBC	Uniform Building Code
USGS	United States Geological Survey
WF	Wide Flange
WGS	Washington Geological Survey

## Reference List

### Codes and References

- 2015 IBC, *2015 International Building Code*, prepared by the International Code Council, Washington, D.C.
- ASCE 7-10, 2010, *Minimum Design Loads for Buildings and Other Structures*, prepared by the Structural Engineering Institute of the American Society of Civil Engineers, Reston, Virginia.
- ASCE 31-03, 2003, *Seismic Evaluation of Existing Buildings*, prepared by the Structural Engineering Institute of the American Society of Civil Engineers, Reston, Virginia.
- ASCE 41-06, 2007, *Seismic Rehabilitation of Existing Buildings*, prepared by the Structural Engineering Institute of the American Society of Civil Engineers, Reston, Virginia.
- ASCE 41-13, 2014, *Seismic Evaluation and Retrofit of Existing Buildings*, prepared by the Structural Engineering Institute of the American Society of Civil Engineers, Reston, Virginia.
- ASCE 41-17, 2018, *Seismic Evaluation and Retrofit of Existing Buildings*, prepared by the Structural Engineering Institute of the American Society of Civil Engineers, Reston, Virginia.
- ATC-14, *Evaluating the Seismic Resistance of Existing Buildings*, prepared for Applied Technology Council by H.J. Degenkolb Associates, San Francisco, California.
- FEMA E-74, 1994, *Reducing the Risks of Nonstructural Earthquake Damage: A Practical Guide*, prepared by Wiss, Janney, Elstner Associates, Inc., under contract from the Federal Emergency Management Agency (FEMA), Washington, D.C.
- FEMA E-74-FM, 2005, *Earthquake Hazard Mitigation for Nonstructural Elements, Field Manual*, prepared by Wiss, Janney, Elstner Associates, Inc., under contract with URS Corporation for the Federal Emergency Management Agency (FEMA), Washington, D.C.
- FEMA 310, 1998, *Handbook for Seismic Evaluations of Buildings – A Prestandard*, prepared by America Society of Civil Engineers, Reston, Virginia.
- FEMA 547, 2006, *Techniques for the Seismic Rehabilitation of Existing Buildings*, prepared by Rutherford & Chekene Consulting Engineers under contract with the National Institute of Standards and Technology (NIST), funded by the Federal Emergency Management Agency (FEMA).
- NFPA 13, 2019, *Standard for the Installation of Sprinkler Systems*, prepared by National Fire Protection Association.
- FEMA P-1000, *Safer, Stronger, Smarter: A Guide to Improving School Natural Hazard Safety*. Prepared by [www.fema.gov/media-library/assets/documents/132592](http://www.fema.gov/media-library/assets/documents/132592)
- Case Studies of Successful U.S. School Seismic Screening Programs*. Prepared by EERI Staff, Members and Volunteers. [https://www.eeri.org/wp-content/uploads/SESI\\_Screening\\_BestPractices\\_Version1\\_Dec2016.pdf](https://www.eeri.org/wp-content/uploads/SESI_Screening_BestPractices_Version1_Dec2016.pdf)

*Incremental Seismic Rehabilitation of School Buildings (K-12): Providing Protection to People and Buildings (2003)*. Prepared by <https://www.fema.gov/media-library/assets/documents/5154>

FEMA E-74, *Reducing the Risks of Nonstructural Earthquake Damage*. Prepared by <https://www.fema.gov/fema-e-74-reducing-risks-nonstructural-earthquake-damage>

*FEMA Earthquake School Hazard Hunt Game and Poster*. Prepared by <https://www.fema.gov/media-library/assets/documents/90409>

*Promoting Seismic Safety: Guidance for Advocates*. Prepared by <https://www.fema.gov/media-library/assets/documents/3229>

#### Drawings

There were not drawings found at the time of this report.



# 1.0 Introduction

---

## 1.1 Background

The Washington Geological Survey (WGS), a division of the Department of Natural Resources (DNR), is conducting a seismic assessment of 222 school buildings and 5 fire stations across Washington State to better understand the current level of seismic risk of Washington State's public-school buildings. The two main components of this project are: (1) geologic site characterization, and (2) the seismic assessment of buildings. As a part of the seismic assessments, Tier 1 screening of structural systems and nonstructural assessments were performed in accordance with the American Society of Civil Engineers' (ASCE) Standard 41-17 *Seismic Evaluation and Retrofit of Existing Buildings*. Concept-level seismic upgrades were developed to address the identified deficiencies of a select number of school buildings to evaluate seismic upgrade strategies, feasibilities, and implementation costs.

Fifteen school buildings were selected in consultation with WGS and the School Seismic Safety Steering Committee (SSSSC) to receive concept-level seismic upgrade designs utilizing the ASCE 41 Tier 1 evaluation results. This report documents the concept-level seismic upgrade design for one of those school buildings. The concept-level seismic upgrades will include structural and nonstructural seismic upgrade recommendations, with concept-level sketches and rough order-of-magnitude (ROM) construction costs determined for each building. The fifteen school buildings were selected from the list of schools with the intent of representing a variety of regions, building uses, construction eras, and construction materials.

The overall goal of the project is to provide a better understanding of the current seismic risk of our state's K-12 school buildings and what needs to be done to improve the buildings in accordance with ASCE 41 to meet seismic performance objectives.

The seismic evaluation consists of a Tier 1 screening for the structural systems performed in accordance with ASCE 41-17.

## 1.2 Scope of Services

The project is being performed in several distinct and overlapping phases of work. The scope of this report is as listed in the following sections.

### 1.2.1 Information Review

1. Project Research: Reid Middleton and their project team researched available school building records, such as relevant site data and record drawings, in advance of the field investigations. This research included searching school building records and contacting the districts and/or the Office of Superintendent of Public Instruction (OSPI) to obtain building plans, seismic reports, condition reports, property records, or related construction information useful for the project.

2. Site Geologic Data: Site geological data provided by the WGS, including site shear wave velocities, was utilized to determine the project Site Class in accordance with ASCE 41, which is included in the Tier 1 checklists and concept-level seismic upgrades design work.

### 1.2.2 Field Investigations

1. Field Investigations: Each of the identified buildings was visited to observe the building's age, condition, configuration, and structural systems for the purposes of the ASCE 41 Tier 1 seismic evaluations. This task included confirmation of general information in building records or layout drawings and visual observation of the structural condition of the facilities. Engineer field reports, notes, photographs, and videos of the facilities were prepared and utilized to record and document information gathered in the field investigation work.
2. Limitations Due to Access and Worker Safety: Field observations at each site were typically performed by an individual engineer. Observation efforts were limited to areas and building elements that were readily observable and safely accessible. Observations requiring access to confined spaces, potential hazardous material exposure, access by unsecured ladder, work around energized equipment or mechanical hazards, access to areas requiring Occupational Safety and Health Administration (OSHA) fall-protection, steep or unstable slopes, deteriorated structural assemblies, or other conditions deemed potentially unsafe by the engineer were not performed. Removal of finishes (e.g., gypsum board, lathe and plaster, brick veneer, roofing materials, etc.) for access to concealed conditions or to expose elements that could not otherwise be visually observed and assessed was not performed. Material testing or sampling was not performed. The ASCE checklist items that were not documented due to access limitations are noted.

### 1.2.3 Seismic Evaluations

1. Preliminary Seismic Evaluations: Preliminary seismic assessments of the structural and nonstructural systems of the school buildings were performed in accordance with ASCE 41-17 Tier 1 Evaluation Procedures.
2. Concept-Level Designs: Further seismic evaluation work was performed to provide concept-level seismic retrofits and/or upgrade designs for the selected school buildings based on the results of the Tier 1 seismic evaluations. The concept-level seismic upgrades design work included narrative descriptions of proposed seismic retrofits and/or upgrade schemes and concept sketches depicting the extent and type of recommended structural upgrades.
3. Cost Estimating: Through the concept-level seismic upgrades design process, ProDims provided opinions of probable construction costs for the concept-level seismic upgrade designs for the selected school buildings. These concept-level seismic upgrade designs and the associated opinions of probable construction costs are intended to be

representative samples that can be extrapolated to estimate the overall capital needs of seismically upgrading Washington State schools.

#### 1.2.4 Reporting and Documentation

1. Project Reports: A preliminary seismic evaluation report on the overall Tier 1 seismic assessment of the schools will be provided to DNR/WGS and OSPI. The Tier 1 seismic evaluation of each building was documented by a standard report format that provides a summary of the structural systems of the building, Tier 1 checklist, building sketches/plans (if available), and site photographs. The reports will summarize the seismic evaluation, with concept-level seismic upgrade sketches and opinions of probable construction costs for seismic upgrades for each school building.
2. Building Photography: Photos and videos were taken of each building during on-site walkthroughs to document the existing building configurations, conditions, and structural systems.
3. Record Drawings: Record drawings and other information that was collected during the evaluation process are available for DNR/WGS, OSPI, and the school districts.

**This page intentionally left blank.**

## 2.0 Seismic Evaluation Procedures and Criteria

### 2.1 ASCE 41 Seismic Evaluation and Retrofit Overview

The current standard for seismic evaluation and retrofit (upgrades) of existing buildings is ASCE 41-17. ASCE 41 provides screening and evaluation procedures used to identify potential seismic deficiencies that may require further investigation or hazard mitigation. It presents a three-tiered review process, implemented by first following a series of predefined checklists and “quick check” structural calculations. Each successive tier is designed to perform an increasingly refined evaluation procedure for seismic deficiencies identified in previous tiers in the process. The flow chart in Figure 2.1 illustrates the evaluation process.

#### TIER 1 – Screening Phase

- Checklists of evaluation statements to quickly identify potential deficiencies
- Requires field investigation and/or review of record drawings
- Analysis limited to “Quick Checks” of global elements
- May proceed to Tier 2, Tier 3, or rehabilitation design if deficiencies are identified

#### TIER 2 – Evaluation Phase

- “Full Building” or “Deficiency Only” evaluation
- Address all Tier 1 seismic deficiencies
- Analysis more refined than Tier 1, but limited to simplified linear procedures
- Identify buildings not requiring rehabilitation

#### TIER 3 – Detailed Evaluation Phase

- Component-based evaluation of entire building using reduced ASCE 41 forces
- Advanced analytical procedures available if Tier 1 and/or Tier 2 evaluations are judged to be overly conservative
- Complex analysis procedures may result in construction savings equal to many times their cost




Figure 2-1. Flow Chart and Description of ASCE 41 Seismic Evaluation Procedure.

The Tier 1 checklists in ASCE 41 are specific to each common building type and contain seismic evaluation statements based on observed structural damage in past earthquakes. These checklists screen for potential seismic deficiencies by examining the lateral-force-resisting systems and details of construction that have historically caused poor seismic performance in similar buildings. Tier 1 screenings include basic “Quick Check” analyses for primary components of the lateral system: in this building’s case, the W2: “wood frame (commercial and industrial)”.

Tier 1 screenings also include prescriptive checks for proper seismic detailing of connections, diaphragm spans and continuity, and overall system configuration.

Tier 2 evaluations then follow with more-detailed structural and seismic calculations and assessments to either confirm the potential deficiencies identified in the Tier 1 review or demonstrate their adequacy. A Tier 3 evaluation involves an even more detailed analysis and advanced structural and seismic computations to review each structural component's seismic demand and capacity. A Tier 3 evaluation is similar in scope and complexity to the types of analyses often required to design a new building in accordance with the International Building Code (IBC), with a comprehensive analysis aimed at evaluating each component's seismic performance. Generally, Tier 3 evaluations are not practical for typical and regular-type buildings due to the rigorous and complicated calculations and procedures. As indicated in the Scope of Services, this evaluation included a Tier 1 screening of the structural systems.

## 2.2 Seismic Evaluation and Retrofit Criteria

Performance-Based Earthquake Engineering (PBEE) can be defined as the engineering of a structure to resist different levels of earthquake demand in order to meet the needs and performance objectives of building owners and other stakeholders. ASCE 41 employs a PBEE design methodology that allows building owners, design professionals, and the local building code authorities to establish seismic hazard levels and performance goals for individual buildings.

### 2.2.1 Carbonado Historical School 19 Seismicity

Seismic hazards for the United States have been quantified by the United States Geological Survey (USGS). The information has been used to create seismic hazard maps, which are currently used in building codes to determine the design-level earthquake magnitudes for building design.

The Level of Seismicity is categorized as Very Low, Low, Moderate, or High based on the probabilistic ground accelerations. Ground accelerations and mass generate inertial (seismic) forces within a building ( $\text{Force} = \text{mass} \times \text{acceleration}$ ). Ground acceleration therefore is the parameter that classifies the level of seismicity. From geographic region to region, as the ground accelerations increase, so does the level of seismicity (from low to high). Where this building is located, the design short-period spectral acceleration,  $S_{DS}$ , is 0.79 g, and the design 1-second period spectral acceleration,  $S_{D1}$  is 0.401 g. Based on ASCE 41 Table 2-4, the Level of Seismicity for this building is classified as **High**.

The ASCE 41 Basic Performance Objective for Existing Buildings (BPOE) makes use of the Basic Safety Earthquake – 1E (BSE-1E) seismic hazard level and the Basic Safety Earthquake – 2E (BSE-2E). The BSE-1E earthquake is defined by ASCE 41 as the probabilistic ground motion with a 20 percent probability of exceedance in 50 years, or otherwise characterized as a ground motion acceleration with a probabilistic 225-year return period. The BSE-2E earthquake is defined by ASCE 41 as the probabilistic ground motion with a 5 percent probability of exceedance in 50 years, or otherwise characterized as a ground motion acceleration with a



probabilistic 975-year return period. The BSE-2N seismic hazard level is the Maximum Considered Earthquake (MCE) ground motion used in current codes for the design of new buildings and is also used in ASCE 41 to classify the Level of Seismicity for a building. The BSE-2N has a statistical ground motion acceleration with 2 percent probability of exceedance in 50 years, or otherwise characterized as a ground motion acceleration with a probabilistic 2,475-year return period.

Table 2.2.1-1 provides the spectral accelerations for the 225-year, 975-year, and 2,475-year return interval events specific to Carbonado Historical School 19 that are considered in this study.

**Table 2.2.1-1. Spectral Acceleration Parameters (Not Site-Modified).**

BSE-1E 20%/50 (225-year) Event		BSE-1N 2/3 of 2,475-year Event		BSE-2E 5%/50 (975-year) Event		BSE-2N 2%/50 (2,475-year) Event	
0.2 Seconds	0.636 g	0.2 Seconds	0.811 g	0.2 Seconds	0.982 g	0.2 Seconds	1.216 g
1.0 Seconds	0.340 g	1.0 Seconds	0.46 g	1.0 Seconds	0.564 g	1.0 Seconds	0.690 g

## 2.2.2 Carbonado Historical School 19 Structural Performance Objective

The school building is a Category E – Educational (Risk Category III) structure and has not been identified as a critical structure requiring immediate use following an earthquake. However, Risk Category III buildings are structures that represent a substantial hazard to human life in the event of failure. According to ASCE 41, the BPOE for Risk Category III structures is the Damage Control structural performance level at the BSE-1E seismic hazard level and the Limited Safety structural performance level at the BSE-2E seismic hazard level. The ASCE 41 Tier 1 evaluations were conducted in accordance with ASCE 41 requirements and ASCE 41 seismic performance levels. Concept-level upgrades were developed for the **Immediate Occupancy** structural performance level at the **BSE-1N** seismic hazard level in accordance with DNR direction, the project scope of work, and the project legislative language.

At the Immediate Occupancy performance level, the structure remains safe to occupy and essentially retains its pre-earthquake strength and stiffness. Nonstructural components might be damaged to the extent that they cannot immediately function but are secured in place so that damage caused by falling, toppling, or breaking of utility connections is avoided. Life safety systems, including doors, stairways, emergency lighting, and fire alarms, generally remain available and operable, provided that power and utility services are available.

### **Knowledge Factor**

A knowledge factor,  $k$ , is an ASCE 41 prescribed factor that is used to account for uncertainty in the as-built data considering the selected Performance Objective and data collection processes (availability of existing drawings, visual observation, and level of materials testing). In-situ testing of building materials and removal of architectural finishes are outside of the scope of this study. Material properties and existing construction information were assumed since existing structural drawings were not available. If the concept design is developed further, additional

materials tests and site investigations will be required to substantiate assumptions about the existing framing systems.

### ***ASCE 41 Classified Building Type***

Use of ASCE 41 for seismic evaluations requires buildings to be classified from a group of common building types historically defined in previous seismic evaluation standards (ATC-14, FEMA 310, and ASCE 31-03). The school is classified in ASCE 41 Table 3-1 as a W2, “Wood Frame”, which means the roof is wood trusses supported by wood posts and beams. Seismic forces are resisted by flexible diaphragms, which are sheathed, and openings are framed with posts and beams.

## **2.3 Report Limitations**

The professional services described in this report were performed based on available record drawing information and limited visual observation of the structure. No other warranty is made as to the professional advice included in this report. This report provides an overview of the seismic evaluation results and does not address programming and planning issues. This report has been prepared for the exclusive use of DNR/WGS and is not intended for use by other parties, as it may not contain sufficient information for purposes of other parties or their uses.

## 3.0 Building Description & Seismic Evaluation Findings

---

### 3.1 Building Overview

#### 3.1.1 Building Description

Original Year Built: 1936  
Building Code: Unknown

Number of Stories: 2  
Floor Area: 5,700 SF

FEMA Building Type: W2  
ASCE 41 Level of Seismicity: High  
Site Class: C



#### 3.1.2 Building Use

The community gym is a timber-framed wood structure with a curved roof. The approximate footprint is 70 feet by 64 feet. There is a small kitchen, a 70-foot by 42-foot gym, a storage room, and a music room.

#### 3.1.3 Structural System

**Table 3.1.3-1. Structural System Descriptions.**

Structural System	Description
Structural Roof	The roof appears to be a curved wood-framed roof. There were no structural drawings available to confirm or contradict.
Structural Floor(s)	The second floor is wood-framed, with joists supported by beams and bearing walls. Structural drawings were not available to provide further details.
Foundations	There are no structural drawings showing the foundation. It is likely a traditional shallow system composed of continuous concrete footings under bearing walls and pads at column locations.
Gravity System	The gravity system appears to be a mixture of post and beam with some bearing walls to support the second floor joist framing.
Lateral System	Based on the time period of the construction, it is likely that the lateral system employs concentric braced frames of wood compression elements (posts and beams) with steel tension bracing.

### 3.1.4 Structural System Visual Condition

**Table 3.1.4-1. Structural System Condition Descriptions.**

<b>Structural System</b>	<b>Description</b>
Structural Roof	No visible signs of damage or deterioration.
Structural Floor(s)	No visible signs of damage or deterioration.
Foundations	Minor deterioration of the concrete.
Gravity System	No visible signs of damage or deterioration.
Lateral System	No visible signs of damage or deterioration.

## 3.2 Seismic Evaluation Findings

### 3.2.1 Structural Seismic Deficiencies

The structural seismic deficiencies identified during the Tier 1 evaluation are summarized below. Commentary for each deficiency is provided based on this evaluation.

**Table 3.2.1-1. Identified Structural Seismic Deficiencies Based on Tier 1 Checklists.**

<b>Deficiency</b>	<b>Description</b>
Load Path	The load path could not be verified during site visit; however based on the era of construction, there are likely gaps in the load path, specifically relating to positive anchorage to the foundations.
Ties Between Foundation Elements	Ties could not be verified during site visit; however based on the era of construction, there does not appear to be a slab on grade or other element to adequately brace the foundation elements.
Walls Connected Through Floors	Based on the era of construction, it is unlikely that there are sufficiently detailed positive connections to transfer the expected overturning and shear forces.
Wood Posts	Based on the era of construction, it is unlikely that there are sufficiently detailed positive connections to transfer the expected overturning and shear forces.
Wood Sills	Based on the era of construction, it is unlikely there are sufficient bolts, if any, to resist the shearing forces.
Straight Sheathing	Based on the era of construction, it is likely the roof diaphragm is straight-sheathed and the aspect ratio appears to exceed 2:1.

### 3.2.2 Structural Checklist Items Marked as “U”nknown

Where building structural component seismic adequacy was unknown due to lack of available information or limited observation, the structural checklist items were marked as “unknown”. These items require further investigation if definitive determination of compliance or noncompliance is desired. The unknown structural checklist items identified during the Tier 1 evaluation are summarized below. Commentary for each unknown item is provided based on the evaluation.

**Table 3.2.2-1. Identified Structural Checklist Items Marked as Unknown.**

<b>Unknown Item</b>	<b>Description</b>
Liquefaction	The liquefaction potential of site soils is unknown at this time given available information. “Very low to low” liquefaction potential is identified per ICOS based on state geologic mapping. Requires further investigation by a licensed geotechnical engineer to determine liquefaction potential.
Slope Failure	Requires further investigation by a licensed geotechnical engineer to determine susceptibility to slope failure. The structure appears to be located on a relatively flat site.
Surface Fault Rupture	Requires further investigation by a licensed geotechnical engineer to determine whether site is near locations of expected surface fault ruptures.
Girder-Column Connection	Items could not be visually verified during site visit and should be further investigated.
Wood Sill Bolts	Items could not be visually verified during site visit and should be further investigated.
Diaphragm Continuity	Items could not be visually verified during site visit and should be further investigated.
Roof Chord Continuity	Items could not be visually verified during site visit and should be further investigated.
Diagonally Sheathed and Unblocked Diaphragms	Items could not be visually verified during site visit and should be further investigated.

### 3.2.3 Nonstructural Seismic Deficiencies

The nonstructural seismic deficiencies identified during the Tier 1 evaluation are summarized below. Commentary for each deficiency is provided based on this evaluation. Some nonstructural deficiencies may be able to be mitigated by school district staff. Other nonstructural components that require substantial mitigation may be more appropriately included

in a long-term mitigation strategy. Some typical conceptual details for the seismic upgrade of nonstructural components can be found in the FEMA E-74 Excerpts appendix.

**Table 3.2.3-1. Identified Nonstructural Seismic Deficiencies based on Tier 1 Checklists.**

<b>Deficiency</b>	<b>Description</b>
LSS-3 Emergency Power	Presence of life safety systems not visually verified during site visit. Due to age of construction, assumed to be nonexistent or noncompliant. Evaluation of emergency power equipment may be appropriate to mitigate seismic risk.
CF-2 Tall Narrow Contents	Some contents appear to be noncompliant. Brace tops of shelving taller than 6 feet to nearest backing wall; provide overturning base restraint.
CF-3 Fall- Prone Contents	Some items in the storage room appear to be noncompliant. Heavy items on upper shelves should be restrained by netting or cabling to avoid falling hazards.

### 3.2.4 Nonstructural Checklist Items Marked as “U”nknown

Where building nonstructural component seismic adequacy was unknown due to lack of available information or limited observation, the nonstructural checklist items were marked as “unknown”. These items require further investigation if definitive determination of compliance or noncompliance is desired. The unknown nonstructural checklist items identified during the Tier 1 evaluation are summarized below. Commentary for each unknown item is provided based on the evaluation.

Some nonstructural deficiencies may be able to be mitigated by school district staff. Other nonstructural components that require substantial mitigation may be more appropriately included in a long-term mitigation strategy. Some typical conceptual details for the seismic upgrade of nonstructural components can be found in the FEMA E-74 Excerpts appendix.

**Table 3.2.4-1. Identified Nonstructural Checklist Items Marked as Unknown.**

<b>Deficiency</b>	<b>Description</b>
LSS-4 Stair and Smoke Ducts	Item not visually verified during site visit. Assumed to be noncompliant due to year of original construction. Further investigation may be appropriate to mitigate seismic risk.
HM-2 Hazardous Material	Unknown whether the building has hazardous materials. Maintenance and facility staff should verify presence of hazardous materials to mitigate seismic risk.



**Table 3.2.4-1. Identified Nonstructural Checklist Items Marked as Unknown.**

<b>Deficiency</b>	<b>Description</b>
C-1 Suspended Lath and Plaster	Items could not be visually verified during site visit. Further investigation may be appropriate to mitigate seismic risk, especially at paths of egress.
PCOA-2 Canopies	Items could not be verified during site visit and there is insufficient data from the existing drawings to confirm. Further investigation may be appropriate to mitigate seismic risk.
S-2 Stair Details	Items could not be verified during site visit and there is insufficient data from the existing drawings to confirm. Further investigation may be appropriate to mitigate seismic risk.

**This page intentionally left blank.**

## 4.0 Conclusion and Recommendations

---

### 4.1 Seismic-Structural Upgrade Recommendations

This section outlines recommendations of conceptual upgrades that would address the identified deficiencies in the seismic lateral-force-resisting system. The sketches in Appendix B illustrate the concepts introduced here.

This report outlines a single alternative out of many potential options and is based on the Tier 1 Rapid Screening, which is a preliminary evaluation and analysis. Before any retrofit scheme is selected, the final design should be based on more detailed evaluation and analysis. Such an analysis should consider the current and future performance goals of the facility.

#### 4.1.1 Building Load Path Upgrades

There are a number of items to be addressed to remedy the potential lateral load path gaps. First, upgrade the second-floor and roof diaphragms. Second, upgrade the exterior and three interior walls. Finally, a number of connections will require upgrading. These three groups of upgrades are discussed in greater detail in the next sections.

The primary framing elements of the roof are visible, despite being wrapped in drywall, near the ends at both low sides of the building. These elements appear to be the bottom chords of a wood timber truss. These trusses are likely supported by timber posts, which are braced perpendicularly by additional framing. While these elements are not necessarily principal components of the lateral system, there needs to be positive connections between the girder-to-column connections, which would extend to the chords of trusses to their supports. Steel bracket connections will need to be added at all these locations.

#### 4.1.2 Roof and Second-Floor Diaphragms

The roof and second-floor diaphragms need to be sheathed with APA-rated wood panels. This will require the roof finishes to be completely removed, down to the existing roof structure. At this time, the chords along the eaves will need to be modified to ensure continuity along the length of the diaphragm edges. This upgrade will likely involve metal strapping along the exterior and steel tension rods, at the interior side of the disrupted chord elements.

Similar upgrades must be made to the second-floor diaphragm. One difference, however, is that the second-floor diaphragm currently has an aspect ratio of approximately 4:1 or greater. To reduce this ratio to a permitted level, the first-story transverse walls at the kitchen and storage rooms should be engaged as shear walls.

Roof diaphragms must be connected to the walls to prevent separation of either element. These connections are generally spaced at 4 feet on center along each exterior edge of the diaphragm. These connections at wood structures often include tension rods, hold-downs, and timber blocking.

### 4.1.3 Shear Walls

The exterior walls and three interior walls need to be upgraded to shear walls by sheathing them with APA-rated wood panels. As it is likely the exterior walls are timber framed, these shear panels will need to be blocked with additional wood blocking.

The shear walls at the second floor must be positively connected to the elements at the first floor. This can be accomplished by installing straps or tension rods at the boundary elements of the upper-story shear walls and installing supporting members directly below in the first story.

Along the sill plates of all the first-story shear walls, anchor bolt connections will need to be added that meet the minimum anchor bolt size and spacing requirements. First-story walls that are not identified as part of the lateral system also need to have anchor bolts installed that meet minimum requirements.

### 4.1.4 Foundation Systems

Nothing is known about the existing foundation. It is likely a traditional shallow foundation with continuous footings at the walls and pad footings under major columns. In addition to the anchorage of the sill plates to the foundations, all posts need to be positively anchored to the foundations. This involves installing steel clips or brackets that bolt or screw to the posts and bolt to the foundations below.

If the presence of ties between foundation elements cannot be confirmed and these ties are deemed necessary, they will need to be installed. This will likely require removing swaths of the existing floor to trench in new grade beams between existing foundation elements. The removed structure would then need to be reinstalled.

## 4.2 Nonstructural Upgrade Recommendations

Table 3.2.3-1 identifies several nonstructural deficiencies that do not meet the performance objective selected for Carbonado Historical School 19. It is recommended that these deficiencies be addressed to provide nonstructural performance consistent with the performance of the upgraded structural lateral-force-resisting system. As-built information for the existing nonstructural systems, such as fire sprinklers, mechanical ductworks, and piping, are not available for review. Only limited visual observation of the systems was performed during field investigation due to limited access or visibility to observe existing conditions. The conceptual mitigation strategies provided in this study are preliminary. The final analysis and design for seismic rehabilitation should include a detailed field investigation.

### 4.2.1 Life Safety Systems

Life safety systems are responsible for protecting and evacuating occupants of a building during emergencies or disasters. These systems include, but are not limited to, fire suppression piping, emergency lighting, and smoke control ducts in stair enclosures. Proper bracing, coupling, and clearances of fire suppression piping not only increase reliability of performance but also help

minimize the damage to pipes and sprinkler heads. This building did not appear to have any sprinkler systems.

The recommended seismic mitigation for the life safety systems are:

- Provide fire suppression system.
- Provide emergency power system.

#### **4.2.2 Hazardous Materials**

The extent of hazardous material contents in the building is unknown. The following recommendations should be implemented to prevent the release of hazardous materials:

- Breakable containers that hold hazardous material, including gas cylinders, should be restrained by latched doors, shelf lips, wires, or other methods.
- Piping or ductwork conveying hazardous materials should be braced or otherwise protected from damage that could result in hazardous material release.
- Piping containing hazardous material, including natural gas, should have shutoff valves or other devices to limit spills or leaks.
- Hazardous material ductwork and piping, including natural gas piping, should have flexible couplings.

#### **4.2.3 Suspended Lath and Plaster Ceilings**

To mitigate heavy overhead hazards and obstructions hazards in the paths of egress, existing lath and plaster ceiling throughout the building should be removed and replaced with gypsum board drywall panels. This can be selectively phased in with future modernization work that updates other building systems.

#### **4.2.4 Contents and Furnishings**

The building contains various tall and narrow furniture, such as shelving and storage units that are freestanding away from any backing walls. This furniture is highly susceptible to toppling if not anchored properly and can become a life-safety hazard or adversely affect post-earthquake operations. The recommended seismic mitigation for tall and narrow furniture is as follows:

- Anchor storage cabinets or shelving units that are more than 6 feet high and have a height-to-depth or height-to-width ratio greater than 3-to-1 to the structure or to each other to prevent toppling during an earthquake.
- Provide bracing or restraint for equipment, stored items, or other contents weighing more than 20 pounds and with a center of mass that is more than 4 feet above the adjacent floor level.
- Fall-prone contents should be braced

#### **4.2.5 Stair Connections**

The stairs that provide access to the second floor need to be positively connected to and supported by the existing structure. In order to do this, the stringers will need to be upgraded and connections to the existing structures will need to be made.

#### **4.2.6 Architectural Considerations**

This section addresses existing construction that, while not posing specific hazards during a seismic event, would be affected by the seismic improvements proposed.

For any remodel project of an existing building, the International Existing Building Code (IEBC) would be applicable. The intent of the IEBC is to provide flexibility to permit the use of alternative approaches to achieve compliance with minimum requirements to safeguard the public health, safety, and welfare insofar as they are affected by the work being done. Elements of the exterior building envelope being affected by the seismic work would also be required to be brought up to the current Washington State Energy Code per Chapter 5, where applicable.

It should also be noted that as a part of any upgrade to existing buildings, the IEBC will require that any altered primary function spaces (classrooms, gyms, entrances, offices) and routes to these spaces, be made accessible to current accessibility standards per the American with Disabilities Act (ADA), unless technically infeasible. This would include, but is not limited to: accessible restrooms, paths of travel, entrances and exits, parking, signage, fire alarm system, etc. Under no circumstances should the facility be made less accessible. The IEBC does however have exceptions for areas that do not contain a primary function (storage room, utility rooms) and states that costs of providing the accessible route are not required to exceed 20 percent of the costs of the alterations affecting the area of Primary Function. As with any major renovation and modernization, an ADA study would be recommended to determine the extent to which an existing facility needs to be improved to be in compliance with the ADA.

#### ***Ceiling Access and Lighting Fixtures***

For implementing the recommended seismic upgrades, removal of the existing plaster and acoustic ceiling tiles at the gym would be required to gain access to the underside of the roof deck for installation of blocking. Another option would be to replace the plaster and acoustic tiles with Tectum acoustic panels suspended below the trusses. Where existing suspended T-bar ceilings occur below upgraded areas, it would also need to be removed and reinstalled with new T-bar in order to gain access to the underside of the roof and floor diaphragms for blocking installation.

The existing ceiling-mounted light fixtures in the gym have open bare bulbs. These will need to be replaced with new shielded light fixtures to protect occupants below from falling glass should the fluorescent bulbs break.



### ***Interior Shear Wall Upgrades***

Existing interior walls that are to be upgraded to shear walls will need to have the drywall removed on one side in order to install new plywood and seismic connections. New drywall will be installed and finished over the wood shear wall panels. Openings in the new shear walls for electrical outlets, switches, etc., need to be modified to accommodate the new wall dimension. Hollow metal door frames in the shear walls will need to be replaced to accommodate the thicker wall dimensions. In order to gain access to the foundation on the interior side of the exterior wall, a portion of the existing maple gym flooring and sub flooring will need to be removed and rebuilt after the foundation work is completed. The gym flooring running perpendicular to the walls will need to be removed and new maple wood flooring re-stitched with the existing.

### ***Exterior Shear Walls***

In order to install new wood shear wall panels at the exterior, the existing exterior sheathing will need to be removed down to the studs to install the shear panel blocking and anchors at the roof, floor, and foundations. Installing new exterior skin consisting of a weather barrier, rainscreen capillary break material, and wood panel and batten siding is recommended. Since there is no mention of any existing insulation, fiberglass batt insulation installed in exterior walls to the full depth of the wood studs is recommended.

### ***Shear Wall Sill Plate Anchorage***

In order to gain access to the shear wall sill plates on the interior side of the exterior wall, a portion of the existing maple gym flooring and sub flooring will need to be removed and rebuilt after the foundation work is completed. The gym flooring running perpendicular to the walls will need to be removed and new maple wood flooring re-stitched with the existing.

### ***Floor Diaphragm Upgrades***

Installation of a new floor diaphragm at the second floor will require the removal of all existing floor finishes. New flooring products will be installed on the new floor diaphragm. Doors and frames will need to be modified and undercut for new floor height.

### ***Exterior Roof Diaphragm***

For installation of the roof diaphragm, the existing roofing will need to be removed and a new roof installed over the new roof deck material. Due to the vaulted nature of the roof, a PVC or TPO single-ply roofing material is recommended. If the existing insulation is above the deck, the insulation would need to be increased to an R-38 rigid insulation per the Washington State Energy Code.

## **4.2.7 Mechanical/Electrical/Plumbing (MEP) Systems**

The main seismic concerns for mechanical equipment, ducting, and piping are sliding, swinging, and overturning. Inadequate lateral restraint or anchorage can shift equipment off its supports or topple equipment to the ground or onto other equipment. Inadequate bracing of piping and

ducting, or the inability for piping to tolerate differential movement from the equipment it is attached to, can damage or dislodge connections. Such damage in fluid piping can potentially lead to major leaks or loss and disruption by damaging contents. The recommended seismic mitigation for MEP systems is:

- Provide seismic bracing for equipment that weighs more than 20 pounds, has a center of mass more than 4 feet above the adjacent floor level, and is not in-line equipment.

### 4.3 Opinion of Conceptual Construction Costs

A preliminary opinion of probable construction costs to perform the concept-level seismic upgrade recommendations provided in this report is included in Appendix C. The input for these preliminary probable costs are the Tier 1 checklists and the preliminary concept-level seismic upgrades design recommendations and sketches. These preliminary concept-level design sketches depict a design concept that could be implemented to improve the seismic safety of the building structure. It is important to note that this preliminary seismic upgrades design concept is based on the results of the Tier 1 seismic screening checklists and engineering design judgement and has not been substantiated by detailed structural analyses and calculations. Consequently, the costs presented in this concept-level design report are very preliminary in nature and are only intended to be utilized in their aggregate form with the entire statewide school seismic safety assessments study.

For this preliminary opinion of probable construction costs, an estimate of the current year (2019) construction costs of the probable scope of work was developed. These costs were developed based on the Tier 1 checklist, concept-level seismic upgrade design sketches, and project narratives. Then a -20 percent (low) to +50 percent (high) range variance was used to develop the construction cost estimate range for the concept-level scope of work. The -20 percent to +50 percent range variance guidance is from Table 1 of the AACE International Recommended Practice 56R-08, *Cost Estimate Classification System for Class 5 Estimates*. The variable cost range of a Class 5 estimate is due to the limited design completeness and is defined as 0 percent to 2 percent Project Definition Deliverables.

The estimated structural and nonstructural construction cost to mitigate the deficiencies identified in the Tier 1 checklists of the Carbonado Historical School No. 19 Community Gym ranges between \$600,000 and \$1.1M (-20 percent/+50 percent). The estimated construction cost to seismically upgrade this building is \$750,000. On a per-square-foot basis, the seismic upgrade construction cost is estimated to be approximately \$137 per square foot in 2019 dollars, with a variance range between \$110 per square foot and \$206 per square foot.

This preliminary opinion of construction cost includes labor, materials, equipment, and general contractor general conditions (mobilization), overhead, and profit. This is based on a public sector design-bid-build project delivery method. Project delivery methods such as negotiated, State of Washington GC/CM, and design-build are not the basis of the construction costs. Owner's project costs not included in the construction cost estimate are building permits, design fees, change order contingencies, escalation at a recommended 4.1 percent\* per year to the midpoint of construction (currently unknown), materials testing/inspection, project planning and

design schedule delay contingencies, and owner’s overall project contingency. Additional owner’s project costs would likely include owner’s general overhead costs, including project management, financing/bond costs, administration/contract/accounting costs, review of plans, value engineering studies, equipment, fixtures, furnishings and technology, and relocation of the school staff and students during construction. These additional costs are not included in this preliminary concept-level design construction cost estimate.

Costs of all types excluded from the construction costs are site work, construction of replacement facilities, and mitigation of seismic risks for existing facilities and building code changes that occur over time after this report. Future planning budgets should not be set on the basis of the preliminary construction costs estimate based on the concept-level design ideas presented in this report. For budget planning purposes, it is highly recommended that a seismic upgrade budget be determined after the owner defines the scope of work and obtains the services of an A/E design team to study the proposed seismic mitigation strategies and to refine the concept-level seismic upgrades design approach contained in this report.

\*-4.1%/year escalation rate for planning purposes should be compounded annually to the midpoint of construction and is sourced from *Engineering News Record (ENR)*, November, 2017, the most recent rate representative of the escalation of construction costs throughout the state of Washington.

**Table 4.3.1. Seismic Upgrades Opinion of Probable Construction Costs.**

Building	FEMA Bldg Type	ASCE 41 Level of Seismicity / Site Class	Structural Performance Objective	Bldg Gross Area	Estimated Seismic Upgrade Cost Range \$/SF (Total)		Estimated Seismic Upgrade Cost/SF (Total)	
Carbonado Historical School 19, Gym	W2	High / C	<b>Structural</b>					
			Immediate Occupancy	5,700 SF	\$82 (\$465K)	- (\$871K)	\$153 (\$153K)	\$102 (\$581K)
			<b>Nonstructural</b>					
			Life Safety	5,700 SF	\$28 (\$128K)	- (\$239K)	\$53 (\$53K)	\$35 (\$159K)
			<b>Total</b>					
				5,700 SF	\$110 (\$593K)	- (\$1.11M)	\$206 (\$206K)	\$137 (\$740K)

W: Wood-Framed; URM: Unreinforced Masonry; RM: Reinforced Masonry; C: Reinforced Concrete; PC: Precast concrete; S: Steel-framed

**This page intentionally left blank.**

# Appendix A: Field Investigation Report and Tier 1 Checklists

**This page intentionally left blank.**

# 1. Carbonado, Carbonado Historical School 19, B - Community Gym

## 1.1 Building Description

Building Name:	B - Community Gym
Facility Name:	Carbonado Historical School 19
District Name:	Carbonado
ICOS Latitude:	47.081
ICOS Longitude:	-122.054
ICOS County/District ID:	27019
ICOS Building ID:	11276
ASCE 41 Bldg Type:	W2
Enrollment:	179
Gross Sq. Ft. :	5,700
Year Built:	1936
Number of Stories:	2
S <sub>XS</sub> BSE-2E:	0.897
S <sub>X1</sub> BSE-2E:	0.475
ASCE 41 Level of Seismicity:	High
Site Class:	C
V <sub>S30</sub> (m/s):	411
Liquefaction Potential:	very low to low
Tsunami Risk:	None
Structural Drawings Available:	No
Evaluating Firm:	BergerABAM/WSP



The community gym is a timber-framed wood structure with a curved roof. The approximate footprint is a 70 feet by 64 feet. There is a small kitchen, 70 foot by 42 foot gym, a storage room, and a music room.

### 1.1.1 Building Use

The structure is primarily used as a community gymnasium, but also has a small kitchen as well as a larger room on the second floor that appears to be used as a music room.

### 1.1.2 Structural System

**Table 1.1-1. Structural System Description of Carbonado Historical School 19**

<b>Structural System</b>	<b>Description</b>
Structural Roof	The roof appears to be a curved wood framed roof, however there were no structural drawings available to confirm or contradict.
Structural Floor(s)	The second floor is wood framed with joists supported by beams and bearing walls. Structural drawings were not available to provide further details.
Foundations	Although there are no structural drawings showing the foundation, it is likely that it is a traditional shallow system comprised of continuous concrete footings under bearing walls and pads at column locations.
Gravity System	The gravity system appears to be a mixture of post and beam with some bearing walls to support the second floor joist framing.
Lateral System	Based on the time period of the construction, it is likely that the lateral system employs concentric braced frames of wood compression elements (posts and beams) with steel tension bracing.

### 1.1.3 Structural System Visual Condition

**Table 1.1-2. Structural System Condition Description of Carbonado Historical School 19**

<b>Structural System</b>	<b>Description</b>
Structural Roof	No visible signs of damage or deterioration.
Structural Floor(s)	No visible signs of damage or deterioration.
Foundations	Minor deterioration of the concrete.
Gravity System	No visible signs of damage or deterioration.
Lateral System	No visible signs of damage or deterioration.



## 1.2 Seismic Evaluation Findings

### 1.2.1 Structural Seismic Deficiencies

The structural seismic deficiencies identified during the Tier 1 evaluation are summarized below. Commentary for each deficiency is also provided based on this evaluation.

**Table 1-3. Identified Structural Seismic Deficiencies for Carbonado Carbonado Historical School 19 B - Community Gym**

Deficiency	Description
Load Path	Items could not be verified during site visit, but based on the era of construction there are likely gaps in the load path, specifically relating to positive anchorage to the foundations.
Ties Between Foundation Elements	Items could not be verified during site visit, but based on the era of construction there did not appear to be a slab on grade or other element to adequately brace the foundation elements.
Walls Connected Through Floors	Items could not be visually verified during site visit, but based on the era of construction, it is unlikely that there are sufficiently detailed positive connections to transfer the expected overturning and shear forces.
Wood Posts	Items could not be visually verified during site visit, but based on the era of construction, it is unlikely that there are sufficiently detailed positive connections to transfer the expected overturning and shear forces.
Wood Sills	Items could not be visually verified during site visit, but based on the era of construction, it is unlikely there are sufficient bolts, if any, to resist the shearing forces.
Straight Sheathing	Based on the era of construction, it is likely the roof diaphragm is straight-sheathed and the aspect ratio appears to exceed 2:1.

### 1.2.2 Structural Checklist Items Marked as 'U'nknown

Where building structural component seismic adequacy was unknown due to lack of available information or limited observation, the structural checklist items were marked as “unknown”. These items require further investigation if definitive determination of compliance or noncompliance is desired. The unknown structural checklist items identified during the Tier 1 evaluation are summarized below. Commentary for each unknown item is also provided based on the evaluation.

**Table 1-4. Identified Structural Checklist Items Marked as Unknown for Carbonado Carbonado Historical School 19 B - Community Gym**

Unknown Item	Description
Liquefaction	The liquefaction potential of site soils is unknown at this time given available information. \very low to low\ liquefaction potential is identified per ICOS based on state geologic mapping. Requires further investigation by a licensed geotechnical engineer to determine liquefaction potential.
Slope Failure	Requires further investigation by a licensed geotechnical engineer to determine susceptibility to slope failure. The structure appears to be located on a relatively flat site.
Surface Fault Rupture	Requires further investigation by a licensed geotechnical engineer to determine whether site is near locations of expected surface fault ruptures.
Girder-Column Connection	Items could not be visually verified during site visit.
Wood Sill Bolts	Items could not be visually verified during site visit.
Diaphragm Continuity	Items could not be visually verified during site visit.
Roof Chord Continuity	Items could not be visually verified during site visit.
Diagonally Sheathed and Unblocked Diaphragms	Items could not be visually verified during site visit.

### 1.3.1 Nonstructural Seismic Deficiencies

The nonstructural seismic deficiencies identified during the Tier 1 evaluation are summarized below. Commentary for each deficiency is also provided based on this evaluation. Some nonstructural deficiencies may be able to be mitigated by school district staff. Other nonstructural components that require more substantial mitigation may be more appropriately included in a long-term mitigation strategy. Some typical conceptual details for the seismic upgrade of nonstructural components can be found in the FEMA E-74 Excerpts appendix.

**Table 1-5. Identified Nonstructural Seismic Deficiencies for Carbonado Carbonado Historical School 19 B - Community Gym**

Deficiency	Description
LSS-3 Emergency Power. HR-not required; LS-LMH; PR-LMH.	Presence of life safety systems not visually verified during site visit. Due to age of construction, assumed to be non-existent or non-compliant. Evaluation of emergency power equipment may be appropriate to mitigate seismic risk.
CF-2 Tall Narrow Contents. HR-not required; LS-H; PR-MH.	Some contents appear to be noncompliant. Brace tops of shelving taller than 6 feet to nearest backing wall, provide overturning base restraint.
CF-3 Fall-Prone Contents. HR-not required; LS-H; PR-H.	Some items in the storage room appear to be noncompliant. Heavy items on upper shelves should be restrained by netting or cabling to avoid falling hazards.

### 1.3.2 Nonstructural Checklist Items Marked as 'U'nknown

Where building nonstructural component seismic adequacy was unknown due to lack of available information or limited observation, the nonstructural checklist items were marked as “unknown”. These items require further investigation if definitive determination of compliance or noncompliance is desired. The unknown nonstructural checklist items identified during the Tier 1 evaluation are summarized below. Commentary for each unknown item is also provided based on the evaluation.

Some nonstructural deficiencies may be able to be mitigated by school district staff. Other nonstructural components that require more substantial mitigation may be more appropriately included in a long-term mitigation strategy. Some typical conceptual details for the seismic upgrade of nonstructural components can be found in the FEMA E-74 Excerpts appendix.

**Table 1-6. Identified Nonstructural Checklist Items Marked as Unknown for Carbonado Carbonado Historical School 19 B - Community Gym**

Unknown Item	Description
LSS-4 Stair and Smoke Ducts. HR-not required; LS-LMH; PR-LMH.	Item not visually verified during site visit, but assumed to be noncompliant due to year of original construction. Further investigation may be appropriate to mitigate seismic risk.
HM-2 Hazardous Material Storage. HR-LMH; LS-LMH; PR-LMH.	Unknown whether the building has hazardous materials. Further investigation may be appropriate to mitigate seismic risk.
C-1 Suspended Lath and Plaster. HR-H; LS-MH; PR-LMH.	Items could not be visually verified during site visit. Further investigation may be appropriate to mitigate seismic risk.
PCOA-2 Canopies. HR-not required; LS-LMH; PR-LMH.	Items could not be verified during site visit and there is insufficient data from the existing drawings to confirm. Further investigation may be appropriate to mitigate seismic risk.
S-2 Stair Details. HR-not required; LS-LMH; PR-LMH.	Items could not be verified during site visit and there is insufficient data from the existing drawings to confirm. Further investigation may be appropriate to mitigate seismic risk.

Photos:



**Figure 1-1. East facade of building**



**Figure 1-2. Example of foundation condition (SE corner of building)**



Figure 1-3. Gymnasium



Figure 1-4. Kitchen



Figure 1-5. Second floor music room






Figure 1-6. Stairs to second floor



Figure 1-7. Fall prone content and shelving that is not adequately braced



**Figure 1-8. Fall prone content and shelving that is not adequately braced**



**Figure 1-9. Example of foundations and minor deterioration of concrete**





**Figure 1-10. Fall prone items in second floor storage area**

# Carbonado, Carbonado Historical School 19, B - Community Gym

## 17-2 Collapse Prevention Basic Configuration Checklist

Building record drawings have been reviewed, when available, and a non-destructive field investigation has been performed for the subject building. Each of the required checklist items are marked Compliant (C), Noncompliant (NC), Not Applicable (N/A), or Unknown (U). Items marked Compliant indicate conditions that satisfy the performance objective, whereas items marked Noncompliant or Unknown indicate conditions that do not. Certain statements might not apply to the building being evaluated.

### Low Seismicity

#### Building System - General

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
Load Path	The structure contains a complete, well-defined load path, including structural elements and connections, that serves to transfer the inertial forces associated with the mass of all elements of the building to the foundation. (Tier 2: Sec. 5.4.1.1; Commentary: Sec. A.2.1.10)		X			Items could not be verified during site visit, but based on the era of construction there are likely gaps in the load path, specifically relating to positive anchorage to the foundations.
Adjacent Buildings	The clear distance between the building being evaluated and any adjacent building is greater than 0.25% of the height of the shorter building in low seismicity, 0.5% in moderate seismicity, and 1.5% in high seismicity. (Tier 2: Sec. 5.4.1.2; Commentary: Sec. A.2.1.2)			X		There are no structures immediately adjacent to this building.
Mezzanines	Interior mezzanine levels are braced independently from the main structure or are anchored to the seismic-force-resisting elements of the main structure. (Tier 2: Sec. 5.4.1.3; Commentary: Sec. A.2.1.3)			X		It is unlikely that the second story is framed like a mezzanine, but rather integrated with the exterior walls as a true story.

#### Building System - Building Configuration

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
Weak Story	The sum of the shear strengths of the seismic-force-resisting system in any story in each direction is not less than 80% of the strength in the adjacent story above. (Tier 2: Sec. 5.4.2.1; Commentary: Sec. A.2.2.2)	X				
Soft Story	The stiffness of the seismic-force-resisting system in any story is not less than 70% of the seismic-force-resisting system stiffness in an adjacent story above or less than 80% of the average seismic-force-resisting system stiffness of the three stories above. (Tier 2: Sec. 5.4.2.2; Commentary: Sec. A.2.2.3)	X				

Vertical Irregularities	All vertical elements in the seismic-force-resisting system are continuous to the foundation. (Tier 2: Sec. 5.4.2.3; Commentary: Sec. A.2.2.4)	X				
Geometry	There are no changes in the net horizontal dimension of the seismic-force-resisting system of more than 30% in a story relative to adjacent stories, excluding one-story penthouses and mezzanines. (Tier 2: Sec. 5.4.2.4; Commentary: Sec. A.2.2.5)	X				
Mass	There is no change in effective mass of more than 50% from one story to the next. Light roofs, penthouses, and mezzanines need not be considered. (Tier 2: Sec. 5.4.2.5; Commentary: Sec. A.2.2.6)	X				
Torsion	The estimated distance between the story center of mass and the story center of rigidity is less than 20% of the building width in either plan dimension. (Tier 2: Sec. 5.4.2.6; Commentary: Sec. A.2.2.7)			X		

**Moderate Seismicity** (Complete the Following Items in Addition to the Items for Low Seismicity)

**Geologic Site Hazards**

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
Liquefaction	Liquefaction-susceptible, saturated, loose granular soils that could jeopardize the building's seismic performance do not exist in the foundation soils at depths within 50 ft (15.2 m) under the building. (Tier 2: Sec. 5.4.3.1; Commentary: Sec. A.6.1.1)				X	The liquefaction potential of site soils is unknown at this time given available information. Very low to low liquefaction potential is identified per ICOS based on state geologic mapping. Requires further investigation by a licensed geotechnical engineer to determine liquefaction potential.
Slope Failure	The building site is located away from potential earthquake-induced slope failures or rockfalls so that it is unaffected by such failures or is capable of accommodating any predicted movements without failure. (Tier 2: Sec. 5.4.3.1; Commentary: Sec. A.6.1.2)				X	Requires further investigation by a licensed geotechnical engineer to determine susceptibility to slope failure. The structure appears to be located on a relatively flat site.
Surface Fault Rupture	Surface fault rupture and surface displacement at the building site are not anticipated. (Tier 2: Sec. 5.4.3.1; Commentary: Sec. A.6.1.3)				X	Requires further investigation by a licensed geotechnical engineer to determine whether site is near locations of expected surface fault ruptures.

**High Seismicity** (Complete the Following Items in Addition to the Items for Low and Moderate Seismicity)

**Foundation Configuration**

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
Overturning	The ratio of the least horizontal dimension of the seismic-force-resisting system at the foundation level to the building height (base/height) is greater than 0.6Sa. (Tier 2: Sec. 5.4.3.3; Commentary: Sec. A.6.2.1)	X				
Ties Between Foundation Elements	The foundation has ties adequate to resist seismic forces where footings, piles, and piers are not restrained by beams, slabs, or soils classified as Site Class A, B, or C. (Tier 2: Sec. 5.4.3.4; Commentary: Sec. A.6.2.2)		X			Items could not be verified during site visit, but based on the era of construction there did not appear to be a slab on grade or other element to adequately brace the foundation elements.

## 17-6 Collapse Prevention Structural Checklist for Building Type W2

Building record drawings have been reviewed, when available, and a non-destructive field investigation has been performed for the subject building. Each of the required checklist items are marked Compliant (C), Noncompliant (NC), Not Applicable (N/A), or Unknown (U). Items marked Compliant indicate conditions that satisfy the performance objective, whereas items marked Noncompliant or Unknown indicate conditions that do not. Certain statements might not apply to the building being evaluated.

### Low and Moderate Seismicity

#### Seismic-Force-Resisting System

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
Redundancy	The number of lines of shear walls in each principal direction is greater than or equal to 2. (Tier 2: Sec. 5.5.1.1; Commentary: Sec. A.3.2.1.1)	X				
Shear Stress Check	The shear stress in the shear walls, calculated using the Quick Check procedure of Section 4.4.3.3, is less than the following values: Structural panel sheathing – 1,000 lb/ft; Diagonal sheathing – 700 lb/ft; Straight sheathing – 100 lb/ft; All other conditions – 100 lb/ft. (Tier 2: Sec. 5.5.3.1.1; Commentary: Sec. A.3.2.7.1)	X				
Stucco (Exterior Plaster) Shear Walls	Multi-story buildings do not rely on exterior stucco walls as the primary seismic-force-resisting system. (Tier 2: Sec. 5.5.3.6.1; Commentary: Sec. A.3.2.7.2)			X		
Gypsum Wallboard or Plaster Shear Walls	Interior plaster or gypsum wallboard is not used for shear walls on buildings more than one story high with the exception of the uppermost level of a multi-story building. (Tier 2: Sec. 5.5.3.6.1; Commentary: Sec. A.3.2.7.3)	X				
Narrow Wood Shear Walls	Narrow wood shear walls with an aspect ratio greater than 2-to-1 are not used to resist seismic forces. (Tier 2: Sec. 5.5.3.6.1; Commentary: Sec. A.3.2.7.4)			X		
Walls Connected Through Floors	Shear walls have an interconnection between stories to transfer overturning and shear forces through the floor. (Tier 2: Sec. 5.5.3.6.2; Commentary: Sec. A.3.2.7.5)		X			Items could not be visually verified during site visit, but based on the era of construction, it is unlikely that there are sufficiently detailed positive connections to transfer the expected overturning and shear forces.

Hillside Site	For structures that are taller on at least one side by more than one-half story because of a sloping site, all shear walls on the downhill slope have an aspect ratio less than 1-to-1. (Tier 2: Sec. 5.5.3.6.3; Commentary: Sec. A.3.2.7.6)				X	
Cripple Walls	Cripple walls below first-floor-level shear walls are braced to the foundation with wood structural panels. (Tier 2: Sec. 5.5.3.6.4; Commentary: Sec. A.3.2.7.7)				X	
Openings	Walls with openings greater than 80% of the length are braced with wood structural panel shear walls with aspect ratios of not more than 1.5-to-1 or are supported by adjacent construction through positive ties capable of transferring the seismic forces. (Tier 2: Sec. 5.5.3.6.5; Commentary: Sec. A.3.2.7.8)				X	

**Connections**

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
Wood Posts	There is a positive connection of wood posts to the foundation. (Tier 2: Sec. 5.7.3.3; Commentary: Sec. A.5.3.3)		X			Items could not be visually verified during site visit, but based on the era of construction, it is unlikely that there are sufficiently detailed positive connections to transfer the expected overturning and shear forces.
Wood Sills	All wood sills are bolted to the foundation. (Tier 2: Sec. 5.7.3.3; Commentary: Sec. A.5.3.4)		X			Items could not be visually verified during site visit, but based on the era of construction, it is unlikely there are sufficient bolts, if any, to resist the shearing forces.
Girder-Column Connection	There is a positive connection using plates, connection hardware, or straps between the girder and the column support. (Tier 2: Sec. 5.7.4.1; Commentary: Sec. A.5.4.1)				X	Items could not be visually verified during site visit.

**High Seismicity** (Complete the Following Items in Addition to the Items for Low & Moderate Seismicity)

**Connections**

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
Wood Sill Bolts	Sill bolts are spaced at 6 ft (1.8 m) or less with acceptable edge and end distance provided for wood and concrete. (Tier 2: Sec. 5.7.3.3; Commentary: Sec. A.5.3.7)				X	Items could not be visually verified during site visit.

**Diaphragms**

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
-----------------	----------------------	---	----	-----	---	---------

Diaphragm Continuity	The diaphragms are not composed of split-level floors and do not have expansion joints. (Tier 2: Sec. 5.6.1.1; Commentary: Sec. A.4.1.1)				X	Items could not be visually verified during site visit.
Roof Chord Continuity	All chord elements are continuous, regardless of changes in roof elevation. (Tier 2: Sec. 5.6.1.1; Commentary: Sec. A.4.1.3)				X	Items could not be visually verified during site visit.
Diaphragm Reinforcement at Openings	There is reinforcing around all diaphragm openings larger than 50% of the building width in either major plan dimension. (Tier 2: Sec. 5.6.1.5; Commentary: Sec. A.4.1.8)			X		
Straight Sheathing	All straight-sheathed diaphragms have aspect ratios less than 2-to-1 in the direction being considered. (Tier 2: Sec. 5.6.2; Commentary: Sec. A.4.2.1)		X			Based on the era of construction, it is likely the roof diaphragm is straight-sheathed and the aspect ratio appears to exceed 2:1.
Spans	All wood diaphragms with spans greater than 24 ft (7.3 m) consist of wood structural panels or diagonal sheathing. (Tier 2: Sec. 5.6.2; Commentary: Sec. A.4.2.2)			X		Although structural drawings were not found, based on the geometry and likely construction of this structure, it's likely that it does not comply with this condition.
Diagonally Sheathed and Unblocked Diaphragms	All diagonally sheathed or unblocked wood structural panel diaphragms have horizontal spans less than 40 ft (12.2 m) and have aspect ratios less than or equal to 4-to-1. (Tier 2: Sec. 5.6.2; Commentary: Sec. A.4.2.3)				X	Items could not be visually verified during site visit.
Other Diaphragms	The diaphragms do not consist of a system other than wood, metal deck, concrete, or horizontal bracing. (Tier 2: Sec. 5.6.5; Commentary: Sec. A.4.7.1)	X				

# Carbonado, Carbonado Historical School 19, B - Community Gym

## 17-38 Nonstructural Checklist

Notes:

C = Compliant, NC = Noncompliant, N/A = Not Applicable, and U = Unknown.

Performance Level: HR = Hazards Reduced, LS = Life Safety, and PR = Position Retention.

Level of Seismicity: L = Low, M = Moderate, and H = High

### Life Safety Systems

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
LSS-1 Fire Suppression Piping. HR-not required; LS-LMH; PR-LMH.	Fire suppression piping is anchored and braced in accordance with NFPA-13. (Tier 2: Sec. 13.7.4; Commentary: Sec. A.7.13.1)			X		No fire suppression system.
LSS-2 Flexible Couplings. HR-not required; LS-LMH; PR-LMH.	Fire suppression piping has flexible couplings in accordance with NFPA-13. (Tier 2: Sec. 13.7.4; Commentary: Sec. A.7.13.2)			X		
LSS-3 Emergency Power. HR-not required; LS-LMH; PR-LMH.	Equipment used to power or control Life Safety systems is anchored or braced. (Tier 2: Sec. 13.7.7; Commentary: Sec. A.7.12.1)		X			Presence of life safety systems not visually verified during site visit. Due to age of construction, assumed to be non-existent or non-compliant. Evaluation of emergency power equipment may be appropriate to mitigate seismic risk.
LSS-4 Stair and Smoke Ducts. HR-not required; LS-LMH; PR-LMH.	Stair pressurization and smoke control ducts are braced and have flexible connections at seismic joints. (Tier 2: Sec. 13.7.6; Commentary: Sec. A.7.14.1)				X	Item not visually verified during site visit, but assumed to be noncompliant due to year of original construction. Further investigation may be appropriate to mitigate seismic risk.
LSS-5 Sprinkler Ceiling Clearance. HR-not required; LS-MH; PR-MH.	Penetrations through panelized ceilings for fire suppression devices provide clearances in accordance with NFPA-13. (Tier 2: Sec. 13.7.4; Commentary: Sec. A.7.13.3)			X		
LSS-6 Emergency Lighting. HR-not required; LS-not required; PR-LMH	Emergency and egress lighting equipment is anchored or braced. (Tier 2: Sec. 13.7.9; Commentary: Sec. A.7.3.1)			X		Not required for Life Safety Performance Level

### Hazardous Materials

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
HM-1 Hazardous Material Equipment. HR-LMH; LS-LMH; PR-LMH.	Equipment mounted on vibration isolators and containing hazardous material is equipped with restraints or snubbers. (Tier 2: Sec. 13.7.1; Commentary: Sec. A.7.12.2)			X		No equipment containing hazardous materials found during site visit.



HM-2 Hazardous Material Storage. HR-LMH; LS-LMH; PR-LMH.	Breakable containers that hold hazardous material, including gas cylinders, are restrained by latched doors, shelf lips, wires, or other methods. (Tier 2: Sec. 13.8.3; Commentary: Sec. A.7.15.1)				X	Unknown whether the building has hazardous materials. Further investigation may be appropriate to mitigate seismic risk.
HM-3 Hazardous Material Distribution. HR-MH; LS-MH; PR-MH.	Piping or ductwork conveying hazardous materials is braced or otherwise protected from damage that would allow hazardous material release. (Tier 2: Sec. 13.7.3, 13.7.5; Commentary: Sec. A.7.13.4)				X	Did not observe any piping or ductwork conveying hazardous materials.
HM-4 Shutoff Valves. HR-MH; LS-MH; PR-MH.	Piping containing hazardous material, including natural gas, has shutoff valves or other devices to limit spills or leaks. (Tier 2: Sec. 13.7.3, 13.7.5; Commentary: Sec. A.7.13.3)				X	
HM-5 Flexible Couplings. HR-LMH; LS-LMH; PR-LMH.	Hazardous material ductwork and piping, including natural gas piping, have flexible couplings. (Tier 2: Sec. 13.7.3, 13.7.5; Commentary: Sec. A.7.15.4)				X	
HM-6 Piping or Ducts Crossing Seismic Joints. HR-MH; LS-MH; PR-MH.	Piping or ductwork carrying hazardous material that either crosses seismic joints or isolation planes or is connected to independent structures has couplings or other details to accommodate the relative seismic displacements. (Tier 2: Sec. 13.7.3, 13.7.5, 13.7.6; Commentary: Sec. A.7.13.6)				X	

### Partitions

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
P-1 Unreinforced Masonry. HR-LMH; LS-LMH; PR-LMH.	Unreinforced masonry or hollow-clay tile partitions are braced at a spacing of at most 10 ft (3.0 m) in Low or Moderate Seismicity, or at most 6 ft (1.8 m) in High Seismicity. (Tier 2: Sec. 13.6.2; Commentary: Sec. A.7.1.1)			X		
P-2 Heavy Partitions Supported by Ceilings. HR-LMH; LS-LMH; PR-LMH.	The tops of masonry or hollow-clay tile partitions are not laterally supported by an integrated ceiling system. (Tier 2: Sec. 13.6.2; Commentary: Sec. A.7.2.1)			X		
P-3 Drift. HR-not required; LS-MH; PR-MH.	Rigid cementitious partitions are detailed to accommodate the following drift ratios: in steel moment frame, concrete moment frame, and wood frame buildings, 0.02; in other buildings, 0.005. (Tier 2: Sec. 13.6.2; Commentary: Sec. A.7.1.2)			X		
P-4 Light Partitions Supported by Ceilings. HR-not required; LS-not required; PR-MH.	The tops of gypsum board partitions are not laterally supported by an integrated ceiling system. (Tier 2: Sec. 13.6.2; Commentary: Sec. A.7.2.1)			X		

P-5 Structural Separations. HR-not required; LS-not required; PR-MH.	Partitions that cross structural separations have seismic or control joints. (Tier 2: Sec. 13.6.2; Commentary: Sec. A.7.1.3)			X		
P-6 Tops. HR-not required; LS-not required; PR-MH.	The tops of ceiling-high framed or panelized partitions have lateral bracing to the structure at a spacing equal to or less than 6 ft (1.8 m). (Tier 2: Sec. 13.6.2; Commentary: Sec. A.7.1.4)			X		Not required for Life Safety Performance Level

**Ceilings**

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
C-1 Suspended Lath and Plaster. HR-H; LS-MH; PR-LMH.	Suspended lath and plaster ceilings have attachments that resist seismic forces for every 12 ft <sup>2</sup> (1.1 m <sup>2</sup> ) of area. (Tier 2: Sec. 13.6.4; Commentary: Sec. A.7.2.3)				X	Items could not be visually verified during site visit. Further investigation may be appropriate to mitigate seismic risk.
C-2 Suspended Gypsum Board. HR-not required; LS-MH; PR-LMH.	Suspended gypsum board ceilings have attachments that resist seismic forces for every 12 ft <sup>2</sup> (1.1 m <sup>2</sup> ) of area. (Tier 2: Sec. 13.6.4; Commentary: Sec. A.7.2.3)			X		
C-3 Integrated Ceilings. HR-not required; LS-not required; PR-MH.	Integrated suspended ceilings with continuous areas greater than 144 ft <sup>2</sup> (13.4 m <sup>2</sup> ) and ceilings of smaller areas that are not surrounded by restraining partitions are laterally restrained at a spacing no greater than 12 ft (3.6 m) with members attached to the structure above. Each restraint location has a minimum of four diagonal wires and compression struts, or diagonal members capable of resisting compression. (Tier 2: Sec. 13.6.4; Commentary: Sec. A.7.2.2)			X		
C-4 Edge Clearance. HR-not required; LS-not required; PR-MH.	The free edges of integrated suspended ceilings with continuous areas greater than 144 ft <sup>2</sup> (13.4 m <sup>2</sup> ) have clearances from the enclosing wall or partition of at least the following: in Moderate Seismicity, 1/2 in. (13 mm); in High Seismicity, 3/4 in. (19 mm). (Tier 2: Sec. 13.6.4; Commentary: Sec. A.7.2.4)			X		
C-5 Continuity Across Structure Joints. HR-not required; LS-not required; PR-MH.	The ceiling system does not cross any seismic joint and is not attached to multiple independent structures. (Tier 2: Sec. 13.6.4; Commentary: Sec. A.7.2.5)			X		
C-6 Edge Support. HR-not required; LS-not required; PR-H.	The free edges of integrated suspended ceilings with continuous areas greater than 144 ft <sup>2</sup> (13.4 m <sup>2</sup> ) are supported by closure angles or channels not less than 2 in. (51 mm) wide. (Tier 2: Sec. 13.6.4 ; Commentary: Sec. A.7.2.6)			X		Not required for Life Safety Performance Level

C-7 Seismic Joints. HR-not required; LS-not required; PR-H.	Acoustical tile or lay-in panel ceilings have seismic separation joints such that each continuous portion of the ceiling is no more than 2,500 ft <sup>2</sup> (232.3 m <sup>2</sup> ) and has a ratio of long-to-short dimension no more than 4-to-1. (Tier 2: Sec. 13.6.4; Commentary: Sec. A.7.2.7)			X		
---	--	--	--	---	--	--

### Light Fixtures

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
LF-1 Independent Support. HR-not required; LS-MH; PR-MH.	Light fixtures that weigh more per square foot than the ceiling they penetrate are supported independent of the grid ceiling suspension system by a minimum of two wires at diagonally opposite corners of each fixture. (Tier 2: Sec. 13.6.4, 13.7.9; Commentary: Sec. A.7.3.2)			X		
LF-2 Pendant Supports. HR-not required; LS-not required; PR-H.	Light fixtures on pendant supports are attached at a spacing equal to or less than 6 ft. Unbraced suspended fixtures are free to allow a 360-degree range of motion at an angle not less than 45 degrees from horizontal without contacting adjacent components. Alternatively, if rigidly supported and/or braced, they are free to move with the structure to which they are attached without damaging adjoining components. Additionally, the connection to the structure is capable of accommodating the movement without failure. (Tier 2: Sec. 13.7.9; Commentary: Sec. A.7.3.3)			X		
LF-3 Lens Covers. HR-not required; LS-not required; PR-H.	Lens covers on light fixtures are attached with safety devices. (Tier 2: Sec. 13.7.9; Commentary: Sec. A.7.3.4)			X		Not required for Life Safety Performance Level

### Cladding and Glazing

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
CG-1 Cladding Anchors. HR-MH; LS-MH; PR-MH.	Cladding components weighing more than 10 lb/ft <sup>2</sup> (0.48 kN/m <sup>2</sup> ) are mechanically anchored to the structure at a spacing equal to or less than the following: for Life Safety in Moderate Seismicity, 6 ft (1.8 m); for Life Safety in High Seismicity and for Position Retention in any seismicity, 4 ft (1.2 m) (Tier 2: Sec. 13.6.1; Commentary: Sec. A.7.4.1)			X		

CG-2 Cladding Isolation. HR-not required; LS-MH; PR-MH.	For steel or concrete moment-frame buildings, panel connections are detailed to accommodate a story drift ratio by the use of rods attached to framing with oversize holes or slotted holes of at least the following: for Life Safety in Moderate Seismicity, 0.01; for Life Safety in High Seismicity and for Position Retention in any seismicity, 0.02, and the rods have a length-to-diameter ratio of 4.0 or less. (Tier 2: Sec. 13.6.1; Commentary: Sec. A.7.4.3)			X		
CG-3 Multi-Story Panels. HR-MH; LS-MH; PR-MH.	For multi-story panels attached at more than one floor level, panel connections are detailed to accommodate a story drift ratio by the use of rods attached to framing with oversize holes or slotted holes of at least the following: for Life Safety in Moderate Seismicity, 0.01; for Life Safety in High Seismicity and for Position Retention in any seismicity, 0.02, and the rods have a length-to-diameter ratio of 4.0 or less. (Tier 2: Sec. 13.6.1; Commentary: Sec. A.7.4.4)			X		
CG-4 Threaded Rods. HR-not required; LS-MH; PR-MH.	Threaded rods for panel connections detailed to accommodate drift by bending of the rod have a length-to-diameter ratio greater than 0.06 times the story height in inches for Life Safety in Moderate Seismicity and 0.12 times the story height in inches for Life Safety in High Seismicity and Position Retention in any seismicity. (Tier 2: Sec. 13.6.1; Commentary: Sec. A.7.4.9)			X		
CG-5 Panel Connections. HR-MH; LS-MH; PR-MH.	Cladding panels are anchored out of plane with a minimum number of connections for each wall panel, as follows: for Life Safety in Moderate Seismicity, 2 connections; for Life Safety in High Seismicity and for Position Retention in any seismicity, 4 connections. (Tier 2: Sec. 13.6.1.4; Commentary: Sec. A.7.4.5)			X		
CG-6 Bearing Connections. HR-MH; LS-MH; PR-MH.	Where bearing connections are used, there is a minimum of two bearing connections for each cladding panel. (Tier 2: Sec. 13.6.1.4; Commentary: Sec. A.7.4.6)			X		
CG-7 Inserts. HR-MH; LS-MH; PR-MH.	Where concrete cladding components use inserts, the inserts have positive anchorage or are anchored to reinforcing steel. (Tier 2: Sec. 13.6.1.4; Commentary: Sec. A.7.4.7)			X		

CG-8 Overhead Glazing. HR-not required; LS-MH; PR-MH.	Glazing panes of any size in curtain walls and individual interior or exterior panes more than 16 ft2 (1.5 m2) in area are laminated annealed or laminated heat-strengthened glass and are detailed to remain in the frame when cracked. (Tier 2: Sec. 13.6.1.5; Commentary: Sec. A.7.4.8)					X	
--	--	--	--	--	--	---	--

**Masonry Veneer**

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
M-1 Ties. HR-not required; LS-LMH; PR-LMH.	Masonry veneer is connected to the backup with corrosion-resistant ties. There is a minimum of one tie for every 2-2/3 ft2 (0.25 m2), and the ties have spacing no greater than the following: for Life Safety in Low or Moderate Seismicity, 36 in. (914 mm); for Life Safety in High Seismicity and for Position Retention in any seismicity, 24 in. (610 mm). (Tier 2: Sec. 13.6.1.2; Commentary: Sec. A.7.5.1)			X		
M-2 Shelf Angles. HR-not required; LS-LMH; PR-LMH.	Masonry veneer is supported by shelf angles or other elements at each floor above the ground floor. (Tier 2: Sec. 13.6.1.2; Commentary: Sec. A.7.5.2)			X		
M-3 Weakened Planes. HR-not required; LS-LMH; PR-LMH.	Masonry veneer is anchored to the backup adjacent to weakened planes, such as at the locations of flashing. (Tier 2: Sec. 13.6.1.2; Commentary: Sec. A.7.5.3)			X		
M-4 Unreinforced Masonry Backup. HR-LMH; LS-LMH; PR-LMH.	There is no unreinforced masonry backup. (Tier 2: Sec. 13.6.1.1, 13.6.1.2; Commentary: Sec. A.7.7.2)			X		
M-5 Stud Tracks. HR-not required; LS-MH; PR-MH.	For veneer with coldformed steel stud backup, stud tracks are fastened to the structure at a spacing equal to or less than 24 in. (610 mm) on center. (Tier 2: Sec. 13.6.1.1, 13.6.1.2; Commentary: Sec. A.7.6.)			X		
M-6 Anchorage. HR-not required; LS-MH; PR-MH.	For veneer with concrete block or masonry backup, the backup is positively anchored to the structure at a horizontal spacing equal to or less than 4 ft along the floors and roof. (Tier 2: Sec. 13.6.1.1, 13.6.1.2; Commentary: Sec. A.7.7.1)			X		
M-7 Weep Holes. HR-not required; LS-not required; PR-MH.	In veneer anchored to stud walls, the veneer has functioning weep holes and base flashing. (Tier 2: Sec. 13.6.1.2; Commentary: Sec. A.7.5.6)			X		Not required for Life Safety Performance Level
M-8 Openings. HR-not required; LS-not required; PR-MH.	For veneer with cold-formed-steel stud backup, steel studs frame window and door openings. (Tier 2: Sec. 13.6.1.1, 13.6.1.2; Commentary: Sec. A.7.6.2)			X		Not required for Life Safety Performance Level

**Parapets, Cornices, Ornamentation, and Appendages**

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
PCOA-1 URM Parapets or Cornices. HR-LMH; LS-LMH; PR-LMH.	Laterally unsupported unreinforced masonry parapets or cornices have height-to-thickness ratios no greater than the following: for Life Safety in Low or Moderate Seismicity, 2.5; for Life Safety in High Seismicity and for Position Retention in any seismicity, 1.5. (Tier 2: Sec. 13.6.5; Commentary: Sec. A.7.8.1)			X		
PCOA-2 Canopies. HR-not required; LS-LMH; PR-LMH.	Canopies at building exits are anchored to the structure at a spacing no greater than the following: for Life Safety in Low or Moderate Seismicity, 10 ft (3.0 m); for Life Safety in High Seismicity and for Position Retention in any seismicity, 6 ft (1.8 m). (Tier 2: Sec. 13.6.6; Commentary: Sec. A.7.8.2)				X	Items could not be verified during site visit and there is insufficient data from the existing drawings to confirm. Further investigation may be appropriate to mitigate seismic risk.
PCOA-3 Concrete Parapets. HR-H; LS-MH; PR-LMH.	Concrete parapets with height-to-thickness ratios greater than 2.5 have vertical reinforcement. (Tier 2: Sec. 13.6.5; Commentary: Sec. A.7.8.3)			X		
PCOA-4 Appendages. HR-MH; LS-MH; PR-LMH.	Cornices, parapets, signs, and other ornamentation or appendages that extend above the highest point of anchorage to the structure or cantilever from components are reinforced and anchored to the structural system at a spacing equal to or less than 6 ft (1.8 m). This evaluation statement item does not apply to parapets or cornices covered by other evaluation statements. (Tier 2: Sec. 13.6.6; Commentary: Sec. A.7.8.4)			X		

**Masonry Chimneys**

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
MC-1 URM Chimneys. HR-LMH; LS-LMH; PR-LMH.	Unreinforced masonry chimneys extend above the roof surface no more than the following: for Life Safety in Low or Moderate Seismicity, 3 times the least dimension of the chimney; for Life Safety in High Seismicity and for Position Retention in any seismicity, 2 times the least dimension of the chimney. (Tier 2: Sec. 13.6.7; Commentary: Sec. A.7.9.1)			X		
MC-2 Anchorage. HR-LMH; LS-LMH; PR-LMH.	Masonry chimneys are anchored at each floor level, at the topmost ceiling level, and at the roof. (Tier 2: Sec. 13.6.7; Commentary: Sec. A.7.9.2)			X		

## Stairs

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
S-1 Stair Enclosures. HR-not required; LS-LMH; PR-LMH.	Hollow-clay tile or unreinforced masonry walls around stair enclosures are restrained out of plane and have height-to-thickness ratios not greater than the following: for Life Safety in Low or Moderate Seismicity, 15-to-1; for Life Safety in High Seismicity and for Position Retention in any seismicity, 12-to-1. (Tier 2: Sec. 13.6.2, 13.6.8; Commentary: Sec. A.7.10.1)			X		
S-2 Stair Details. HR-not required; LS-LMH; PR-LMH.	The connection between the stairs and the structure does not rely on post-installed anchors in concrete or masonry, and the stair details are capable of accommodating the drift calculated using the Quick Check procedure of Section 4.4.3.1 for moment-frame structures or 0.5 in. for all other structures without including any lateral stiffness contribution from the stairs. (Tier 2: Sec. 13.6.8; Commentary: Sec. A.7.10.2)				X	Items could not be verified during site visit and there is insufficient data from the existing drawings to confirm. Further investigation may be appropriate to mitigate seismic risk.

## Contents and Furnishings

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
CF-1 Industrial Storage Racks. HR-LMH; LS-MH; PR-MH.	Industrial storage racks or pallet racks more than 12 ft high meet the requirements of ANSI/RMI MH 16.1 as modified by ASCE 7, Chapter 15. (Tier 2: Sec. 13.8.1; Commentary: Sec. A.7.11.1)	X				
CF-2 Tall Narrow Contents. HR-not required; LS-H; PR-MH.	Contents more than 6 ft (1.8 m) high with a height-to-depth or height-to-width ratio greater than 3-to-1 are anchored to the structure or to each other. (Tier 2: Sec. 13.8.2; Commentary: Sec. A.7.11.2)		X			Some contents appear to be noncompliant. Brace tops of shelving taller than 6 feet to nearest backing wall, provide overturning base restraint.
CF-3 Fall-Prone Contents. HR-not required; LS-H; PR-H.	Equipment, stored items, or other contents weighing more than 20 lb (9.1 kg) whose center of mass is more than 4 ft (1.2 m) above the adjacent floor level are braced or otherwise restrained. (Tier 2: Sec. 13.8.2; Commentary: Sec. A.7.11.3)		X			Some items in the storage room appear to be noncompliant. Heavy items on upper shelves should be restrained by netting or cabling to avoid falling hazards.
CF-4 Access Floors. HR-not required; LS-not required; PR-MH.	Access floors more than 9 in. (229 mm) high are braced. (Tier 2: Sec. 13.6.10; Commentary: Sec. A.7.11.4)			X		
CF-5 Equipment on Access Floors. HR-not required; LS-not required; PR-MH.	Equipment and other contents supported by access floor systems are anchored or braced to the structure independent of the access floor. (Tier 2: Sec. 13.7.7 13.6.10; Commentary: Sec. A.7.11.5)			X		

CF-6 Suspended Contents. HR-not required; LS-not required; PR-H.	Items suspended without lateral bracing are free to swing from or move with the structure from which they are suspended without damaging themselves or adjoining components. (Tier 2: Sec. 13.8.2; Commentary: Sec. A.7.11.6)			X		
--	---	--	--	---	--	--

### Mechanical and Electrical Equipment

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
ME-1 Fall-Prone Equipment. HR-not required; LS-H; PR-H.	Equipment weighing more than 20 lb (9.1 kg) whose center of mass is more than 4 ft (1.2 m) above the adjacent floor level, and which is not in-line equipment, is braced. (Tier 2: Sec. 13.7.1 13.7.7; Commentary: Sec. A.7.12.4)			X		
ME-2 In-Line Equipment. HR-not required; LS-H; PR-H.	Equipment installed in line with a duct or piping system, with an operating weight more than 75 lb (34.0 kg), is supported and laterally braced independent of the duct or piping system. (Tier 2: Sec. 13.7.1; Commentary: Sec. A.7.12.5)			X		
ME-3 Tall Narrow Equipment. HR-not required; LS-H; PR-MH.	Equipment more than 6 ft (1.8 m) high with a height-to-depth or height-to-width ratio greater than 3-to-1 is anchored to the floor slab or adjacent structural walls. (Tier 2: Sec. 13.7.1 13.7.7; Commentary: Sec. A.7.12.6)			X		
ME-4 Mechanical Doors. HR-not required; LS-not required; PR-MH.	Mechanically operated doors are detailed to operate at a story drift ratio of 0.01. (Tier 2: Sec. 13.6.9; Commentary: Sec. A.7.12.7)			X		
ME-5 Suspended Equipment. HR-not required; LS-not required; PR-H.	Equipment suspended without lateral bracing is free to swing from or move with the structure from which it is suspended without damaging itself or adjoining components. (Tier 2: Sec. 13.7.1, 13.7.7; Commentary: Sec. A.7.12.8)			X		
ME-6 Vibration Isolators. HR-not required; LS-not required; PR-H.	Equipment mounted on vibration isolators is equipped with horizontal restraints or snubbers and with vertical restraints to resist overturning. (Tier 2: Sec. 13.7.1; Commentary: Sec. A.7.12.9)			X		
ME-7 Heavy Equipment. HR-not required; LS-not required; PR-H.	Floor supported or platform-supported equipment weighing more than 400 lb (181.4 kg) is anchored to the structure. (Tier 2: Sec. 13.7.1, 13.7.7; Commentary: Sec. A.7.12.10)			X		
ME-8 Electrical Equipment. HR-not required; LS-not required; PR-H.	Electrical equipment is laterally braced to the structure. (Tier 2: Sec. 13.7.7; Commentary: Sec. A.7.12.11)			X		
ME-9 Conduit Couplings. HR-not required; LS-not required; PR-H.	Conduit greater than 2.5 in. (64 mm) trade size that is attached to panels, cabinets, or other equipment and is subject to relative seismic displacement has flexible couplings or connections. (Tier 2: Sec. 13.7.8; Commentary: Sec. A.7.12.12)			X		



## Piping

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
PP-1 Flexible Couplings. HR-not required; LS-not required; PR-H.	Fluid and gas piping has flexible couplings. (Tier 2: Sec. 13.7.3, 13.7.5; Commentary: Sec. A.7.13.2)			X		
PP-2 Fluid and Gas Piping. HR-not required; LS-not required; PR-H.	Fluid and gas piping is anchored and braced to the structure to limit spills or leaks. (Tier 2: Sec. 13.7.3, 13.7.5; Commentary: Sec. A.7.13.4)			X		
PP-3 C-Clamps. HR-not required; LS-not required; PR-H.	One-sided C-clamps that support piping larger than 2.5 in. (64 mm) in diameter are restrained. (Tier 2: Sec. 13.7.3, 13.7.5; Commentary: Sec. A.7.13.5)			X		Not required for Life Safety Performance Level
PP-4 Piping Crossing Seismic Joints. HR-not required; LS-not required; PR-H.	Piping that crosses seismic joints or isolation planes or is connected to independent structures has couplings or other details to accommodate the relative seismic displacements. (Tier 2: Sec. 13.7.3, 13.7.5; Commentary: Sec. A.7.13.6)			X		

## Ducts

EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
D-1 Duct Bracing. HR-not required; LS-not required; PR-H.	Rectangular ductwork larger than 6 ft <sup>2</sup> (0.56 m <sup>2</sup> ) in cross-sectional area and round ducts larger than 28 in. (711 mm) in diameter are braced. The maximum spacing of transverse bracing does not exceed 30 ft (9.2 m). The maximum spacing of longitudinal bracing does not exceed 60 ft (18.3 m). (Tier 2: Sec. 13.7.6; Commentary: Sec. A.7.14.2)			X		Not required for Life Safety Performance Level
D-2 Duct Support. HR-not required; LS-not required; PR-H.	Ducts are not supported by piping or electrical conduit. (Tier 2: Sec. 13.7.6; Commentary: Sec. A.7.14.3)			X		Not required for Life Safety Performance Level
D-3 Ducts Crossing Seismic Joints. HR-not required; LS-not required; PR-H.	Ducts that cross seismic joints or isolation planes or are connected to independent structures have couplings or other details to accommodate the relative seismic displacements. (Tier 2: Sec. 13.7.6; Commentary: Sec. A.7.14.4)			X		

## Elevators


EVALUATION ITEM	EVALUATION STATEMENT	C	NC	N/A	U	COMMENT
EL-1 Retainer Guards. HR-not required; LS-H; PR-H.	Sheaves and drums have cable retainer guards. (Tier 2: Sec. 13.7.11; Commentary: Sec. A.7.16.1)			X		
EL-2 Retainer Plate. HR-not required; LS-H; PR-H.	A retainer plate is present at the top and bottom of both car and counterweight. (Tier 2: Sec. 13.7.11; Commentary: Sec. A.7.16.2)			X		

EL-3 Elevator Equipment. HR-not required; LS-not required; PR-H.	Equipment, piping, and other components that are part of the elevator system are anchored. (Tier 2: Sec. 13.7.11; Commentary: Sec. A.7.16.3)			X		
EL-4 Seismic Switch. HR-not required; LS-not required; PR-H.	Elevators capable of operating at speeds of 150 ft/min or faster are equipped with seismic switches that meet the requirements of ASME A17.1 or have trigger levels set to 20% of the acceleration of gravity at the base of the structure and 50% of the acceleration of gravity in other locations. (Tier 2: Sec. 13.7.11; Commentary: Sec. A.7.16.4)			X		
EL-5 Shaft Walls. HR-not required; LS-not required; PR-H.	Elevator shaft walls are anchored and reinforced to prevent toppling into the shaft during strong shaking. (Tier 2: Sec. 13.7.11; Commentary: Sec. A.7.16.5)			X		Not required for Life Safety Performance Level
EL-6 Counterweight Rails. HR-not required; LS-not required; PR-H.	All counterweight rails and divider beams are sized in accordance with ASME A17.1. (Tier 2: Sec. 13.7.11; Commentary: Sec. A.7.16.6)			X		
EL-7 Brackets. HR-not required; LS-not required; PR-H.	The brackets that tie the car rails and the counterweight rail to the structure are sized in accordance with ASME A17.1. (Tier 2: Sec. 13.7.11; Commentary: Sec. A.7.16.7)			X		Not required for Life Safety Performance Level
EL-8 Spreader Bracket. HR-not required; LS-not required; PR-H.	Spreader brackets are not used to resist seismic forces. (Tier 2: Sec. 13.7.11; Commentary: Sec. A.7.16.8)			X		
EL-9 Go-Slow Elevators. HR-not required; LS-not required; PR-H.	The building has a go-slow elevator system. (Tier 2: Sec. 13.7.11; Commentary: Sec. A.7.16.9)			X		

## **Appendix B: Concept-Level Seismic Upgrade Figures**

---

**This page intentionally left blank.**



Building A




Reid Middleton

Berger ABAM

**Carbonado Historical School #19 Seismic Upgrades**  
Washington State School Seismic Safety Assessments Project –  
Carbonado School District – June 2019

**Figure 1** - Plan of Site


■ New Shear Wall



**Figure 2** - Community Gym (Building B) – Roof Plan



■ New Shear Wall



**Figure 3** - Community Gym (Building B) – First Floor Plan

**This page intentionally left blank.**



## **Appendix C: Opinion of Probable Construction Costs**

---

**This page intentionally left blank.**



520 Kirkland Way, Suite 301  
 Kirkland, WA 98033  
 tel: (425) 828-0500  
 fax: (425) 828-0700  
[www.prodims.com](http://www.prodims.com)

Name: **Wa State School Seismic Safety Assessment**  
 Second Name: **Carbonado Gym**  
 Location: **State of Washington**  
 Design Phase: **ROM Cost Estimates**  
 Date of Estimate: **April 11, 2019**  
 Date of Revision:  
 Month of Cost Basis: **1Q, 2019**

**Carbonado Gym**

**Master Estimate Summary**

Project Name		Total Estimated Construction Cost
Carbonado Gym	Structural Costs	\$580,739
Carbonado Gym	Non-Structural Costs	\$159,481
<b>TOTAL ESTIMATED CONSTRUCTION COST</b>		<b>\$740,220</b>

**Estimate Assumptions:**

The ROM Construction Cost estimates are based on the Concept Design Report for the Project.  
 Construction Escalation is not included. Costs are current as of month of Cost Basis noted Above

**Estimate Qualifications:**

The ROM estimates are not be relied on solely for proforma development and financial decisions.  
 Further design work is required to determine construction budgets.  
 All Buildings Estimated to the 5' foot line for Utilities, All Sitework is estimated to go with any combination of the buildings and alternatives.  
 The ROM estimates do not include any Hazardous Material Abatement/Disposal.  
 For Construction Cost Markups they are additive, not cumulative. Percentages are added to the previous subtotal rather than the direct cost subtotal.  
 Owner Soft Costs are not included in the estimates. Soft costs can include design fees, sales tax, permits, owner's contingency and FF+E.  
 Estimated labor is based on an 8 hour per day shift 5 days a week. Accelerated schedule work of overtime has not been included.  
 Estimated labor is based on working on unoccupied facility without phased construction.  
 Estimate is based on a competitive public bid with at least 3 bona fide submitted and unrescinded general contractor bids.  
 Estimate is based on a competitive public bid with a minimum 6 week bidding schedule and no significant addendums within 2 weeks of bid opening.  
 State of Washington General Contractor/ Construction Manager (GC/CM) contracts typically raises construction costs. It is Not Included in this estimate.  
 Estimated construction cost is for the entire project. This estimate is not intended to be used for other projects.  
 Please consult the cost estimator for any modifications to this estimate. Unilaterally adding and deleting markups, scope of work, schedule, specifications, plans and bid forms could incorrectly restate the project construction cost.  
 Construction reserve contingency for change orders is not included in the estimate.  
 Sole source supply of materials and/ or installers typically results in a 40% to 100% premium on costs over open specifications.



520 Kirkland Way, Suite 301  
 Kirkland, WA 98033  
 Phone: 425-828-0500 Fax: 425-528-0700  
[www.prodim.com](http://www.prodim.com)

Wa State School Seismic  
 Name: Safety Assessment

Areas sqft

**Structural Costs**

Second Name: Carbonado Gym  
 Location: Carbonado, WA  
 1st Floor 4,500  
 2nd Floor 1,200

Design Phase: ROM Cost Estimates  
 Date of Estimate: April 11, 2019  
 Date of Revision:  
 Month of Cost Basis: 4Q, 2018, 1Q, 2019

Total Areas 5,700

**Carbonado Gym**

**Construction Cost Estimate**

**Subtotal Direct Cost From the Estimate Detail Below \$ 443,312**

	Percentage of Previous Subtotal	Amount	Running Subtotal
Scope Contingency	10.0%	\$ 44,331	\$ 487,643
General Conditions	10.0%	\$ 44,331	\$ 531,975
Home Office Overhead	5.0%	\$ 22,166	\$ 554,140
Profit	6.0%	\$ 26,599	\$ 580,739
Escalation Not Included-Costs in 4Q, 2018 Dollars	0.0%	\$ -	\$ 580,739
Washington State Sales Tax	0.0%	\$ -	\$ 580,739

Total Markups Applied to the Direct Cost  
 Markups are multiplied from each subtotal. They are not multiplied from the direct cost

<b>TOTAL ESTIMATED CONSTRUCTION COST--</b>	<b>\$ 580,739</b>	<b>\$ 101.88</b>
<b>-20% TOTAL ESTIMATED CONSTRUCTION COST VARIANCE --</b>	<b>\$ 464,591</b>	<b>\$ 81.51</b>
<b>+50% TOTAL ESTIMATED CONSTRUCTION COST VARIANCE --</b>	<b>\$ 871,108</b>	<b>\$ 152.83</b>

**Please see the Master Summary for Assumptions and Qualifications for ROM Cost Estimates**

**Direct Cost of Construction**

WBS	Description	Quantity	U of M	Labor	Labor Total	Material	Material Total	Equipment	Equipment Total	Total \$/U of M	Direct Cost
-----	-------------	----------	--------	-------	-------------	----------	----------------	-----------	-----------------	-----------------	-------------

WBS	Description	Quantity	U of M	Labor	Labor Total	Material	Material Total	Equipment	Equipment Total	Total \$/U of M	Direct Cost	
<b>1 - Seismic Retrofit</b>												
<b>Foundations</b>												
	The Building Floor System to Concrete Foundation with Anchor Bolt System	322 Init		\$ 30.72	\$ 9,891.84	\$ 17.28	\$ 5,564.16	\$ 2.88	\$ 927.36	\$ 50.88	\$ 16,383.36	
<b>Superstructure Upper Floor Systems</b>												
	Add Plywood Sheathing/Blocking at 2nd Floor	1,200 sqft		\$ 2.31	\$ 2,769.00	\$ 1.24	\$ 1,491.00	\$ 0.21	\$ 255.60	\$ 3.76	\$ 4,515.60	
	Remove and Reinstall New Floor Finish System	1,200 sqft		\$ 4.64	\$ 5,568.00	\$ 3.36	\$ 4,032.00	\$ 0.48	\$ 576.00	\$ 8.48	\$ 10,176.00	
<b>Roof Systems</b>												
	Connect Trusses to Columns	28 each		\$ 510.00	\$ 14,280.00	\$ 240.00	\$ 6,720.00	\$ 45.00	\$ 1,260.00	\$ 795.00	\$ 22,260.00	
	Connect Roof Diaphragm to Exterior Wall	322 Init		\$ 42.50	\$ 13,685.00	\$ 20.00	\$ 6,440.00	\$ 3.75	\$ 1,207.50	\$ 66.25	\$ 21,332.50	
	Add Plywood Sheathing/Blocking at Roof Structure	4,500 sqft		\$ 2.31	\$ 10,383.75	\$ 1.24	\$ 5,591.25	\$ 0.21	\$ 958.50	\$ 3.76	\$ 16,933.50	
<b>Exterior Closure Exterior Wall System</b>												
	Add Plywood Sheathing/Blocking System at Exterior Walls	7,406 sqft		\$ 2.18	\$ 16,108.05	\$ 1.58	\$ 11,664.45	\$ 0.23	\$ 1,666.35	\$ 3.98	\$ 29,438.85	
	Remove and Reinstall New Exterior Wall Finish System	7,406 sqft		\$ 16.24	\$ 120,273.44	\$ 11.76	\$ 87,094.56	\$ 1.68	\$ 12,442.08	\$ 29.68	\$ 219,810.08	
<b>Roofing System</b>												
	Remove Existing Roofing System	4,500 sqft		\$ 2.02	\$ 9,072.00	\$ 0.08	\$ 378.00	\$ 0.15	\$ 567.00	\$ 2.23	\$ 10,017.00	
	Install New Roofing System - Including Roof Membrane, New Insulation, Coverboard and Flashing and Trim for a Complete System	4,500 sqft		\$ 10.02	\$ 45,076.50	\$ 8.53	\$ 38,398.50	\$ 1.11	\$ 5,008.50	\$ 19.66	\$ 88,483.50	
<b>Interiors Interior Wall/Door/Casework/Specialties Systems</b>												
	Add Plywood Sheathing/Blocking System at Interior Walls to 2nd Floor	1,150 sqft		\$ 1.89	\$ 2,167.75	\$ 1.37	\$ 1,569.75	\$ 0.20	\$ 224.25	\$ 3.45	\$ 3,961.75	
<b>Subtotal of the Direct Cost of Construction</b>											<b>\$</b>	<b>443,312</b>
<b>Carbonado Gym</b>												



520 Kirkland Way, Suite 301  
 Kirkland, WA 98033  
 Phone: 425-828-0500 Fax: 425-528-0700  
[www.prodim.com](http://www.prodim.com)

Wa State School Seismic  
 Name: Safety Assessment

Areas sqft

**Non-Structural Costs**

Second Name: Carbonado Gym  
 Location: Carbonado, WA

Building Area 4,500

Design Phase: ROM Cost Estimates  
 Date of Estimate: April 11, 2019

Date of Revision:  
 Month of Cost Basis: 4Q, 2018, 1Q, 2019

Total Areas 4,500

**Carbonado Gym**

**Construction Cost Estimate**

Subtotal Direct Cost From the Estimate Detail Below \$ **121,741**

	Percentage of Previous Subtotal	Amount	Running Subtotal
Scope Contingency	10.0%	\$ 12,174	\$ 133,915
General Conditions	10.0%	\$ 12,174	\$ 146,089
Home Office Overhead	5.0%	\$ 6,087	\$ 152,176
Profit	6.0%	\$ 7,304	\$ 159,481
Escalation Not Included-Costs in 4Q, 2018 Dollars	0.0%	\$ -	\$ 159,481
Washington State Sales Tax	0.0%	\$ -	\$ 159,481

Total Markups Applied to the Direct Cost  
 Markups are multiplied from each subtotal. They are not multiplied from the direct cost.

<b>TOTAL ESTIMATED CONSTRUCTION COST--</b>	<b>\$ 159,481</b>	<b>\$ 35.44</b>
<b>-20% TOTAL ESTIMATED CONSTRUCTION COST VARIANCE --</b>	<b>\$ 127,585</b>	<b>\$ 28.35</b>
<b>+50% TOTAL ESTIMATED CONSTRUCTION COST VARIANCE --</b>	<b>\$ 239,221</b>	<b>\$ 53.16</b>

Please see the Master Summary for Assumptions and Qualifications for ROM Cost Estimates

**Direct Cost of Construction**

WBS	Description	Quantity	U of M	Labor	Labor Total	Material	Material Total	Equipment	Equipment Total	Total \$/U of M	Direct Cost
<b>2- Non- Structural Demo/Restoration*</b>											
<b>Interiors and M/E/P/F systems</b>											
	New Floor Finishes for Installation of Seismic Work at 2nd Floor	1,200	sqft	\$ 3.08	\$ 3,696.00	\$ 2.42	\$ 2,904.00	\$ 0.33	\$ 396.00	\$ 5.83	\$ 6,996.00
	Rebuild Staircase	1	each	\$ 1,600.00	\$ 1,600.00	\$ 900.00	\$ 900.00	\$ 150.00	\$ 150.00	\$ 2,650.00	\$ 2,650.00

WBS	Description	Quantity	U of M	Labor	Labor Total	Material	Material Total	Equipment	Equipment Total	Total \$/U of M	Direct Cost
	New Ceilings and Finishes for Installation of Seismic Work	4,500 sqft		\$ 3.03	\$ 13,612.50	\$ 2.48	\$ 11,137.50	\$ 0.33	\$ 1,485.00	\$ 5.83	\$ 26,235.00
	Mechanical/Electrical/Fire Protection Systems	4,500 sqft		\$ 9.90	\$ 44,550.00	\$ 8.10	\$ 36,450.00	\$ 1.08	\$ 4,860.00	\$ 19.08	\$ 85,860.00
	*Allows 30 percent of existing nonstructural systems M/E/P/F/P require upgrades/replacement.										
	<b>Subtotal of the Direct Cost of Construction</b>										<b>\$ 121,741</b>

**This page intentionally left blank.**



# Appendix D: Earthquake Performance Assessment Tool (EPAT) Worksheet

---

**This page intentionally left blank.**

**Washington Schools Earthquake Performance Assessment Tool (EPAT)  
MAIN PAGE**

<b>Full District Name</b>	Carbonado		
<b>Point of Contact</b>	Scott Hubbard		
<b>Telephone</b>	360-829-0121		
<b>E-Mail</b>	shubbard@carbonado.k12.wa.us		
<b>File Name</b>	Carbonado, Carbonado Historical School 19 - B - Community Gym EPAT	<b>File Date:</b>	7/5/2018

<b>District</b>	Carbonado
<b>Facility Name</b>	Carbonado Historical School 19
<b>Building Part Name</b>	B - Community Gym

Earthquake Ground Motion (% g)		Earthquake Hazards	
<b>20% in 50 year PGA</b>	20.8%	<b>Site Class</b>	C
<b>10% in 50 year PGA</b>	28.8%	<b>Ground Shaking Hazard</b>	High
<b>2% in 50 year PGA</b>	49.7%	<b>Liquefaction Potential</b>	Very Low to Low
<b>Percentile S<sub>s</sub></b> <i>Among all WA Campuses</i>	51%	<b>Combined Earthquake Hazard Level</b>	High

<b>Total Building Part Area (Square Feet)</b>	<b>Building Evaluated By</b>	<b>Input Data by Person(s)</b>
803	DNR, Reid Middleton	Tim Green, Reid Middleton

The Earthquake Ground Motion and Earthquake Hazard Hazards data shown above are primarily for use and interpretation by engineers.

Refer to the EPAT User Guide for technical explanations of the Earthquake Ground Motion and the Earthquake Hazards information.

**Washington Schools Earthquake Performance Assessment Tool (EPAT)  
BUILDING DATA PAGE**

<b>Facility Name</b>	Carbonado Historical School 19
<b>Building Name</b>	B - Community Gym
<b>Building Use</b>	Assembly

Data Entry Item	User Entered Values	Default Values	Used for BCA
<b>Seismic Data</b>			
Decimal Latitude	47.081324	47.081324	47.081324
Decimal Longitude	-122.05387	-122.05387	-122.05387
Site Class (Soil/Rock Type)	C	C-D	C
Liquefaction Potential	Very Low to Low	Very Low to Low	Very Low to Low
Geographic Region for Seismic Zones	Puget Sound	Puget Sound	Puget Sound
<b>Building Structural Data</b>			
HAZUS Building Type***	W2	Wood, Commercial & Industrial (>5,000 SF)	W2
Number of Stories (Excluding Basement)***	2		2
Year Built***	1936		1936
Code for Building Design (if known)	Unknown	<b>Use the Drop-Down menus to Select Data Entries for the Bright Green Shaded data cells.</b>	Unknown
Design Code Year (if known)	Unknown		Unknown
Severe Vertical Irregularity***	No		No
Moderate Vertical Irregularity***	No		No
Plan (Horizontal) Irregularity***	No		No

\*\*\* Mandatory Data Entry

## Washington Schools Earthquake Performance Assessment Tool (EPAT) RESULTS SUMMARY

<b>District Name</b>	Carbonado	<b>Existing Building Life Safety Risk &amp; Priority for Retrofit or Replacement</b>
<b>School Name</b>	Carbonado Historical School 19	
<b>Building Name</b>	B - Community Gym	<b>Moderate-High</b>

### Building Data

<b>HAZUS Building Type</b>	W2	Wood, Commercial & Industrial (>5,000 SF)
<b>Year Built</b>	1936	These parameters determine the capacity of the existing building to withstand earthquake forces.
<b>Building Design Code</b>	<1973 UBC	
<b>Existing Building Code Level</b>	Pre	
<b>Geographic Area</b>	Puget Sound	
<b>Severe Vertical Irregularity</b>	No	Buildings with irregularities have greater earthquake damage than otherwise similar buildings that are regular.
<b>Moderate Vertical Irregularity</b>	No	
<b>Plan Irregularity</b>	No	

### Seismic Data

<b>Earthquake Ground Shaking Hazard Level</b>	High	Frequency and severity of earthquakes at this site
<b>Percentile S<sub>s</sub> Among WA K-12 Campuses</b>	51%	Earthquake ground shaking hazard is higher than 51% of WA campuses.
<b>Site Class (Soil or Rock Type)</b>	C	Very Dense Soil and Soft Rock
<b>Liquefaction Potential</b>	Very Low to Low	Liquefaction increases the risk of major damage to a building
<b>Combined Earthquake Hazard Level</b>	High	Earthquake ground shaking and liquefaction potential

### Severe Earthquake Event (Design Basis Earthquake Ground Motion)<sup>1</sup>

<b>Building State</b>	<b>Building Damage Estimate<sup>2</sup></b>	<b>Probability Building is not Repairable<sup>3</sup></b>	<b>Life Safety<sup>4</sup> Risk Level</b>	<b>Most Likely Post-Earthquake Tagging<sup>5</sup></b>
Existing Building	49%	43%	Moderate-High	Red
Life Safety Retrofit Building	9.6%	3.3%	Very Low	Green
Current Code Building	7.5%	1.9%	Very Low	Green

- |  |   |
|--|---|
| 1. 2/3rds of the 2% in 50 year ground motion   | 4. Based on probability of Complete Damage State.       |
| 2. Percentage of building replacement value.   | 5. Most likely post-earthquake damage state per ATC-20. |
| 3. Probability building is in the Extensive or Complete damage states. For existing buildings, the probability that the building is not economically repairable may be higher: some buildings in the Moderate Damage state are also likely to be demolished. |   |

### Source for the Data Entered into the Tool

<b>Building Evaluated By:</b>	DNR, Reid Middleton
<b>Person(s) Who Entered Data in EPAT:</b>	Tim Green, Reid Middleton
<b>User Overrides of Default Parameters:</b>	Building Design Code Year, Latitude, Longitude, Site Class, Liquefaction, Geographic Region

**This page intentionally left blank.**

## Appendix E: Not Used

---


**This page intentionally left blank.**



# Appendix F: FEMA E-74 Nonstructural Seismic Bracing Excerpts

**This page intentionally left blank.**


## Life Safety Systems



**Note:** for seismic design category D, E & F, the flexible sprinkler hose fitting must accommodate at least 1" of ceiling movement without use of an oversized opening. Alternatively, the sprinkler head must have a 2" oversize ring or adapter that allows 1" movement in all directions.

**Figure G-1. Flexible Sprinkler Drop.**


*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Figure G-2. End of Line Restraint.**

*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*


## Partitions



**Figure G-3. Mitigation Schemes for Bracing the Tops of Metal Stud Partition Walls.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Figure G-4. Mitigation Schemes for Bracing the Tops of Metal Stud Partition Walls.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Figure G-5. Full-height Glazed Partition.**

*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*



**Figure G-6. Full-height Heavy Partition.**

*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*



**Figure G-7. Typical Glass Block Panel Details.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*



## Ceilings






Figure G-8. Suspension System for Acoustic Lay-in Panel Ceilings – Edge Conditions.  
(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)



**Note:** Compression strut shall not replace hanger wire. Compression strut consists of a steel section attached to main runner with 2 - #12 sheet metal screws and to structure with 2 - #12 screws to wood or 1/4" min. expansion anchor to structure. Size of strut is dependent on distance between ceiling and structure ( $l/r \leq 200$ ). A 1" diameter conduit can be used for up to 6'; a 1-5/8" X 1-1/4" metal stud can be used for up to 10'

Per DSA IR 25-5, ceiling areas less than 144 sq. ft., or fire rated ceilings less than 96 sq. ft., surrounded by walls braced to the structure above do not require lateral bracing assemblies when they are attached to two adjacent walls. (ASTM E580 does not require lateral bracing assemblies for ceilings less than 1000 sq. ft.; see text.)

**Figure G-9. Suspension System for Acoustic Lay-in Panel Ceilings – General Bracing Assembly.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*



**Figure G-10. Suspension System for Acoustic Lay-in Panel Ceilings – General Bracing Layout.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*






Figure G-11. Suspension System for Acoustic Lay-in Panel Ceilings – Overhead Attachment Details.

(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)




**a) Gypsum board attached directly to ceiling joists**




**b) Gypsum board attached directly to furring strips (hat channel or similar)**

Note: Commonly used details shown; no special seismic details are required as long as furring and gypboard secured. Check for certified assemblies (UL listed, FM approved, etc.) if fire or sound rating required.


**Figure G-12. Gypsum Board Ceiling Applied Directly to Structure.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Figure G-13. Retrofit Detail for Existing Lath and Plaster.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*



**Figure G-14. Diagrammatic View of Suspended Heavy Ceiling Grid and Lateral Bracing.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**A-A Main Runner at Perimeter**



**B-B Cross Runner at Perimeter**

**Figure G-15. Perimeter Details for Suspended Gypsum Board Ceiling.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*







**Note:** Compression strut shall not replace hanger wire. Compression strut consists of a steel section attached to main runner with 2 - #12 sheet metal screws and to structure with 2 - #12 screws to wood or 1/4" min. expansion anchor to concrete. Size of strut is dependent on distance between ceiling and structure ( $l/r \leq 200$ ). A 1" diameter conduit can be used for up to 6', a 1-5/8" X 1-1/4" metal stud can be used for up to 10'. See figure 6.3.4.1-6 for example of bracing assembly.

**Figure G-16. Details for Lateral Bracing Assembly for Suspended Gypsum Board Ceiling.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*

## Light Fixtures




**Figure G-17. Recessed Light Fixture in suspended Ceiling (Fixture Weight < 10 pounds).**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Figure G-18. Recessed Light Fixture in suspended Ceiling (Fixture Weight 10 to 56 pounds).**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*

## Contents and Furnishings



**Figure G-19. Light Storage Racks.**


*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*



**Note:** Purchase storage racks designed for seismic resistance. Storage racks may be classified as either nonstructural elements or nonbuilding structures depending upon their size and support conditions. Check the applicable code to see which provisions apply.


**Figure G-20. Industrial Storage Racks.**

*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Figure G-21. Wall-mounted File Cabinets.**

*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Figure G-22. Base Anchored File Cabinets.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Note:** Engineering required for all permanent floor-supported cabinets or shelving over 6 feet tall. Details shown are adequate for typical shelving 6 feet or less in height.

**Figure G-23. Anchorage of Freestanding Book Cases Arranged Back to Back.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Figure G-24. Desktop Computers and Accessories.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*






**Cantilevered Access Floor Pedestal**



**Braced Access Floor Pedestal**  
 (use for tall floors or where pedestals are not strong enough to resist seismic forces)


**Note:** For new floors in areas of high seismicity, purchase and install systems that meet the applicable code provisions for "special access floors."

**Figure G-25. Equipment Mounted on Access Floor.**  
 (FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)




**Equipment installed on an independent steel platform within a raised floor**

**Figure G-26. Equipment Mounted on Access Floor – Independent Base.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*



**Equipment restrained with cables beneath a raised floor**


**Figure G-27. Equipment Mounted on Access Floor – Cable Braced.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*



**Equipment anchored with vertical rods beneath a raised floor**


**Figure G-28. Equipment Mounted on Access Floor – Tie-down Rods.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*

**Mechanical and Electrical Equipment**




**Note: Rigidly mounted equipment shall have flexible connections for the fuel lines and piping.**


**Figure G-29. Rigidly Floor-mounted Equipment with Added Angles.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*



**Supplemental base with restrained spring isolators**




**Supplemental base with open springs and all-directional snubbers**




**Supplemental base with open springs and one-directional snubbers**

**Figure G-30. HVAC Equipment with Vibration Isolation.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Figure G-31. Rooftop HVAC Equipment.**

*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Figure G-32. Suspended Equipment.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Figure G-33. Water Heater Strapping to Backing Wall.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*







**Figure G-34. Water Heater – Strapping at Corner Installation.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*



**Figure G-35. Water Heater – Base Mounted.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Figure G-36. Rigid Bracing – Single Pipe Transverse.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*




**Figure G-37. Cable Bracing – Single Pipe Transverse.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*


## Electrical and Communications



**Figure G-38. Electrical Control Panels, Motor Controls Centers, or Switchgear.**  
(FEMA E-74, 2012, *Reducing the Risks of Nonstructural Earthquake Damage*)



**Figure G-39. Freestanding and Wall-mounted Electrical Control Panels, Motor Controls Centers, or Switchgear.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*



**Figure G-40. Emergency Generator.**  
*(FEMA E-74, 2012, Reducing the Risks of Nonstructural Earthquake Damage)*

**This page intentionally left blank.**



## ReidMiddleton

728 – 134th St SW  
Suite 200  
Everett, WA 98204

Tel 425-741-3800  
Fax 425-741-3900

[www.reidmiddleton.com](http://www.reidmiddleton.com)  
File No. 262018.063