
# CITY OF ALEXANDRIA, VIRGINIA




MURPHY NG, EXT# 4699
DEPARTMENT OF PROJECT IMPLEMENTATION
CITY OF ALEXANDRIA
301 KING STREET, SUITE 3200
ALEXANDRIA, VA 22314



GI001


SHEET 01 of 10 SCALE AS SHOWN



# CIP2022-00015 POLK AVENUE SIDEWALK



PROJECT AREA MAP SCALE 1" = 200'



VICINITY MAP SCALE 1" = 4000'

SHEET INDEX		
SHEET TYPE	SHEET NUMBER	SHEET TITLE
GI001	01	COVER SHEET
GI002	02	GENERAL NOTES
GC101	03	EROSION AND SEDIMENT CONTROL PLAN
VF101	04	EXISTING CONDITIONS
CD101	05	DEMOLITION PLAN
CS101	06	SITE PLAN
CS501	07	SITE DETAILS
CG101	08	GRADING PLAN
CG701	09	STORMWATER MANAGEMENT PLAN
CG702	10	STORMWATER MANAGEMENT COMPLIANCE



DEPUTY DIRECTOR OF TRANSPORTATION

RECOMMENDED FOR APPROVAL

DEPARTMENT OF PROJECT IMPLEMENTATION

PROJECT DESCRIPTION:

THE PROJECT PROPOSE TO CONSTRUCT A

CONCRETE SIDEWALK (APPROXIMATELY 280' IN LENGTH) ON THE NORTH SIDE OF POLK AVENUE BETWEEN NORTH PELHAM STREET AND PALMER

DATE:

DATE:

DATE: 04/20/23



#### EXISTING CONDITIONS SURVEY NOTES

- HORIZONTAL DATUM: NAD 1983 VERTICAL DATUM: NAVD 1988
- 2. UTILITY AND TOPOGRAPHY INFORMATION, AS SHOWN ON THIS PLAN, IS TAKEN FROM THE RECORDS AND/OR FIELD SURVEY COMPLETED BY THE CITY, DATED 11/2021; AND CANNOT BE GUARANTEED. FOR EXACT LOCATIONS OF EXISTING UNDERGROUND UTILITIES, NOTIFY 'MISS UTILITY" AT 1-800-257-7777, 72 HOURS BEFORE THE START OF ANY EXCAVATION OR CONSTRUCTION.
- LOCATION AND DEPTH OF ALL EXISTING UNDERGROUND UTILITIES TO BE VERIFIED BY CONTRACTOR PRIOR TO CONSTRUCTION.

#### CITY STANDARD GENERAL NOTES

- "CITY" MEANS THE CITY OF ALEXANDRIA, A MUNICIPAL CORPORATION OF VIRGINIA AND ITS AUTHORIZED REPRESENTATIVES AND EMPLOYEES.
- TOTAL SITE AREA: 4,514 SQUARE FEET OR 0.1036 ACRES OF WHICH 4,514 SQUARE FEET OR 0.1036 ACRES WILL BE DISTURBED WITH THIS PROJECT.
- 3. THE NATURAL SOILS AT THE SITE CONSIST OF GRISS MILL WOODSTOWN COMPLEX (HSG-D).
- 4. THE SITE IS LOCATED IN THE HOLMES RUN WATERSHED.
- 5. NO PORTION OF THE SUBJECT PROPERTY LIES WITHIN A CITY OF ALEXANDRIA RESOURCE PROTECTION
- ALL NEW CONSTRUCTION WILL CONFORM TO THE CURRENT STANDARDS AND SPECIFICATIONS OF THE CITY OF ALEXANDRIA AND/OR THE VIRGINIA DEPARTMENT OF TRANSPORTATION (VDOT) STANDARDS AND SPECIFICATIONS.
- ALL EROSION AND SEDIMENTATION CONTROL SHALL BE PLACED AND MAINTAINED IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS OF THE CITY OF ALEXANDRIA AND/OR VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH).
- ANY WORK IN THE PUBLIC RIGHT OF WAY SHALL REQUIRE A SEPARATE PERMIT FROM THE CITY.
- 9. THERE IS NO OBSERVABLE EVIDENCE OF CEMETERIES OR BURIAL GROUNDS ON THIS PROJECT.

#### ARCHAEOLOGY NOTES

ΑM

- THE CONTRACTOR SHALL CALL ALEXANDRIA ARCHAEOLOGY IMMEDIATELY (703-746-4399) IF ANY BURIED STRUCTURAL REMAINS (WALL FOUNDATIONS, WELLS, PRIVIES, CISTERNS, ETC.) OR CONCENTRATIONS OF ARTIFACTS ARE DISCOVERED DURING DEVELOPMENT. WORK MUST CEASE IN THE AREA OF THE DISCOVERY UNTIL A CITY ARCHAEOLOGIST COMES TO THE SITE AND RECORDS THE
- THE CONTRACTOR SHALL NOT ALLOW ANY METAL DETECTION TO BE CONDUCTED ON THE PROPERTY. UNLESS AUTHORIZED BY ALEXANDRIA ARCHAEOLOGY.

## ENVIRONMENTAL SITE ASSESSMENT

- THERE ARE NO TIDAL WETLANDS, TIDAL SHORES, TRIBUTARY STREAMS, FLOODPLAINS, CONNECTED TIDAL WETLANDS, ISOLATED WETLANDS, HIGHLY ERODIABLE/PERMEABLE SOILS OR BUFFER AREAS ASSOCIATED WITH SHORES, STREAMS, OR WETLANDS LOCATED ON THE SITE. FURTHER, THERE ARE NO WETLAND PERMITS REQUIRED FOR THIS DEVELOPMENT PROJECT. ADDITIONALLY, THERE ARE NO KNOWN UNDERGROUND STORAGE TANKS OR AREAS OF SOIL OR GROUNDWATER CONTAMINATION ON THE SITE.
- THE CITY OF ALEXANDRIA DEPARTMENT OF TRANSPORTATION AND ENVIRONMENTAL SERVICES, DIVISION OF ENVIRONMENTAL QUALITY MUST BE NOTIFIED IF UNUSUAL OR UNANTICIPATED CONTAMINATION OR UNDERGROUND STORAGE TANKS, DRUMS, AND CONTAINERS ARE ENCOUNTERED AT THE SITE. IF THERE IS ANY DOUBT ABOUT PUBLIC SAFETY OR A RELEASE TO THE ENVIRONMENT, THE ALEXANDRIA FIRE DEPARTMENT MUST BE CONTACTED IMMEDIATELY BY CALLING 911. THE TANK OR CONTAINER'S REMOVAL, ITS CONTENTS, ANY SOIL CONTAMINATION AND RELEASES TO THE ENVIRONMENT WILL BE HANDLED IN ACCORDANCE WITH FEDERAL, STATE, AND CITY REGULATIONS.
- ALL CONSTRUCTION ACTIVITIES MUST COMPLY WITH THE ALEXANDRIA NOISE CONTROL CODE TITLE 11. CHAPTER 5. WHICH PERMITS CONSTRUCTION ACTIVITIES TO OCCUR BETWEEN THE FOLLOWING HOURS:
  - MONDAY THROUGH FRIDAY FROM 7 AM TO 6 PM AND SATURDAYS FROM 9 AM TO 6 PM.
  - NO CONSTRUCTION ACTIVITIES ARE PERMITTED ON SUNDAYS.
  - PILE DRIVING IS FURTHER RESTRICTED TO THE FOLLOWING HOURS:
  - MONDAY THROUGH FRIDAY FROM 9 AM TO 6 PM AND SATURDAYS FROM 10 AM TO 4 PM.

#### UTILITY CONTACTS

DOMINION ENERGY	703-838-2478
VERIZON COMMUNICATIONS	703-212-5261
COMCAST	703-926-0534
WASHINGTON GAS	703-750-4256
PEPCO PEPCO	202-833-7500
VIRGINIA AMERICAN WATER	703-706-3889
SANITARY SEWER - CITY OF ALEX.	703-746-4014

CONTRACTOR SHALL CONFORM TO THE OVERHEAD HIGH VOLTAGE ACT (EFFECTIVE JULY 1, 2003) AND SHALL CONTACT THE NECESSARY AUTHORITIES PRIOR TO START OF CONSTRUCTION.

#### **CONSTRUCTION NOTES**

- ALL WORK MUST BE PERFORMED IN STRICT COMPLIANCE WITH THE MOST CURRENT APPLICABLE FEDERAL, STATE, AND LOCAL LAWS AND REGULATIONS, INCLUDING BUT NOT LIMITED, TO ENVIRONMENTAL PROTECTION AGENCY (EPA), OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA), VIRGINIA OCCUPATIONAL AND SAFETY HEALTH COMPLIANCE PROGRAM (VOSH ENFORCEMENT), VIRGINIA OVERHEAD HIGH VOLTAGE LINE SAFETY ACT, NATIONAL EMISSIONS STANDARDS FOR HAZARDOUS AIR POLLUTANTS (NESHAPS), AND NATIONAL INSTITUTE OF OCCUPATIONAL SAFETY AND HEALTH (NIOSH).
- THE EXISTING UNDERGROUND UTILITIES SHOWN HEREON ARE BASED UPON AVAILABLE INFORMATION THE CONTRACTOR MUST BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION OF ALL UTILITIES BEFORE COMMENCING WORK AND FOR ANY DAMAGES WHICH MAY OCCUR BY HIS FAILURE TO LOCATE OR PRESERVE THESE UNDERGROUND UTILITIES. IF DURING CONSTRUCTION OPERATIONS, THE CONTRACTOR SHOULD ENCOUNTER UTILITIES OTHER THAN THOSE SHOWN ON THE PLANS, HE MUST IMMEDIATELY NOTIFY THE CITY AND TAKE NECESSARY ACTION AND PROPER STEPS TO PROTECT THE FACILITY AND ASSURE THE CONTINUATION OF SERVICE.
- LOCATION AND DEPTH OF ALL EXISTING UNDERGROUND UTILITIES MUST BE VERIFIED BY CONTRACTOR PRIOR TO CONSTRUCTION AND DIG TEST PITS AS REQUIRED. CONTRACTOR SHOULD DIG TEST PITS BY HAND AT ALL UTILITY CROSSINGS TO VERIFY THE EXACT LOCATION. ANY DISCREPANCIES ARE TO BE REPORTED IMMEDIATELY TO THE CITY. REDESIGN AND APPROVAL BY REVIEWING AGENCIES SHALL BE OBTAINED, IF REQUIRED.
- THE CONTRACTOR MUST WORK WITH THE CITY FOR THE COORDINATION OF WORK WITH REPRESENTATIVE UTILITY COMPANIES AND FOR THE IMPLEMENTATION OF REQUIRED UTILITY-RELATED
- THE CONTRACTOR MUST VISIT THE SITE AND MUST VERIFY EXISTING CONDITIONS PRIOR TO ANY LAND DISTURBING ACTIVITY.
- THE CONTRACTOR MUST IMMEDIATELY NOTIFY THE CITY UPON ENCOUNTERING ANY HAZARDOUS MATERIALS DURING DEMOLITION AND/OR CONSTRUCTION ACTIVITIES. THE CONTRACTOR MUST DOCUMENT SAME TO THE CITY AND OBTAIN DIRECTION AS TO THE APPROPRIATE ACTION(S) TO BE TAKEN.
- PRIOR TO REMOVAL OF MATERIALS OVER EXISTING UTILITY SYSTEMS. THE CONTRACTOR MUST DOCUMENT EXISTING CONDITIONS AND, IF AT VARIANCE WITH CONDITIONS AS REPRESENTED ON THE PLANS, NOTIFY THE CITY AND OBTAIN DIRECTION AS TO THE APPROPRIATE ACTION(S) TO BE TAKEN.
- PRIOR TO COMMENCING NEW WORK, THE CONTRACTOR MUST PROTECT FROM DAMAGE ALL EXISTING ADJACENT AREAS. ALL ADJACENT AREAS DAMAGED DURING DEMOLITION AND/OR CONSTRUCTION ACTIVITIES MUST BE RESTORED TO ORIGINAL OR BETTER CONDITION AT NO ADDITIONAL COST TO THE CITY.
- THE CONTRACTOR MUST PROTECT AND PREVENT DAMAGE TO EXISTING UTILITY DISTRIBUTION
- 10. EXISTING CONSTRUCTION MUST BE REMOVED TO NEAREST JOINT. NEW CONSTRUCTION MUST BE PROVIDED AS SHOWN AND ANY DAMAGED AREA MUST BE REPAIRED TO MATCH CONDITIONS EXISTING PRIOR TO CONSTRUCTION.
- 11. THE CONTRACTOR MUST BE RESPONSIBLE FOR REPAIRS TO THE ADJACENT CURB, GUTTER, AND RIGHT-OF-WAY. IF DAMAGED DURING CONSTRUCTION ACTIVITY AS DETERMINED BY THE CITY.
- 12. TOPS OF EXISTING STRUCTURES WHICH REMAIN IN USE ARE TO BE ADJUSTED IN ACCORDANCE WITH THE GRADING PLAN. ALL PROPOSED STRUCTURE TOP ELEVATIONS ARE TO BE VERIFIED BY THE CONTRACTOR WITH THE SITE GRADING PLANS. IN CASE OF CONFLICT, THE GRADING PLAN MUST SUPERSEDE PROFILE ELEVATIONS. ADJUSTMENTS TO MEET FINISHED GRADE ELEVATIONS MAY BE REQUIRED.
- 13. THE CONTRACTOR MUST BACKFILL EXCAVATED AREAS WITH APPROVED MATERIALS AS PER THE CITY'S STANDARDS AND SPECIFICATIONS.
- 14. SMOOTH GRADE MUST BE MAINTAINED FROM THE CENTERLINE OF THE EXISTING ROAD TO THE PROPOSED ENTRANCE AND/OR CURB & GUTTER TO PRECLUDE THE FORMING OF FALSE GUTTER AND/OR THE PONDING OF WATER ON THE ROADWAY.
- 15. THE CONTRACTOR MUST ENSURE THAT POSITIVE DRAINAGE OCCURS ON SITE TO PREVENT PONDING OR DRAINAGE PROBLEMS ON ADJACENT PROPERTIES. NOTIFY THE CITY IF SITE CONDITIONS PREVENT POSITIVE DRAINAGE.
- 16. CONTRACTOR MUST ENSURE THAT THERE IS NO DISTURBANCE ON ADJACENT PROPERTIES, UNLESS OTHERWISE NOTED ON PLANS.
- 17. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN UTILITY SERVICES AT ALL TIMES DURING CONNECTION AND/OR CONSTRUCTION.
- 18. THE CONTRACTOR IS RESPONSIBLE FOR ALL TRAFFIC CONTROL DURING CONSTRUCTION INCLUDING THE DEVELOPMENT OF TRAFFIC CONTROL PLANS. ALL TRAFFIC CONTROL COSTS FOR ALL STAGES MUST BE INCLUDED IN THE BID PRICE FOR "MAINTENANCE OF TRAFFIC (LS)."
- 19. THE CONTRACTOR MUST FURNISH ALL LABOR. MATERIALS. AND EQUIPMENT NECESSARY FOR THE CONSTRUCTION OF THE WORK.

#### FIELD QUALITY CONTROL

1.1. CONCRETE MATERIAL, MIXTURES, FORM WORK, COMPACTION REQUIREMENTS, INSTALLATION TOLERANCES AND JOINT MATERIAL SHALL CONFORM WITH VIRGINIA DEPARTMENT OF TRANSPORTATION, ROAD AND BRIDGE SPECIFICATIONS, 2016.

#### 2. ASPHALT WORK

- 2.1. ASPHALT PAVING SHALL COMPLY WITH MATERIALS, WORKMANSHIP, COMPACTION REQUIREMENTS, INSTALLATION TOLERANCES AND OTHER APPLICABLE REQUIREMENTS OF VIRGINIA DEPARTMENT OF TRANSPORTATION, ROAD AND BRIDGE SPECIFICATIONS, 2016.
- 2.2. FOR ALL ASPHALT PAVING, CONTRACTOR SHALL: A. ENGAGE A QUALIFIED TESTING AGENCY TO PERFORM TESTS AND INSPECTIONS B. REPLACE AND COMPACT HOT-MIX ASPHALT WHERE CORE TESTS WERE TAKEN C. REMOVE AND REPLACE OR INSTALL ADDITIONAL HOT-MIX ASPHALT WHERE TEST RESULTS OR MEASUREMENTS INDICATE THAT IT DOES NOT COMPLY WITH SPECIFIED REQUIREMENTS

#### 3. EARTHWORK

- 3.1. EXCAVATIONS, GRADING, BORROW MATERIALS, SUBBASE AND BASE MATERIAL, COMPACTION REQUIREMENTS SHALL CONFORM WITH VIRGINIA DEPARTMENT OF TRANSPORTATION. ROAD AND BRIDGE SPECIFICATIONS, 2016.
- 3.2. REMOVE ALL SURPLUS SOIL AND WASTE MATERIAL INCLUDING TRASH AND DEBRIS AND LEGALLY DISPOSE OF IT OFF PROJECT SITE.

#### LANDSCAPE PLANTING NOTES

- 1. ALL LANDSCAPE RELATED WORK SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE CURRENT AND MOST UP-TO-DATE EDITION (AT TIME OF CONSTRUCTION) OF THE CITY OF ALEXANDRIA LANDSCAPE GUIDELINES, ANSI Z60.1-2014 AMERICAN STANDARD FOR NURSERY STOCK, AND LANDSCAPE SPECIFICATION GUIDELINES (6TH EDITION - 2014) AS PRODUCED BY THE LANDSCAPE CONTRACTORS ASSOCIATION OF MARYLAND, VIRGINIA, DISTRICT OF COLUMBIA AND VIRGINIA.
- 2. PLANTING AREA SHALL BE FREE FROM DEBRIS, STONES, GRAVEL, OR OTHER FOREIGN MATTER PRIOR TO PLANTING, SEEDING, OR SODDING.

### LANDSCAPE SPECIFICATION AND INSTALLATION

#### 1. SEED

- 1.1. PROCURE FROM NEW OF THE YEAR SEED CROPS, FREE OF FOREIGN MATERIAL OR WEED SEEDS.
- 1.2. FURNISH AND INSTALL PERMANENT SEEDING IN CONFORMANCE WITH THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK; SPECIFICATION 3.32- PERMANENT SEEDING (VESCH-PS).
- 1.3. PREPARE PLANTING AREA PER VESCH AND BY RAKING OUT AND REMOVING ALL DEBRIS OVER 1" IN
- 1.4. PREPARE PLANTING AREA WITH SOIL CONDITIONER, TOPSOIL, AND/OR LIME, AS PER THE RECOMMENDATIONS OF A SOIL TEST CONDUCTED FOR HORTICULTURAL/LANDSCAPE PLANTING PER VESCH.
- 1.5. PACK OR ROLL SEED BEFORE AND AFTER SEEDING. SEEDBED SHOULD BE FIRM, SHOWING ONLY A SLIGHT IMPRINT WHEN STEPPED ON.
- 1.6. REPLACEMENT OR OVERSEEDING MIXES SHALL MATCH OR COMPLIMENT ORIGINAL INSTALLATION/EXISTING CONDITIONS SPECIFIED TO REMAIN.
- 1.7. PROVIDE CONTINUOUS UNIFORM AND CONSISTENT COVERAGE

#### 2. TOPSOIL

- 2.1. SEE LANDSCAPE SPECIFICATION GUIDELINES REFERENCED IN PAGE 1 OF CITY OF ALEXANDRIA LANDSCAPE
- 2.2. SUITABLE TOPSOIL SHALL BE STRIPPED FROM EXCAVATIONS AND STOCKPILED FOR REUSE.
- 2.3. THE CONTRACTOR SHALL SUPPLY ANY ADDITIONAL MATERIAL AS REQUIRED. THIS SOIL SHALL BE FRIABLE LOAM, AND SHALL BE OBTAINED FROM NATURALLY WELL-DRAINED AREAS. IT SHALL BE FREE FROM SUBSOIL, CLAY LUMPS, STONES, STUMPS, ROOTS, BRUSH, WEEDS, LITTER, TRASH OR OTHER HARMFUL

### SIGNING AND PAVEMENT MARKING

- 1. ALL SIGN WORK AND PAVEMENT MARKING SHALL MEET ALL THE LASTEST APPLICABLE VDOT. CITY OF ALEXANDRIA STANDARDS. AND MANUAL ON UNIFORM TRAFFIC CONTROL (MUTCD) REQUIREMENTS.
- 2. ALL PAVEMENT MARKINGS ARE THERMOPLASTIC UNLESS OTHERWISE NOTED.
- ALL EXISTING PAVEMENT MARKINGS MAY NOT BE SHOWN. ALL EXISTING PAVEMENT MARKINGS THAT CONFLICT WITH PROPOSED PAVEMENT MARKINGS SHALL BE ERADICATED.
- 4. ALL SIGNS SHALL BE HIGH INTENSITY SHEETING MEETING THE REQUIREMENTS OF AASHTO M268.
- 5. NO PORTION OF PROPOSED SIGN PANEL SHALL OVERHANG ADJACENT ROADWAY PAVEMENT. I.E. SHALL NOT HANG IN FRONT OF FACE OF CURB.
- 6. PROPOSED SIGN POSTS SHALL BE LOCATED A MINIMUM OF 2 FEET BEHIND ANY ADJACENT FACE OF CURB (ADDITIONAL REQUIREMENTS APPLY TO ACCOMMODATE SIGN PANEL LATERAL AND VERTICAL CLEARANCE). IF LOCATED ADJACENT TO SIDEWALKS, A 32" MINIMUM CLEAR AND 48" PREFERRED PASSING SPACE ON EXISTING AND PROPOSED SIDEWALKS SHALL BE MAINTAINED.
- 7. PROPOSED SIGN POSTS SHALL BE INSTALLED IN NEW LOCATIONS SUCH THAT THE EXISTING SIGNS OR SIGNALS ARE NOT BLOCKED.
- 8. FOR NEW POST INSTALLATION, THE CONTRACTOR SHALL VERIFY THERE ARE NO CONFLICTING UNDERGROUND OR OVERHEAD UTILITIES.
- 9. SIGNS MOUNTED TO EXISTING LIGHT, SIGNAL OR UTILITY POLES SHALL BE FASTENED WITH A MANUFACTURED STEEL BANDING SYSTEM. POLES SHALL NOT BE DRILLED DIRECTLY, THE CONTRACTOR SHALL SUBMIT MANUFACTURER INFORMATION ON THE BANDING SYSTEM TO THE CITY FOR APPROVAL PRIOR TO INSTALLATION.

### **ABBREVIATIONS**

AREA

 IMPERVIOUS AREA APPROXIMATE CLEANOUT

COMMUNICATIONS

CONCRETE CONCRETE MASONRY UNIT

CRITICAL ROOT ZONE

 COMBINED SEWER OVERFLOW DRAINAGE AREA

DIAMETER AT BREAST HEIGHT

EASTING

ELEVATION

EXISTING FIRE HYDRANT

FLOW LINE

GRADE BREAK POINT

HIGH POINT

INLET PROTECTION

LIMITS OF DISTURBANCE

LIGHT MANHOLE

NORTHING NORTH AMERICAN DATUM

NOMINAL PIPE SIZE

POINT OF CURVATURE

 POINT OF TANGENCY PEDESTRIAN PROVIDE

PROPOSED RIGHT OF WAY

 SANDBAG BARRIER SANITARY SEWER

 STORM SEWER STRUCTURAL CRITICAL ROOT ZONE

TRAFFIC

TIME OF CONCENTRATION

 TOP OF CURB TOP OF CURB

TYPICAL TOP OF WALL


BOTTOM OF WALL

 UNLESS NOTED OTHERWISE VIRGINIA COORDINATE SYSTEM

WATERLINE WATER VALVE

CROSSING DEED BOOK

PAGE



SIGN

00

ATION <u>GIN</u>

MEN 9 CI

4/18/2023 0

MURPHY M. NG

GENER,

G1002

SHEET  $\triangleleft$ 02 of 10

KNOW WHAT'S BELOW. CALL BEFORE YOU DIG. DIAL 811 IN VIRGINIA OR 1-800-552-7001

AL

SID

SCALE

#### POLLUTION PREVENTION NOTES

- ALL SAW CUTTING AND DEMOLITION MUST INCLUDE WATER FOR DUST SUPPRESSION. INLETS MUST BE PROTECTED AND SLURRY MUST NOT ENTER THE STORM INLET. WASTE MATERIALS MUST BE COLLECTED USING DRY TECHNIQUES (SHOVEL, BROOM, ETC.) AND NOT WASHED DOWN THE INLETS.
- ENSURE THE STAGING/STORAGE/APPLICATION/CLEAN-UP OF GAS, CHEMICALS, AND OILS (INCLUDING FORM RELEASE OIL) IS SUCH AS TO PREVENT BEING WASHED DOWN THE INLETS.
- ENSURE DISCHARGE OF SOAPS, SOLVENTS, DETERGENTS, WASH WATER AND CONSTRUCTION MATERIALS, INCLUDING THE CLEAN-UP OF STUCCO, VEHICLE AND EQUIPMENT WASH WATER, PAINT, FORM RELEASE OILS AND CURING COMPOUNDS (COVER, PLASTIC SHEETING OR TEMPORARY ROOFS) AND PROVIDE COLLECTION AND PROPER DISPOSAL TO PREVENT CONTACT WITH STORMWATER.
- CONTRACTOR SHALL EXERCISE EFFORT TO PREVENT THE DISCHARGE OF FUELS, OILS AND OTHER PETROLEUM PRODUCTS, HAZARDOUS OR TOXIC WASTES, SANITARY WASTES, SPILLED AND LEAKED FUELS/CHEMICALS FROM VEHICLES AND EQUIPMENT (I.E. SPILL KITS, SPILL CONTAINMENT, ETC.).
- CONTRACTOR TO MINIMIZE THE DISCHARGE OF POLLUTANTS FROM STORAGE, HANDLING AND DISPOSAL OF CONSTRUCTION PRODUCTS; BUILDING PRODUCTS; PESTICIDES, HERBICIDES, INSECTICIDES, FERTILIZERS AND LANDSCAPE MATERIAL; AND DOMESTIC WASTES.
- CONTRACTOR TO PROVIDE PROPOSED LOCATION OF CONCRETE MIXING TO BE APPROVED BY THE CITY.
- CONTRACTOR TO DIRECT CONCRETE WASH WATER INTO A LEAK-PROOF CONTAINER OR LEAK-PROOF SETTLING BASIN, WITH HARDENED CONCRETE WASTES AND LIQUID CONCRETE WASTES PROPERLY DISPOSED OF AS CONSTRUCTION WASTES.
- 8. TO REPORT LEAKS, SPILLS AND OTHER RELEASES, CONTACT:


703-838-4660 FOR HAZARDOUS DISCHARGES FIRE DEPARTMENT 703-746-4065 FOR DISCHARGES TO STORM SEWER

DEQ NORTHERN VIRGINIA 703-583-3870 FOR PETROLEUM THAT REACHES SURFACE WATER REGIONAL OFFICE DURING NORMAL HOURS

VIRGINIA DEPARTMENT OF 1-800-468-8892 FOR PETROLEUM THAT REACHES SURFACE WATER EMERGENCY MANAGEMENT 24 HOUR

#### ARCHAEOLOGY NOTES

- THE CONTRACTOR SHALL CALL ALEXANDRIA ARCHAEOLOGY IMMEDIATELY (703-746-4399) IF ANY BURIED STRUCTURAL REMAINS (WALL FOUNDATIONS, WELLS, PRIVIES, CISTERNS, ETC.) OR CONCENTRATIONS OF ARTIFACTS ARE DISCOVERED DURING DEVELOPMENT. WORK MUST CEASE IN THE AREA OF THE DISCOVERY UNTIL A CITY ARCHAEOLOGIST COMES TO THE SITE AND RECORDS THE FINDS.
- THE CONTRACTOR SHALL NOT ALLOW ANY METAL DETECTION TO BE CONDUCTED ON THE PROPERTY, UNLESS AUTHORIZED BY ALEXANDRIA ARCHAEOLOGY.



## (SB) SANDBAG BARRIER

- 1. MAXIMUM TOP OF SPILLWAY ELEVATION = TOP OF CURB ELEVATION MINUS 1 INCH.
- 2. BAGS MUST BE MADE OF EITHER BURLAP OR GEOTEXTILE FABRIC AND FILLED WITH CLEAN MINERAL AGGREGATE (SIZE 57) OR SAND.
- 3. PACK SAND/GRAVEL FILLED BAGS TIGHTLY TOGETHER END-TO-END TO ENSURE NO SEDIMENT FLOWS BETWEEN OR UNDERNEATH BAGS. WHERE TIGHT FIT IS UNACHIEVABLE, INSTALL GEOTEXTILE FABRIC ALONG THE UPSTREAM FACE OF THE BAGS LAPPING OVER THE TOP BAGS 6 INCHES AND EXTENDING GEOTEXTILE FABRIC A MINIMUM OF 18 INCHES UPSTREAM OF THE BAGS. COVER GEOTEXTILE FABRIC WITH MINERAL AGGREGATE (SIZE 57) STONE WEDGE TO THE TOP OF THE BAGS.


## LEGEND INLET PROTECTION (P) SANDBAG BARRIER (SB) PROPERTY LINE (GIS) -----SANITARY SEWER (GIS) -STORM SEWER (GIS) DRAINAGE DIVIDES LIMITS OF DISTURBANCE ———LOD——


#### GENERAL EROSION AND SEDIMENT CONTROL NOTES

- 1. ALL EROSION AND SEDIMENT CONTROL MEASURE ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING. AN INSPECTION BY THE CITY OF ALEXANDRIA IS REQUIRED AFTER INITIAL INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND BEFORE ANY CLEARING OR GRADING CAN BEGIN.
- THE CONTRACTORS ARE TO KEEP DENUDED AREAS TO A MINIMUM.
- THE CITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENTS OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION. CERTIFIED RESPONSIBLE LAND DISTURBER (CRLD) IS REQUIRED TO ATTEND PRE-CONSTRUCTION MEETING.
- 4. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN THOSE INDICATED ON THESE PLANS INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS, THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION CONTROL PLAN TO THE CITY FOR REVIEW AND APPROVAL.
- ALL DISTURBED AREAS OF THE SITE NOT TO BE WORKED FOR SEVEN OR MORE CALENDAR DAYS MUST BE STABILIZED.
- ALL TEMPORARY EARTH BERMS, DIVERSIONS AND SEDIMENT CONTROL DAMS SHALL BE SEEDED AND MULCHED OR OTHERWISE STABILIZED AS SOON AS POSSIBLE BUT NO LATER THAN 48 HOURS AFTER
- ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.
- DURING DEWATERING OPERATION, WATER WILL BE PUMPED THROUGH AND APPROVED FILTERING DEVICE.
- THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES DAILY AND AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.
- PERMANENT OR TEMPORARY SOIL STABILIZATION SHALL BE APPLIED TO DENUDED AREAS WITHIN SEVEN DAYS AFTER FINAL GRADE IS REACHED ON ANY PORTION OF THE SITE. TEMPORARY SOIL STABILIZATION SHALL BE APPLIED WITHIN SEVEN DAYS TO DENUDED AREAS THAT MAY NOT BE AT FINAL GRADE BUT WILL REMAIN DORMANT FOR LONGER THAN 30 DAYS. PERMANENT STABILIZATION SHALL BE APPLIED TO AREAS THAT ARE TO BE LEFT DORMANT FOR MORE THAN ONE YEAR.
- STOCKPILE BORROW SOIL MATERIALS AND EXCAVATED SATISFACTORY SOIL MATERIALS WITHOUT INTERMIXING. PLACE, GRADE, AND SHAPE STOCKPILES TO DRAIN SURFACE WATER AND COVER TO PREVENT WINDBLOWN DUST IN CONFORMANCE WITH VESCH, CHAPTER 3.
- 13. THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES AS NECESSARY TO PREVENT EROSION AND SEDIMENTATION AND AS DETERMINED BY THE CITY OF ALEXANDRIA.
- 14. PROVIDE TREE PROTECTION FENCING AS DIRECTED BY THE EROSION AND SEDIMENT CONTROL INSPECTOR.
- ANY DENUDED SLOPES, EITHER DISTURBED OR CREATED BY THIS PLAN THAT EXCEED 2500 SQUARE FEET SHALL BE SODDED AND PEGGED FOR STABILITY AND EROSION CONTROL. AT THE COMPLETION OF THE PROJECT, ALL DISTURBED AREAS SHALL BE STABILIZED PERMANENTLY AND ALL TEMPORARY EROSION AND SEDIMENT CONTROLS SHALL BE REMOVED.
- 16. SEE POLLUTION PREVENTION NOTES FOR ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES.


#### SEQUENCE OF CONSTRUCTION

- INSTALL EROSION AND SEDIMENT CONTROLS.
- CONDUCT DEMOLITION AND CONSTRUCTION ACTIVITIES ACCORDING TO THE APPLICABLE PLANS. INSTALL ADDITIONAL EROSION AND SEDIMENT CONTROL PRACTICES AS NECESSARY AND AS DIRECTED BY THE
- AS CONTRIBUTORY DRAINAGE AREAS ARE STABILIZED AND WITH THE PERMISSION OF THE EROSION AND SEDIMENT CONTROL INSPECTOR, REMOVE INDIVIDUAL EROSION AND SEDIMENT CONTROL PRACTICES. UPON COMPLETION OF DEMOLITION, CONSTRUCTION AND LAND DISTURBING ACTIVITIES AND WITH THE APPROVAL OF THE EROSION AND SEDIMENT CONTROL INSPECTOR; REMOVE ALL REMAINING EROSION AND SEDIMENT CONTROL PRACTICES AND PROVIDE PERMANENT STABILIZATION ACCORDING TO APPROVED METHODS.
- CONSTRUCTION DEBRIS MUST BE REMOVED TO AN APPROVED LANDFILL WITH ADEQUATE FREQUENCY IN ACCORDANCE WITH THE VIRGINIA STATE LITTER CONTROL ACT.









DE 0

> ATION VIRGINI,

2

4/18/2023


EROSION AND SEDIMENT CONTRC PLAN


SIDEWALK


GC101

SHEET

03 of 10 SCALE 1"=30'









KNOW WHAT'S BELOW. CALL BEFORE YOU DIG.

DIAL 811 IN VIRGINIA OR

1-800-552-7001






MURPHY M. NG 4/18/2023 DE SITE SIDI VENUE CS501 SHEET  $\triangleleft$ 

07 of 10

SCALE AS SHOWN



DEQ Virginia Runoff Reduction Method Re-Development Compliance Spreadsheet - Version 3.0

#### SITE DRAINAGE ANALYSIS

THE EXISTING DRAINAGE DIVIDES WILL BE MAINTAINED IN THE PROPOSED CONDITIONS. RUNOFF FROM THE SITE PRIMARILY FLOWS FROM THE NORTHERN WOODED PARK AREA ONTO POLK AVENUE, WITH A SMALL PORTION TRAVELING WEST AND THE MAJORITY TRAVELING EAST ON POLK AVENUE. RUNOFF FROM THE WEST TRAVELS ONTO THE EXISTING CURB AND GUTTER WHICH LEADS TO A CURB INLET ON N PELLHAM ST APPROXIMATELY 600 FT SOUTH OF THE PROJECT SITE. THE PROPOSED IMPROVEMENTS WILL NOT INCREASE RUNOFF TO THIS AREA SINCE THE AMOUNT OF IMPERVIOUS SURFACE WILL REMAIN THE SAME IN THE POST-DEVELOPMENT CONDITION. RUNOFF FROM THE EAST SHEET FLOWS ACROSS POLK AVENUE AND INTO A CURB INLET ON PALMER PL. THE PROPOSED IMPROVEMENTS FOR THE EAST DRAINAGE AREA INCLUDES THE CONSTRUCTION OF APPROXIMATELY 190 LF OF UNDERDRAIN WITH #57 STONE AGGREGATE TO ALLOW PORTIONS OF THE RUNOFF TO BE STORED AND DISCHARGED AT A SLOWER RATE BACK ONTO POLK AVENUE. THE #57 STONE AGGREGATE FACILITY (STONE RESERVOIR) IS SIZED TO PROVIDE ENOUGH STORAGE SUCH THAT THE POST-DEVELOPMENT COMPOSITE CN NUMBER IS LESS THAN THE PRE-DEVELOPMENT COMPOSITE CN NUMBER. THEREFORE, THE POST-DEVELOPMENT PEAK RUNOFF RATE COMPARED TO THE PRE-DEVELOPMENT PEAK RUNOFF RATE FOR A TWO-YEAR AND TEN-YEAR STORM WILL RESULT IN NO NET INCREASE. IT IS THE OPINION OF THE ENGINEER THAT THIS PROJECT WILL NOT HAVE AN ADVERSE EFFECT NOR CAUSE FLOODING OF ANY DOWNSTREAM PROPERTY OR STRUCTURES

SIGN 00

'ATION **VIRGINIA** ANDRI, R

IMEN CI.

MURPHY M. NG 4/18/2023

TOTAL D.A. TO INLET

 $CN_{COMPOSITE}$  (PRE<sub>2YR</sub>) =84.32

 $CN_{COMPOSITE}$  (POST<sub>2YR</sub>) =83.72

 $CN_{COMPOSITE}$  (PRE<sub>10YR</sub>) =84.32

CN<sub>COMPOSITE</sub> (POST<sub>10YR</sub>) =83.97

KNOW WHAT'S BELOW.

CALL BEFORE YOU DIG.

DIAL 811 IN VIRGINIA OR

<u>1-800-552-7001</u>

 $A_{TOTAL} = 39,680 \text{ SF}$ 

 $T_C = 11 MIN.$ 

ALMER

STORMWATI MANAGEMENT

WAL

SIDI

VENU

 $\triangleleft$ 

CG701

SHEET

09 of 10 SCALE 1"=30'



# DEPARTMENT OF TRANSPORTATION AND ENVIRONMENTAL SERVICES Infrastructure and Environmental Quality

2900B Business Center Dr. Alexandria, Virginia 22314 www.alexandriava.gov

DATE 03/16/2023

Gavin Pellitteri T&ES Stormwater Management 2900 Business Center Dr Alexandria VA, 22314

RE: CIP2022-00015 - Polk Avenue Sidewalk

Dear Mr. Pellitteri:

Department of Project Implementation is requesting to meet the Virginia Stormwater Phosphorus Removal Requirements, specified in the Environmental Management Ordinance (Article XIII of the City's zoning ordinance) through use of the City's Internal Phosphorous Exchange Bank. The installation of a structural BMP was not feasible on this project due to site constraints.

I am requesting to purchase 0.05 lbs, of Phosphorus Credits in the amount of \$2,500. The purchased credits will be used to meet the Phosphorus Removal Requirements for the Polk Avenue Sidewalk project. 51411829 account will be used to purchase the credits. This letter confirms that funds are available in the budget as written.

Sincerely,

Murphy Ng, P.E.
Associate Project Manager
City of Alexandria, Virginia
Department of Project Implementation



### DEPARTMENT OF TRANSPORTATION AND ENVIRONMENTAL SERVICES

Infrastructure and Environmental Quality 2900B Business Center Drive Alexandria, Virginia 22314 www.alexandriava.gov

03/21/2023

Murphy Ng, PE Associate Project Manager City of Alexandria, Virginia Department of Project Implementation 703.746.4699 (Direct)

RE: CIP2022-00015 - 5325 Polk Avenue Alexandria VA 22304

Dear Mr. Ng:

This is in regard to your letter dated 03/16/2023 requesting to meet the State Water Quality Phosphorous Removal requirements by utilizing the City's Internal Phosphorous Exchange Bank. You have requested to withdraw .05 pounds of credits from the bank and deposit \$2500 into the bank. This represents 100 percent of the overall phosphorous removal requirements.

Your request has been approved. The procedure now is to scan your request letter onto your final plan on a sheet that is labeled Stormwater Facility BMP Details or something similar. Your final plan will be eligible for approval when you have paid the fee \$2500. The approval of the plan (with your request therein) will act as the approval of your request.

Sincerely,



Gavin Pellitteri Water Quality Compliance Specialist T&ES Stormwater Management POLK AVENUE SIDEWALK

100%

CG702

4/18/2023

STORMWATER MANAGEMENT COMPLIANCE

SHEET
10 of 10

NA

SCALE