

Madison, Wisconsin

INDEX OF SHEETS - STREETS


	4	
SHEET NO.	1	TITLE
SHEET NO.	D1– $D2$	NOTES AND DETAILS
SHEET NO.	P1–P4	PLAN & PROFILE
SHEET NO.	<i>U1–U3</i>	UTILITY PLAN & PROFILE
SHEET NO.	U– SAN	SANITARY SEWER SCHEDULE
SHEET NO.	U– STM	STORM SEWER SCHEDULE
SHEET NO.	WI-W3	WATER PLAN & PROFILE
SHEET NO.	W4	WATER PLAN OVERVIEW
SHEET NO.	W5	WATER ESTIMATE OF MATERIALS

CITY OF MADISON

CITY ENGINEERING DIVISION DEPARTMENT OF PUBLIC WORKS PLAN OF PROPOSED IMPROVEMENT

VILLAGE AT AUTUMN LAKE - PHASE 9

MUNIS NO. 12522 CITY PROJECT NO. 12522 CITY CONTRACT NO. 8342







PUBLIC IMPROVEMENT PROJECT APPROVED


MARCH 1, 2019


BY THE COMMON COUNCIL OF MADISON, WISCONSIN

PUBLIC IMPROVEMENT DESIGN APPROVED BY:









NO TREES IN THE RIGHT OF WAY OR ON PUBLIC LANDS SHALL BE TRIMMED, PRUNED, REMOVED OR ADVERSELY AFFECTED IN ANY WAY UNTIL THE DEVELOPER HAS RECEIVED WRITTEN PERMISSION FROM THE CITY ENGINEER OR CITY FORESTER. SAID WRITTEN PERMISSION SHALL INCLUDE LANGUAGE INDICATING THAT SECTION 10.101 OF THE MADISON GENERAL ORDINANCES AND ADMINISTRATIVE PROCEDURE MEMORANDUM NO. 6–2, REFERING TO NOTIFICATION OF PROPERTY OCCUPANTS AND/OR OWNERS, HAS BEEN COMPLIED WITH.

CONTRACTORDEVELOPER SHALL SUBMIT A TRAFFIC CONTROL PLAN TO CITY TRAFFIC ENGINEERING AT LEAST 10 WORKING DAYS PRIOR TO THE START OF WORK. WORK WITHIN THE RIGHT-OF-WAY SHALL NOT BEGIN UNTIL THE TRAFFIC CONTROL PLAN IS APPROVED.

CONVENTIONAL	SIGNS
FIELD VERIFY ALL UTIL	ITY LOCATIONS
GAS	— с —
STORM SEWER	st
SANITARY SEWER	SAN
WATER	—— w ——
OVERHEAD ELECTRIC	—— ОН ——
POWER POLE	φ
ADA COMPLIANT RAMP DETECTABLE WARNING	'''
COMBUSTIBLE FLUIDS	-CAPTIONS

ALL PAVEMENT IN THE LEVITAN LANE AND WATERFALL WAY RIGHTS-OF-WAY SHALL BE TYPE A PAVEMENT PER STANDARD DETAIL DRAWING 4.02.

UNDERDRAINS SHALL BE INSTALLED, PER STANDARD DETAIL DRAWING 4.05 FOR 75'ON EACH SIDE OF THE LOW POINT, OR TO THE NEAREST CURB HIGH POINT. ALL UNDERDRAIN SHALL BE WRAPPED.

ALL GUTTERS SHALL DRAIN WITH A MINIMUM GRADES OF 0.5% TOWARD STORM SEWER INLETS.

ALL DITCHES SHALL DRAIN WITH A MINIMUM GRADES OF 0.5%

THE CROSS SLOPE OF SIDEWALKS AND BARRIER FREE SIDEWALK CURB
RAMPS SHALL TYPICALLY BE 1.5%. THE LONGITUDINAL GRADE OF BARRIER
FREE SIDEWALK CURB RAMPS SHALL NOT EXCEED 8.33%. ALL SIDEWALK
RAMPS SHALL BE CONSTRUCTED ACCORDING TO S.D.D. 3.03. AT ALL
OTHER LOCATIONS THE LONGITUDINAL GRADE OF SIDEWALKS SHALL
NOT EXCEED 5.0 % OR THE ADJACENT STREET GRADE WHICHEVER
IS GREATER NOR BE LESS THAN 0.5% AND SHALL DRAIN TOWARD
STORM SEWER INLETS. SIDE SLOPES WITHIN TEN FEET OF A PUBLIC
SIDEWALK SHALL NOT EXCEED 4.00:1. ALL SIDEWALK AND SIDEWALK RAMP
ELEVATIONS AND GRADES SHALL BE FIELD VERIFIED AND SET TO COMPLY WITH
THE CITY OF MADISON STANDARD SPECIFICATIONS AND THE A.D.A. GUIDELINES.

OBTAIN A PRINT OUT OF THE ALIGNMENT FROM THE CITY ENGINEER PRIOR TO STAKING THIS PROJECT.

CURB STATION AND OFFSETS SHALL BE TO THE FACE OF CURB UNLESS OTHERWISE INDICATED. CURB ELEVATIONS SHALL BE TO THE TOP OF CURB (OR EXTENDED TOP OF CURB FOR DRIVEWAYS OR RAMPS) UNLESS OTHERWISE INDICATED.

POWER POLES AND OTHER OBSTRUCTIONS SHALL BE MOVED TO PROVIDE 2 FEET MINIMUM OF CLEAR DISTANCE FROM ANY FACE OF CURB OR EDGE OF SIDEWALK.

ANY INFORMATION SHOWN ON THIS PLAN, WHICH IS NOT PART OF THIS PROJECT, IS PRELIMINARY AND NOT FOR CONSTRUCTION.

THERE MAY BE EXISTING UTILITIES OR OTHER FEATURES WHICH ARE EITHER NOT SHOWN OR SHOWN INCORRECTLY ON THIS PLAN. IT IS THE RESPONSIBILITY OF THE DEVELOPER TO LOCATE AND IDENTIFY ALL UTILITIES AND TOPOGRAPHY WHICH MAY AFFECT THE CONSTRUCTION OF THESE IMPROVEMENTS.

ALL PERMANENT SIGNING AND POSTING WILL BE DETERMINED AND PROVIDED BY THE TRAFFIC ENGINEERING DIVISION, FOLLOWING CONSTRUCTION OF THESE IMPROVEMENTS.

THE DEVELOPER SHALL PROVIDE, INSTALL AND MAINTAIN ALL STREET END BARRICADES, SIGNING AND TRAFFIC CONTROL, AS REQUIRED BY THE CITY TRAFFIC ENGINEER.

PAVEMENT SAWCUTS SHALL BE AS DIRECTED BY THE CITY CONSTRUCTION ENGINEER. SAWCUTS SHOWN ON THE PLAN ARE APPROXIMATE.

CURB ON CUL DE SACS SHALL BE INSTALLED ACCORDING TO SDD 3.05.

VILLAGE AT AUTUMN LAKE: PHASE 9 PROJECT NO. 12522

SHEET NO. D-1

DETAIL

STANDARD NOTES AND COMMENTS


CITY OF MADISON


PLOT SO

PLOT NAME

EV. DATE:

R: CITY OF MADISON, STREETS DIVISION





TYPICAL SECTION

WATERFALL WAY
NOT TO SCALE

[†]CITY OF MADISON MINIMUM PAVEMENT DESIGN


		CRUSHED AGGREG	SATE BASE COURSE	ASPHALTIC CONCRETE PAVEMENT								
TYPE		LOWER LAYER	UPPER LAYER	LOWER	LAYER	UPPER LAYER						
		GRADATION 1	GRADATION 2	TYPE	THICKNESS	TYPE	THICKNESS					
	Α	6"	6"	4 LT 58-28 S	1.75"	4 LT 58-28 S	1.75"					
	В	6"	6"	3 LT 58-28 S	2.50"	4 LT 58-28 S	2.00"					
	\subset	6"	6"	3 MT 58-28 S/H	3.50"	4 MT 58-28 S/H	2.00"					
L		0	0	3 HT 58-28 H	3.30	4 HT 58-28 H	2.00					


NOTES


* LEVITAN LN AND WATERFALL WAY TO BE CONSTRUCTED AS TYPE 'A' PAVEMENT;
PER CITY OF MADISON MINIMUM PAVEMENT DESIGN †


FILE NAME: M;\DESIGN\Projects\12522\Microstation\Streets\Design\12522EN-D2_TypSection.dgn


DATE: 7/11/2019

















SANITARY SEWER SCHEDULE

VILLAGE AT AUTUMN LAKE PHASE 9
PROJECT NO. 12522

SHEET NO. U-SAN

SANITARY SEWER SCHEDULE

CITY OF MADISON

PROPOSED SANITARY STRUCTURES							PROPOSED								
SAS NO.	STATION	LOCATION (OFFSET)	TOP OF CASTING	E.I.	DEPTH	NOTES	FROM (DNSTM)	TO (UPSTM)	DWNSTR E.I.	M UPSTRM E.I.	PLAN LGTH (FT)	SLOPE (%)	PIPE SIZE	PVC TYPE	NOTES
WATERFA	LL WAY														
SAS#1	12+86.31	RT-2.35	907.29	896.79	10.50	-	EX SAS	SAS#1	887.86	896.79	161	5.55%	8"	SDR-35	-
SAS#2	13+83.78	RT-2.00	910.14	898.88	11.26	-	SAS#1	SAS#2	896.89	898.88	97	2.05%	8"	SDR-35	-
SAS#3	17+25.00	CL	910.83	900.52	10.31	-	SAS#2	SAS#3	898.98	900.52	341	0.45%	8"	SDR-35	-

STORM	SEWER	SCHEDUL	F
		1	_

VILLAGE AT AUTUMN LAKE PHASE 9 PROJECT NO. 12522 SHEET NO. U-STM

STORM SEWER SCHEDULE

CITY OF MADISON

PROPOSE STRUC. NO.	ED STORM STRU STATION	CTURES LOCATION (OFFSET)	TYPE	TOP OF CASTING		DEPTH	NOTES	PROPOSE PIPE NO.	FROM (DNSTM)	TO (UPSTM)	DISCH. E.I.	INLET E.I.	PLAN (PAY) LGTH (FT)	PIPE LGTH (FT)	SLOPE (%)	PIPE SIZE	TYPE	NOTES
WATERFALL WAY																		
S-1	17+81.54	LT-13.50	12" RCP AE	-	905.00	-	-	P-1	S-1	S-2	905.00	907.07	229	228	0.91%	12"	RCP	-
S-2	15+52.33	LT-13.50	H INLET	910.39	907.07	3.32	W/ R-3067-7004-VB	P-2	S-2	S-3	907.07	907.23	27	25	0.64%	12"	RCP	-
S-3	15+52.33	RT-13.50	H INLET	910.39	907.23	3.16	LP; W/ R-3067-7004-VB; (1)											

NOTE: PLAN LENGTH (PAY LENGTH) IS FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE. PIPE LENGTH IS ACTUAL LENGTH OF PIPE FROM STRUCTURE WALL TO STRUCTURE WALL. SLOPE CALCULATED USING PIPE LENGTH.

SPECIFIC NOTES


(1) INSTALL LOW POINT PVC DRAIN PER S.D.D 5.7.7A


STANDARD NOTES:


- ABBREVIATIONS: AE = APRON ENDWALL; RCP = REINFORCED CONCRETE PIPE; HERCP = HORIZONTAL ELLIPTICAL REINFORCED CONCRETE PIPE; DNA = DOES NOT APPLY; SAS = SEWER ACCESS STRUCTURE; LP = LOW POINT INLET STRUCTURE; FP = FIELD POURED STRUCTURE; TR = TOP OF CONCRETE ROOF; NCM = NO CROWN MATCH FOR PIPES; UD = UNDERDRAIN

- APPROXIMATE DISCHARGE E.I. GIVEN, ADJUST E.I. AND PIPE SLOPE IN THE FIELD.
- TOP OF CASTING GRADE GIVEN IS THE TOP OF CURB FOR INLET STRUCTURES AND THE FLOWLINE OF THE CLOSED CASTING FOR SAS's.
- TOP OF CONCRETE ROOF (TR) IS 1.25' BELOW TOP OF CASTING UNLESS OTHERWISE NOTED.
- ALL REINFORCED CONCRETE PIPES TO BE CLASS III UNLESS OTHERWISE NOTED.
- SURVEYOR TO CONFIRM THAT ALL INLET STATION / OFFSETS LINE UP WITH PROPOSED CURB AND GUTTER.

- ALL STRUCTURES CALLED OUT AS FIELD POURED SHALL BE FIELD POURED. ALL OTHER STRUCTURES (NOT INDICATED AS FIELD POURED) SHALL BE SUBMITTED TO CITY ENGINEERING FOR APPROVAL IF PRECAST STRUCTURES ARE PREFERRED. CONTACT ELIA E. ACOSTA OF CITY ENGINEERING AT (608) 266-4096 FOR PRECAST APPROVALS, FAX SHOP DRAWINGS TO (608) 264-9275, OR EMAIL SHOP DRAWINGS TO EACOSTA@CITYOFMADISON.COM.









- CONSTRUCT NEW WATER MAIN 6.0' BELOW FINISHED GRADE, UNLESS OTHERWISE NOTED. INSULATE MAIN WITH POLYSTYRENE BOARD AT UTILITY CROSSINGS OR OTHER AREAS IDENTIFIED BY ENGINEER AS HAVING INADEQUATE COVER.
- VERIFY SIZE OF EXISTING
 WATER SERVICES AND RECONNECT SERVICES
 AS INDICATED.
- 3. MINIMIZE DISRUPTION OF SERVICE TO EXISTING CUSTOMERS. NOTIFY PER CONTRACT REQUIREMENTS OF ANY PLANNED WATER OUTAGE.
- 4. THE EXISTING UTILITIES SHOWN ON THIS PLAN REPRESENT THE BEST INFORMATION AVAILABLE TO THE WATER UTILITY AT THE TIME OF PLAN PREPARATION. CONTRACTOR IS RESPONSIBLE FOR HAVING EACH UTILITY LOCATED PRIOR TO COMMENCING WORK.

WN1 REPLACE THE EXISTING LEAD SERVICE WITH A NEW COPPER SERVICE.

WN2 EXTEND AND RECONNECT THE EXISTING COPPER SERVICE TO THE NEW WATER MAIN.

WN3 EXISTING SERVICE TO BE ABANDONED WHEN THE WATER MAIN IS CUT OFF.

WN4 DISCONNECT FROM THE OLD WATER MAIN AND RECONNECT THE EXISTING COPPER WATER SERVICE LATERAL TO THE NEW WATER MAIN.

WN5 RELOCATE THE EXISTING FIRE HYDRANT.

WN6 ABANDON WATER VALVE ACCESS STRUCTURE.

WN7 FURNISH AND INSTALL THE NEW TOP SECTION FOR THE WATER ACCESS STRUCTURE.

WN8 ABANDON THE VALVE BOX.

WN9 FURNISH THE DITCH, COMPACTION, AND ALL MATERIALS AND LABOR FOR THE INSTALLATION OF NEW SERVICE LATERAL.

WN10 REMOVE AND SALVAGE EXISTING HYDRANT

WN11 REPLACE THE EXISTING COPPER SERVICE WITH A COPPER SERVICE

WN20+ SEE WATER IMPACT PLAN FOR CONNECTION POINT ISOLATION AND WATER SHUT-OFF NOTFICATION INFORMATION.

VILLAGE AT AUTUMN LAKE- PHASE 9 PROJECT NO. 12522 SHEET NO. W-5

WATER ESTIMATE OF MATERIALS

DETAIL DRAWING NO. 7.04

VILLAGE AT AUTUMN LAKE- PH 9 CITY OF MADISON

ESTIMATE OF MATERIALS SUPPLIED BY CONTRACTOR:

* ESTIMATE OF MATERIALS IS FOR INFORMATION ONLY. ENGINEER DOES NOT GUARANTEE ACCURACY OF MATERIAL TAKE-OFF.

20-FT - 6-IN PIPE

1 - 8-IN 11.25° BEND 2 - 8-IN 22.5° BEND

1- 6-IN VALVE & BOX

1 - 8-IN MJ PLUG

2 - 8-IN VALVE & BOX

8-FT - 2-IN STYROFOAM INSULATION

2 - 8-IN X 6-IN TEE 1 - 8-IN X 8-IN TEE

930-FT - POLY WRAP

1-IN TO 2-IN COPPER (AS REQ'D)

FACILITIES BEFORE YOU
DIG IN WISCONSIN
CALL DIGGERS HOTLINE

TO OBTAIN LOCATION OF

PARTICIPANTS' UNDERGROUND

TOLL FREE

811 OR 1-800-242-8511

FAX-A-LOCATE 1-800-338-3860

TDD (FOR HEARING IMPAIRED) 1-800-542-2289

WIS. STATUTE 182.0175 (1974) REQUIRES MIN. OF 3 WORK DAYS NOTICE BEFORE YOU EXCAVATE.



DISCLAIMER NOTE:
UTILITY LOCATIONS SHOWN ARE APPROXIMATE
ONLY. IT SHALL BE THE CONTRACTOR'S
RESPONSIBILITY TO DETERMINE THE EXACT
HORIZONTAL AND VERTICAL LOCATION OF ALL
EXISTING UNDERGROUND AND OVERHEAD
UTILITIES PRIOR TO COMMENCING WORK.

REVISED: 12/2017 RoDon HIGH-VISIBILITY LOCATING DEVICE W/ A BOLT-ON FLAT STEEL MOUNTING BRACKET. MIN. 2.5 FT. OR AS REQUIRED BY DRAWINGS OR FIELD CONDITIONS STANDARD 5 FT. LENGTH. BURY LINE ON HYDRANT SHALL BE AT FINISHED GRADE OR WITHIN +3 INCHES. DO NOT DISH OUT OR BUILD UP GRADE FOR MORE DETAILS GO TO RoDonCorp.com AROUND HYDRANT TO MEET REQUIREMENTS 0 1/2-IN EXPANSION JOINT FILLER WHEN IN CONCRETE VALVE BOX 1/4 INCH - 1/2 INCH BELOW FINAL GRADE CURB & GUTTER PAVEMENT--4 FT. X 4 FT. MIN. SIZE, 6 MIL POLYETHYLENE FILM OR GEOTEXTILE FABRIC. 6 FT (MIN.) 6-IN VALVE & BOX 1-IN WASHED STONE HYDRANT LEAD (* MEGALUGS (TYF POURED CONCRETE OR SOLID CONCRETE MASONRY BLOCK SOLID CONCRETE BLOCK TO UNDISTURBED SOIL (*) RESTRAIN ENTIRE LENGTH OF HYDRANT LEAD FROM THE TEE THROUGH THE VALVE TO THE HYDRANT AS SPECIFIED USING JOINT RESTRAINTS SOLID CONCRETE MASONRY BLOCK CITY OF MADISON TYPICAL HYDRANT INSTALLATION NOT TO SCALE WATER UTILITY

City of Madison Standard Specifications for Public Works Construction

PART VII - WATER MAINS AND SERVICE LATERALS

MATERIALS SUPPLIED BY CITY:

ESTIMATE OF MATERIALS IS FOR INFORMATION ONLY. ENGINEER DOES NOT GUARANTEE ACCURACY OF MATERIAL TAKE-OFF.

NONE

ESTIMATE OF MATERIALS REUSED:

* ESTIMATE OF MATERIALS IS FOR INFORMATION ONLY. ENGINEER DOES NOT GUARANTEE ACCURACY OF MATERIAL TAKE-OFF.

2 - 5-IN HYDRANT

RIGINATOR: CITY OF